REVISION NOTES		
#	DATE/BY	NOTES

OPTIONAL SLIDING GLASS DOOR

DEN W/ CORNER FIREPLACE

OPTIONAL FIREPLACE

APPROVED
MAR 2 2 2002
HWCNC, P.C.

OPTIONAL SLIDING GLASS DOOR

DEN W/ STRAIGHT FIREPLACE

BOOK CASE

FIREPLACE OPTIONAL

ENTERTAINMENT CENTER

6'-8 3/4" DOOR

OPTIONAL SLIDING GLASS DOOR

9'-4" 11'-4"
3660 3660E
SPINDLE WALL
OPTIONAL STUDY
14"X14" RAG IN CEILING WITH 12" FLEX CONNECTING RAG IN CEILING AT FURNACE COMPARTMENT
OPTIONAL BEDROOM #4
RAG
2-8
2-0

60'-0"
9'-2" 7'-9 1/2" 23'-4 1/2" 20'-8"
55'-6 3/4" 45'-10" 37'-8" 33'-2" 28'-8" 24'-2" 8'-0 3/4"
3646SG 3660 3660 3660 3660 3660 3660

2-8
UTILITY
LINEN
FREEZER SPACE
1 1/2" A.V.
8" VTR
BATH
14"X14" CEILING RAG
1 1/2" VTR
2-4 RAG
20" FULL LOUVERED DOOR
OPT. DRY
OPT. WASH
22"X30" ATTIC ACCESS ROOM WHEN ATTIC CLEAR HEIGHT IS OVER 30"
W/H
2-4
2-4
2/8 x 6'-8" MIN. TYP
KITCHEN
1 1/2 A.V.

DINING ROOM
SPINDLE WALL
DEN
14"X14" RAG IN CEILING WITH 12" FLEX CONNECTING RAG IN CEILING AT FURNACE COMPARTMENT
RAG
13'-8"
27'-4"
HITCH END

5'-0 1/2"
MASTER BEDROOM
LIVING ROOM
2-0
2-8
2-8
2-0
1-4
2-4
1 1/2" A.V.
BEDROOM #2
BATH
BEDROOM #3
1 1/2" VTR
3/0 x 6'-8" MIN.

3660E 3660 3660 3660 3660E 3660E
55'-1 3/4" 46'-8 3/4" 34'-8 3/4" 28'-6" 21'-4 3/4" 4'-0 3/4"
14'-8" 17'-4" 11'-4" 5'-4" 11'-4"

9'-4" 11'-4"
3660 3660E
OPTIONAL STUDY
OPTIONAL BEDROOM #4
14"X14" RAG IN CEILING WITH 12" FLEX CONNECTING RAG IN CEILING AT FURNACE COMPARTMENT
2-8
RAG
2-8
2-0

20'-8"
3'-4" 17'-4"
3660 3660E
2-0
OPTIONAL BEDROOM #4
14"X14" RAG IN CEILING WITH 12" FLEX CONNECTING RAG IN CEILING AT FURNACE COMPARTMENT
RAG
2-8

1640 SQ. FT.

3-0
28'-6"
OPTIONAL FRONT DOOR

COLUMN STRAPPING SCHEDULE

Ⓐ (2) 2X4 SPF #2 THIS HALF.	Ⓑ (2) 2X4 SPF #2 EACH HALF.
Ⓒ (3) 2X4 SPF #2 THIS HALF.	Ⓓ (3) 2X4 SPF #2 EACH HALF.
Ⓔ (4) 2X4 SPF #2 THIS HALF.	Ⓕ (4) 2X4 SPF #2 EACH HALF.
Ⓖ (5) 2X4 SPF #2 THIS HALF.	Ⓗ (5) 2X4 SPF #2 EACH HALF.

*: WITH RIDGE BEAM BEARING STIFFNER

NOTES:
1. ALL COLUMN STUDS SHALL BE GLUED/NAILED TOGETHER. PVA GLUE WITH 100% COVERAGE SHALL BE USED.
2. INSTALL ONE STEEL STRAP PER STUD AT EACH COLUMN.
3. COLUMN STUDS SHALL NOT BE NOTCHED OR BORED.

17 Acknowledgement of Plans
Kevin Cox 4-10-02
Debra M. Dow

CLAYTON/RICHFIELD 44073 HWY. 52 N. RICHFIELD, NC 28137	
DRAWING #: 33-713N	PAGE #: (3 of 11)
DATE: 11 MAR 02	
CODES: SEE NOTES	
STATE LABEL(S): N.C.	DRAWN BY: TODD HATHCOCK
SCALE: 1/8"=1'-0"	△ INDICATES CHANGE.
MODEL #: MNJA803C	NC RESIDENTIAL MOD. 27'-4" X 60'-0"
FLOOR PLAN	JOB # 1868-0217