IREDELL COUNTY HEALTH DEPARTMENT

Statesville Office (704) 878-5305 Mooresville Office (704) 660-3625 PERMIT # 225047

IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM

PIN # 4614959151

APPLICANT: Wayne Moore APPLICANT ADDRESS: 110 Twiggs Ln Mooresville, NC 28117

SITE ADDRESS: 110 Twiggs Ln Mooresville, NC PHONE: Jugafan115@yahoo.com ALT. PHONE: Mike 704576-3887

SITE DIRECTIONS: Brawley School Rd TR Tuskarora TL Bearcreek TR Twiggs at end on right

SUBDIVISION: CLAT SECTION: 6 LOT # 371 LOT AREA: .59 Acre DESIGN FLOW: 480gpd L.T.A.R.: .3

Septic Tank 1000exist (gal) STB Date

Pump Tank (gal) PT Date

Pump Make Model Serial #

Nitrification Fields 1 # Lines 2 Linear Ft: 104'

Trench Width 36" Max. Trench Bottom Depth 24"-36" Gravel Depth N/A

☐ New System ☐ Repair ☒ Expansion System Type: I II III IV V VI

System Description: Gravity-25% Reduction

Repair System Description: Pre-treatment PPBPS

Maintenance Agreement Required: ☐ YES ☒ NO

☒ GRAVITY ☐ PRESSURE

☒ Residence ☐ Business ☐ Other ☐ Slab ☐ Crawl Space ☒ Basement w/plumbing ☐ Basement w/o plumbing

No. Bedrooms 4 No. Persons 8 No. Employees

Water Supply: ☒ Private ☐ Public ☐ Community

Comments / Conditions: A IC gravity flow can not be maintained to uppermost drainline being added, then new ST will have to be installed.

Note: Shorten existing drainline closest to deck to achieve a 5FT setback.

INITIAL SITE SKETCH

See attached, approved Septic plan by Michael Athanas & Associates dated 2/15/17

AS BUILT SKETCH

3-28-17 - CHECKED LINES BA

3-29-17 LEVELED D-BOXES & FLOW SPLITTER BA

Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system. **CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION**

☐ **IMPROVEMENT PERMIT** *with plat valid without expiration.* ☒ **IMPROVEMENT PERMIT** *with site plan valid for 60 mos.* ☐ **AUTHORIZATION TO CONSTRUCT** *valid for period equal to IMPROVEMENT PERMIT--not to exceed 60 mo.*

Owner / Applicant Signature: Chad Moore Date: 3-6-17 Installed by:

IMPROVEMENT PERMIT by: Maria Dotson Date: 3/3/17 OPERATION PERMIT by: ABERNATHY Date: 3-29-17

AUTHORIZATION TO CONSTRUCT by: Maria Dotson Date: 3/6/17 Existing System Inspected by: Date:

Health Dept. Copy - WHITE Applicant (Final Approval) - YELLOW Applicant (Conditional Approval) - PINK

plat book 34, page 25, that the ratio of precision is 1':10,000, that this map was prepared in accordance with the General Statutes of North Carolina Chapter 89C.


my hand and seal on the 6, day of FEB.,
A.D. 20 17.

WILLIAM M. ALLEN, PLS

NORTH CAROLINA PROFESSIONAL SEAL L-3499 LAND SURVEYOR WILLIAM M. ALLEN

Approved
MD
3/3/17

CURVE TABLE				
CURVE	RADIUS	LENGTH	BEARING	CHORD
C1	50.00'	76.65'	S 08°20'37" E	69.36'



VICINITY MAP***NO SCALE

PB84 PG26

LAKE NORMAN

760 CONTOUR PER ACTUAL FIELD SURVEY

761 CONTOUR (FLOOD LINE)

50' BUFFER FROM ACTUAL 760' CONTOUR

LOT 372
HOOVER PATRICK ANN REVOCABLE TRUST
2233\1790

Well

LOT 371
0.59 AC.

LOT 369
STEVEN MALLORY
2289\550

LOT 1727
LANCE JOHNSON
2458\762

TWIGGS LN.
60' R\W

SHED
DECK
PATIO
2 STORY HARDY COMP. RF.
GARAGE
CONC. DR.
PRIVACY FENCE
15' SIDE SETBACK
35' FRONT SETBACK
15' SIDE
New ST
Ex. ST

182.79
198.18
85.11
67.3
24.3
14.4
9.99
5.0

(BASE BEARING) S56°51'00"W
N55°25'52"E
S37°11'50"E
N54°25'50"W 50.00


Note: If gravity flow can not be maintained to this line then new ST will have to be installed.

LEGEND
P.P. = POWER POLE
POWER TRANS.
E.I.P. = EXISTING IRON FOUND
I.P.S. = #4 REBAR SET
R/W = RIGHT-OF-WAY
WELL
CP = COMPUTED POINT

LINE TABLE		
LINE	BEARING	LENGTH
L1	N 15°37'00" W	55.24'
L2	N 04°47'00" W	50.92'
L3		

0' 20' 40' 100'
SCALE IN FEET

NOTES
1) THIS PROPERTY MAY BE SUBJECT TO ANY EASEMENT AND/OR RIGHTS-OF-WAY OF RECORD.
2) AREA COMPUTED BY THE COORDINATE METHOD.
3) EXISTING 760' & 761' CONTOUR ELEVATION BASED ON LAKE NORMAN LAKE LEVEL AT COWAN'S FORD DAM (READING



MICHAEL ATHANAS & ASSOCIATES
LICENSED SOIL SCIENTIST
561 Ennis Rd.
Weddington, NC 28173
(704) 576-3887

Approved
MD
3/3/17

Reference: Data Sheet for 110 Twiggs Ln., CL&T Sec 6 Lot 371
House Footprint: See attached plan
Building Setbacks: 35' front, 15' side, 50' lake
Water Source: Private well
Number of Bedrooms: 4/480 GPD
Proposed LTAR: 0.3 GPD/FT2
Proposed System Type: 25% Reduction
Proposed Repair System Type: Pre-Treatment PPBPS
Distribution: Gravity-Flow divider to Two Distribution boxes
Septic Tank Size: 1000 gallons (existing)
Proposed Trench Bottom: 24-36" (initial), 30" (repair)

Line	Design Length	Actual Length
Blue 1		48'
White 2		46'
Pink 3		72'
Orange 4		27'
Blue 5	**50'**	**50'**
White 6 (ex)	**50'**	**50'**
Orange 7 (ex)	**50'**	**50'**
Pink 8 (ex)	**50'**	**50'**
Blue 9 (ex)	**50'**	**50'**
White 10 (ex)	**50' (change to 46')**	**50'**
Orange 11 (ex)	**50'**	**50'**
Pink 12	**54'**	**50'**
Yellow 13		72'
White 14		53'

Initial System: 400' **Repair System:** 318'

Comments:
This property has 300' of 25% reduction system installed for a three bedroom residence. There is a flow divider going to two distribution boxes. MA&A are proposing to add two 50' lines to the system to increase the system to four bedrooms.

Approved
3/3/17

There is 193' of repair outside of the 50' lake setback. This means 111' of PPBPS line is need at 25% reduction inside the 50' lake buffer (we have 125'). The repair is laid out on 8' centers.

If B5 is installed at 36", gravity flow may be achieved from the existing septic tank. If it is not possible to keep gravity to B5 from the exiting tank, a new tank will need to be installed to keep a gravity system. This may need to be determined at the time of installation.

The existing line W10 is closer than 5' to the deck post. One chamber should be removed from W10 and added to P12.

The red flags at the lake represent 35' from the 760'. The other red flags represent 50' from wells. The existing tank and the possible new tank are marked with yellow flags.



DEPARTMENT OF HEALTH AND HUMAN SERVICES
DIVISION OF PUBLIC HEALTH, ENVIRONMENTAL HEALTH SECTION
ON-SITE WATER PROTECTION BRANCH

Approved MD 3/3/17

PROPERTY ID #: 4614959151_
COUNTY: _Iredell_

SOIL/SITE EVALUATION
***for* ON-SITE WASTEWATER SYSTEM**
(Complete all fields in full)

OWNER: Wayne Moore_____ APPLICATION DATE_____
ADDRESS: 110 Twiggs Ln, Mooresville, NC 28117_____ DATE EVALUATED: _____
PROPOSED FACILITY: _4 bdrm_____ PROPOSED DESIGN FLOW (.1949): _480 GPD___ PROPERTY SIZE: _0.59 AC_____
LOCATION OF SITE: _110 Twiggs Ln, CL&T Sec 6 Lot 371_____ PROPERTY RECORDED: _1976_____
WATER SUPPLY: ☒ Private ☐ Public ☒ Well ☐ Spring ☐ Other _____
EVALUATION METHOD: ☒ Auger Boring ☐ Pit ☐ Cut TYPE OF WASTEWATER: ☒ Sewage ☐ Industrial Process ☐ Mixed

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
1	LS 10%	0-6	Br SCL WSBK	FR SS SP SEXP	N/A	48"	F-C SAP	N/A	PS 0.3-0.35
		6-24	R C SBK	FR SS SP SEXP					
		24-48	R CL WSBK	FR SS SP SEXP					
2	LS 10%	0-4	Br SCL WSBK	FR SS SP SEXP	N/A	48"	F-C SAP	N/A	PS 0.3-0.35
		4-20	R C SBK	FR SS SP SEXP					
		20-48	R CL WSBK	FR SS SP SEXP					
3	LS 10%	0-5	Br SCL WSBK	FR SS SP SEXP	N/A	48"	N/A	N/A	PS 0.3
		5-38	R C SBK	FR SS SP SEXP					
		38-48	R CL WSBK	FR SS SP SEXP					
4	LS 10%	0-12	FILL		N/A	48"	Few SAP	N/A	PS 0.3
		12-18	Br SCL WSBK	FR SS SP SEXP					
		18-40	R C SBK	FR SS SP SEXP					
		40-48	R CL WSBK	FR SS SP SEXP					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	300 FT2 ADD	636 FT2
System Type(s)	25% Reduction	PPBPS
Site LTAR	0.3	0.3

OTHER FACTORS (.1946): _____
SITE CLASSIFICATION (.1948): _____PS_____
EVALUATED BY: _____MA&A_____
OTHER(S) PRESENT: _____

COMMENTS:_____

SOIL/SITE EVALUATION

(Continuation Sheet-Complete all field in full)

DEPARTMENT OF HEALTH AND HUMAN SERVICES
DIVISION OF PUBLIC HEALTH
ENVIRONMENTAL HEALTH SECTION
ON-SITE WATER PROTECTION BRANCH

PROPERTY ID #: 4614959151
DATE OF EVALUATION: _____
COUNTY: IREDELL

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
5	LS 10%	0-30	FILL						US
6	LS 10%	0-20	R C SBK	FR SS SP SEXP	N/A	46"	Com SAP	N/A	PS 0.3-0.35
		20-46	R CL WSBK	FR SS SP SEXP					
		46-52	SL SAP M	VFR SS SP SEXP					
7	LS 6%	0-5	Br CL WSBK	FR SS SP SEXP	N/A	48"	F-C SAP	N/A	PS 0.3-0.35
		5-24	R C SBK	FR SS SP SEXP					
		24-48	R CL WSBK	FR SS SP SEXP					

COMMENTS: _____

RECEIVED FEB 1 6 2017

IREDELL COUNTY HEALTH DEPARTMENT

Paid $350.00

ENVIRONMENTAL HEALTH DIVISION

PAGE 1: *APPLICATION FORM*

Expansion # 225047

Application For:

( ) New Well Permit ( ) Well Repair Permit ( ) Well Abandonment

(X) Septic Improvement Permit (X) Authorization to Construct ( ) Existing System Inspection ( ) Septic System Repair

THE ABOVE PERMIT DOCUMENTS WILL BECOME INVALID IF INFORMATION PROVIDED ON THIS APPLICATION IS FALSIFIED OR CHANGED, OR IF THE SITE IS ALTERED. THE IMPROVEMENT PERMIT IS VALID FOR EITHER 60 MONTHS OR WITHOUT EXPIRATION DEPENDING UPON DOCUMENTATION SUBMITTED APPLICATION WITH SITE PLAN 60 MONTHS, APPLICATION WITH COMPLETE, SCALED PLAT WITHOUT EXPIRATION. SEE 15A NCAC 18A .1937(f) FOR DETAILS.

Page 2: *Site Plan Worksheet* form MUST accompany this application

The following optional attachments may also be submitted: (X) Survey Plat, scaled no more than 1 inch = 60 feet

Place an (X) beside whichever is submitted if applicable ( ) Custom Site Plan, scaled no more than 1 inch = 60 feet

Applicant Information:

Applicant Name: Wayne Moore Address: 110 Twiggs Ln. Mooresville, NC 28117 Phone: ugafan115@yahoo.com

Owner Name: Same Address: _____ Phone: _____

Property Information:

Street Address: 110 Twiggs Ln

Subdivision Name: CL&T Section/Phase: 6 Lot Number: 371

Driving Directions: BSR, TR Tuskaroara, TL Bearcreek, TR Twiggs, at end on RT

Site Development Information: *(check or complete ALL that apply)*

( ) New Single Family Residence
( ) New Multi-Family Residence
( ) Accessory Building
(X) Bedroom(s) Addition

Maximum Number of Bedrooms: 4
Maximum Number of Occupants: _____
( ) Swimming Pool
( ) Other Addition/Structure: _____

( ) Crawl Space Foundation
( ) Concrete Slab Foundation
(X) Basement with Plumbing
( ) Basement without Plumbing

Non-Residential Site Development:

Type of Business: _____
Square Footage of Building: _____
Maximum Number of Employee: _____
Maximum Number of Seats/Beds/Other: _____

Water Supply:

( ) New Well (X) Existing Well ( ) Community Well ( ) City Water ( ) Other Public Water

Desired Septic System Type: *(you may rank in order of preference)* Year existing system installed: _____

( ) No Preference ( ) Alternative ( ) Conventional ( ) Innovative ( ) Modified Conventional (X) Other: Accepted

Please answer the following to the best of your ability:

( ) Yes (X) No Does the site contain any jurisdictional wetlands?
( ) Yes (X) No Is any non-domestic sewage (i.e. industrial) to be generated?
( ) Yes (X) No Is the site subject to approval by any other public agency?

I have read this application and certify that the information provided herein is true, complete, and correct. Authorized county and state officials are granted right of entry to conduct necessary inspections to determine compliance with applicable laws and rules. I understand that I am solely responsible for the proper identification and labeling of all property lines and corners and making the site accessible so that a complete site evaluation can be performed.

Signature: _____ 2/15/2017

Property owner or owner's legal representative signature (SIGNATURE REQUIRED) DATE

Public Health
Protect Promote Protect
Iredell County Health Department

IREDELL COUNTY DEPARTMENT OF ENVIRONMENTAL HEALTH

Public Health
Protect Promote Protect
Iredell County Health Department

DOCUMENTATION TO AUTHORIZE AN OWNER'S LEGAL REPRESENTATIVE

Applications for permits require the "signature of the owner or owner's legal representative" (15A NCAC 18A .1937). If the owner does not sign the application himself or herself, they can submit any one of the following documents to designate their legal representative:

Power of Attorney; Real Estate Contract; Estate executor; Bankruptcy trustee; Court ordered guardianship

In the absence of the above documentation, the property owner may provide the local health department with documentation that designates a legal representative. A property owner may:

Complete this form to document his or her legal representative, or provide his or her own form that contains the information in this form.

If there are multiple property owners, then all property owners must sign the form that designates a legal representative.

By signing a form that designates a legal representative for purposes of 15A NCAC 18A .1937, the property owner authorizes that representative to act on their behalf in matters pertaining to the application and permitting process, including signing or receiving any application, document or permit. The owner retains full responsibility to meet all permit conditions specified by the local health department.

I, WAYNE A MOORE, am the legal owner(s) of the property located at 110 TWIGGS LANE, identified as PIN (Parcel Identification Number) _____, located in Iredell County, North Carolina.

I do hereby authorize (**print legal representative/company name**) MICHAEL ATHANAS, _____, to act as an agent on my behalf in applying for/signing/obtaining any of the documents described below.

- Application for Improvement Permit (IP) / Authorization to Construct (AC)
- Improvement Permit (IP) / Authorization to Construct (AC)
- Application for soil-site evaluation (new/repair)
- Application/permit for private drinking water well/well abandonment
- Application for Compliance Inspection

I agree to abide by all decisions and/or conditions between the legal representative acting on my behalf and the Iredell County Department of Public Health, Environmental Health Division.

Wayne A Moore — Signature of Owner(s) — 2/14/17 — Date

Cheryl H Moore — Signature of Witness — 2-14-17 — Date

Please return this signed form to the appropriate office:

Mooresville - Environmental Health
ronda.hart@co.iredell.nc.us
Fax: 704-662-3239
610 E. Center Avenue, Mooresville, NC 28115

Statesville - Environmental Health
adrienne.shea@co.iredell.nc.us
Fax: 704-871-3483
349 N. Center Street, Statesville, NC 28677

IREDELL COUNTY HEALTH DEPARTMENT


ENVIRONMENTAL HEALTH DIVISION

PAGE 2: *SITE PLAN WORKSHEET*

SEE THE "SAMPLE SITE PLAN" BELOW. *INCOMPLETE SITE PLANS WILL BE RETURNED TO YOU FOR COMPLETION AND MAY RESULT IN A DELAY IN THE ISSUANCE OF YOUR SEPTIC SYSTEM PERMIT!!!*

Place an (X) beside each item as you complete the site plan:

( ) **Property Line measurements are clearly identified**
( ) **All proposed structures are indicated**
( ) **Front and side setbacks from property line**
( ) **Preferred driveway location and well location**
( ) **Area you prefer your septic system to be placed**
( ) **North arrow, or other sufficient indicator of direction**



Circle N/A on the following if appropriate:

Location of septic systems and wells within 100' of your property	**N/A**
Location of easements and rights of ways on your property	**N/A**
Location of any designated wetlands on the property	**N/A**

USE THIS SPACE TO DRAW YOUR SITE PLAN

Show: proposed house or business footprint, wells, water lines, patios, pools and decks, and any other item that will occupy space on the site

See Attached Plan

Signature: _____ 2/15/2017

Property owner or owner's legal representative signature (SIGNATURE REQUIRED) **DATE**

plat book 34, page 25, that the ratio of precision is 1':10,000, that this map was prepared in accordance with the General Statutes of North Carolina Chapter 89C.

my hand and seal on the 6, day of FEB.


A.D. 20 17.

WILLIAM M. ALLEN, PLS

NORTH CAROLINA PROFESSIONAL SEAL L-3499 LAND SURVEYOR WILLIAM M. ALLEN

Approved MD 3/3/17

CURVE TABLE				
CURVE	RADIUS	LENGTH	BEARING	CHORD
C1	50.00'	76.65'	S 08°20'37" E	69.36'



VICINITY MAP***NO SCALE

PB84 PG85

LAKE NORMAN

760 CONTOUR PER ACTUAL FIELD SURVEY

761 CONTOUR (FLOOD LINE)

50' BUFFER FROM ACTUAL 760' CONTOUR

SHED

PATIO

DECK

2 STORY HARDY COMP. RF.

GARAGE

CONC. DR.

PRIVACY FENCE

15' SIDE SETBACK

35' FRONT SETBACK

15' SIDE

LOT 372
HOOVER PATRICK ANN REVOCABLE TRUST
2233\1790

Well

LOT 371
0.59 AC.

LOT 369
STEVEN MALLORY
2289\550

LOT 1727
LANCE JOHNSON
2458\762

TWIGGS LN.
60' R\W

Note: If gravity flow can not be maintained to this line then new ST will have to be installed.


LINE TABLE		
LINE	BEARING	LENGTH
L1	N 15°37'00" W	55.24'
L2	N 04°47'00" W	50.92'

LEGEND
- P.P. = POWER POLE
- = POWER TRANS.
- E.I.P. = EXISTING IRON FOUND
- I.P.S. = #4 REBAR SET
- R/W = RIGHT-OF-WAY
- W = WELL
- CP = COMPUTED POINT

NOTES
1) THIS PROPERTY MAY BE SUBJECT TO ANY EASEMENT AND/OR RIGHTS-OF-WAY OF RECORD.
2) AREA COMPUTED BY THE COORDINATE METHOD.
3) EXISTING 760' & 761' CONTOUR ELEVATION BASED ON LAKE NORMAN LAKE LEVEL AT COWAN'S FORD DAM (READING

0' 20' 40' 100'
SCALE IN FEET

Book 0034
Pages 0025 - 0025
FILED
1 PAGE(S)
IREDELL COUNTY NC
11/16/1999 9:29 AM
BRENDA D. BELL
Register Of Deeds



APPROVED IN ACCORDANCE WITH THE PROVISIONS OF THE SUBDIVISION ORDINANCE OF MECKLENBURG COUNTY, NORTH CAROLINA.
CHARLOTTE-MECKLENBURG PLANNING COMMISSION
Fred E. Bryant ACTING SECRETARY June 16, 1976

STATE OF NORTH CAROLINA
COUNTY OF MECKLENBURG
The foregoing certificate(s) of Henry H. Jenkins, Jr.
a Notary Public of said County and State is now certified to be correct.
This 21st day of September 19 76
Recorded in Book ____ Page ____ and Verified.
CHARLES E. CROWDER, Register of Deeds
By Maryanne K. Deputy

APPROVED IN ACCORDANCE WITH THE ENGINEERING REQUIREMENTS OF THE SUBDIVISION ORDINANCE OF MECKLENBURG COUNTY, NORTH CAROLINA.
MECKLENBURG COUNTY ENGINEERING DEPARTMENT
E K Hall (COUNTY ENGINEER) 2 June 76 (DATE)

PRESENTED FOR REGISTRATION
1976 SEP 21 PM 3 50
REGISTER OF DEEDS MECKLENBURG CO. N.C.

NORTH CAROLINA
MECKLENBURG COUNTY
The undersigned surveyor, being duly sworn, deposes and says that the plat upon which this certificate appears was prepared in accordance with G.S. 47-30 as amended, to the best of his knowledge and belief, and was completed from an actual survey made by him on the 14th day of May, 19 76 with a maximum error of closure of 1:10,000 and a maximum field error of angular closure of 25 sec per angle
L. Dale Arthur L.S.

STATE OF NORTH CAROLINA
COUNTY
I, Henry H. Jenkins, Jr., a Notary Public in and for said County and State, do hereby certify that L. Dale Arthur personally appeared before me this day and acknowledged the due execution of the foregoing instrument.
Witness my hand and Notarial Seal this 18th day of May, 19 76.
My Commission Expires February 6, 1981

NOTE: DUKE POWER COMPANY TO CRESCENT LAND & TIMBER CORP. DEED BOOK 3146, PAGE 153 DATED: MAY 1, 1969.

BUILDING SETBACK LINES ARE 30 FEET FROM ROAD RIGHT OF WAY LIMIT, 50 FEET FROM CONTOUR ELEV. 760 U.S.G.S. SEA LEVEL DATUM, AND 10 FEET FROM SIDE LOT LINE.


ALL STREET CORNER RADII ARE 20 FEET. PROPERTY LINE DISTANCES ARE COMPUTED TO POINT OF INTERSECTION AT STREET CORNERS.

CRESCENT LAND & TIMBER CORP.
LAKE NORMAN
MAP OF
RECREATION LOTS
SECTION 6
LOTS 260, 262-266, 359-365
368, 369, 371 - 373 & 375
LEMLEY TOWNSHIP
MECKLENBURG COUNTY, N.C.

SCALE: 1" = 100'
DEC. 19, 1975
MISC. BOOK NO. 372 & 378
DWG. NO. C.F. 6-0

0 100 200 300 400
SCALE IN FEET

MAP 17 621



First Floor

Acknowledgement of Plans Submittal ONLY!

Date 3-6-17


Date 3/6/17

Acknowledgement Of Plans Submittal ONLY!

Date 8-25-04

Date 8-26-04

Acknowledgement of
Plans Submittal ONLY!
Date 3-6-17
Date 3/6/17



2nd floor

Acknowledgement Of
Plans Submittal ONLY!
Date 8-25-04
Date 3/6/17

IMG_5772.JPG

Open with

Basement

Acknowledgement of Plans Submittal ONLY!

Date 3-6-17

Date 3/6/17

