-SITE WASTEWATER SECTION

COUNTY: _____

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

WNER: James "Chris" Williams APPLICANT: _____

DDRESS: _____ APPLICATION DATE: _____ DATE EVALUATED: 7-21-04

OPOSED FACILITY: _____ PROPOSED DESIGN FLOW (.1949): 360gpd PROPERTY SIZE: _____

CATION OF SITE: Sect 6 Lot 371 Twn 58 Lot 19 PROPERTY RECORDED: _____

ATER SUPPLY: ☐ Private ☐ Public ☐ Well ☐ Spring ☐ Other _____

ALUATION METHOD: ☐ Auger Boring ☐ Pit ☐ Cut NEED well abandonment form.

PE OF WASTEWATER: ☐ Sewage ☐ Industrial Process ☐ Mixed

Keep trenches shallow to stay out of B-C Stop Hans.

.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS & LTAR
16% S/L	0-7	wk sbk lm sl/scl	fr ss sp					.3
	7-41	wk sbk r cl/l	fr ss sp stp	few-common mi stp				
	41-48	wk sbk cl/l	fr ss sp	common mi stp				
8% S	0-8	gr-wk sbk lm sl/scl	fr ss sp					.3
	8-31	wk sbk r cl/cl	fr ss sp stp					
	31-48	wk sbk gr cl/l	fr ss sp	few mi stp few mica				
	0-6	gr-wk sbk lm sl/scl	fr ss sp	common gravel & saprolite rock				.3
	6-30	wk sbk r cl/cl	fr ss sp stp					
	30-48	wk sbk gr cl/l	fr ss sp	few-common mi stp				

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
uilable Space (.1945)	PS	PS
tem Type(s)	Conv 25% Mod	LPP / LP 25-30%
: LTAR	.3	.3

OTHER FACTORS (.1946): _____

SITE CLASSIFICATION (.1948): PS

EVALUATED BY: [signature]

OTHER(S) PRESENT: _____

Lot platted prior to 1983