Russel Williams 980429 1580

IREDELL COUNTY HEALTH DEPARTMENT

STATESVILLE 704-878-5305 MOORESVILLE 704-664-5281

IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM INSPECTION

PERMIT# 14752 PIN# 4626115224.054 DATE 12/14/07

OWNER OR APPLICANT Mid Atlantic Custom Builders PHONE: Business 828 478-2761 Cell Home 202-5568

ADDRESS P.O. Box 3792 Mooresville, NC 28117

LOCATION Brawley School Rd TR Chickwood take to end TL Barber Lp. lot on left

SUBDIVISION Watertree Land BLOCK / SECTION ____ LOT 54 LOT AREA 30,145 ft² SITE CLASS. PS DESIGN FLOW 480 gpd L.T.A.R. .3

Septic Tank: 1000 Gallons; STB ____ Date ____

Pump Tank: 1000 Gallons; PT ____ Date ____

Pump Make: ____ Model ____ Serial No. ____

Nitrification Field: No Fields 1 Square Feet 270' Linear Feet 270'

No Lines 3 Trench Width As per plan Trench Bottom Depth 36" Gravel Depth N/A ☐ Gravity ☒ Pressure

☒ New System ☐ Repair ☐ Expansion System Type: I II III IV V VI

System Description: Pump-LP-Panel Blk

Repair System Description: Same

Maintenance Agreement Required: ☒ Yes ☐ No

☒ House/Mod. Home No. Bedrooms 4

☐ Mobile Home No. Persons ____

☐ Business No. Employees ____

☐ Other ____

Water Supply: ☒ Individual ☐ Public ☐ Community

☐ Slab ☒ Crawl Space ☐ Basement w/plumbing ☐ Basement wo/plumbing

Comments/Conditions: See plan specs for trench width. Initial site evaluation and design performed by Rollans Soil & Environmental Services.

Comments/Conditions: Type 4 System, needs Maint. agreement. Used In Line Filter in PT 1/10/08 Reviewed Floor Plans, essentially in compliance with original design/plan.

INITIAL SITE SKETCH

See plan from Rollans Soil & Env. Services

AS BUILT SKETCH

Permit can be suspended or revoked if any false information is supplied toward securing the permit/any unauthorized changes are made to the site/any unauthorized changes are made in the installation of the system. Improvement Permit with plat valid without expiration ☐ Improvement Permit with site plan valid for sixty months ☐ Authorization to Construct is valid for a period equal to that of Improvement Permit – not to exceed sixty months.

Signed: ____ date ____

Improvement Permit by: Mark Tolson RS date 12/14/07

Authorization to Construct by: Mark Tolson RS date 1/10/08

Installed by: ____

Operation Permit by: ____ date ____

Existing System Inspection by: ____ date ____

HEALTH DEPT. COPY: WHITE OWNER COPY (FINAL): YELLOW OWNER COPY (INITIAL): PINK