CALCULATIONS

Location WATERTREE LANDING

Project Number 01-1430

Lot No: Lot 54

No. of Bedrooms	4	
Design Flow	480	$^{gal}/_{day}$
LTAR	0.300	$^{gal}/_{ft^2\,day}$
PPBPS? (YES OR NO)	YES	
Supply Line Length	93	ft.
Supply Line Volume	16.182	gal.
Required Feet of Line	266.6667	ft.
Amount of Line from Layout	270	ft.
Gallons per Minute	25.42	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Minimum Standard Tank Size	1000	
Panel Volume	3.6	gal.
# of Panels	62	
Dosing Volume	149.54	gal.

Note: Dosing Volume based on 33% of # of panels times 3.6 gal/panel

Tank Draw Down	7.1	*Generic Draw Down of 21 gal.per in.*
Pump Run Time	5.88	minutes
Elevation Head	8.6	ft.
Pressure Head	2	ft.
Friction Factor	1.78	ft./100 ft. *(From the interpolater.)*
Friction Head	1.66	ft.
Total Dynamic Head (+15%)	14.09	ft.

FRICTION FACTOR
INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42