

1/2 SLAB DETAIL
3/4" = 1'-0"

NOTE: LOCATE GRADE BEAMS UNDER ALL LOAD BEARING WALLS

NOTE: ALL ANGLES ARE 45° UNLESS OTHERWISE NOTED

UNFINISHED BASEMENT
4" CONC. SLAB W/ 6" X 6" 10/10 W.W.F. OVER 6 MIL POLY OVER 4" GRAVEL (TYP.)

GARAGE SLAB
4" CONC. SLAB W/ 6" X 6" 10/10 W.W.F. OVER 6 MIL POLY OVER 4" GRAVEL (TYP.)

PORCH SLAB
DROP 8" BELOW FINISH FLOOR

NOTE: DROP FOUNDATION WALL UNDER GARAGE SLAB 8" FROM MAIN FOUNDATION WALLS

TURNED DOWN SLAB (TYP.)

STEP DOWN FOUND. WALL AS SITE ALLOWS

2-0 HALF-LITE DOOR

2 x 6 STUD WALL (TYP.)

GRADE BEAMS AS REQ'D. (TYP.)

CONT. CONC. WALL AS REQ'D. (TYP.)

CONT. CONC. FTG. AS REQ'D. (TYP.)

BEAM AS REQ'D.

STAIRS TO 1ST

LINE OF FLOOR ABOVE

PORCH LEDGE AS REQ'D. (TYP.)

STONE LEDGE AS REQ'D. (TYP.)

PROVIDE SUPPORT FOR PORCH AND STEPS TO GARAGE AS REQ'D.

HVAC

W/H

COPYRIGHT © 2002 BY FRANK BETZ ASSOCIATES, INC. NOT TO BE REPRODUCED

BASEMENT FOUNDATION PLAN

1/4" = 1'-0"

FRANK BETZ ASSOCIATES, INC. ASSUMES NO LIABILITY FOR ANY CHANGES OR MODIFICATIONS MADE TO THESE PLANS BY OTHERS.

REVISIONS	DATE	BY
ALL 2nd FLR	4-8-02	CJF

Copyright Frank Betz Associates, Inc. All Rights Reserved. The Duplication, Reproduction, Display, Sale, Rental, Licensing, or any other distribution or use of these drawings, any portion thereof, or the plans depicted herein is Strictly Prohibited unless expressly authorized in writing by FBA, Inc.

HOMEPLANS
DESIGNED FOR TODAY'S MARKET

BASEMENT FOUND. PLAN

THE WOODCLIFFE

FBA
FRANK BETZ ASSOCIATES, INC.
2401 LAKE PARK DRIVE/SUITE 250
SMYRNA, GEORGIA 30080
770/431-0888
www.frankbetz.com

BY: FLD CK: KKW

DATE: 2/19/02

SHEET: 2

OF: 5

THURSDAY, APRIL 04, 2002 PATH NAME: R:\BOBCAT\WOODCLIFFE\WOODCLIFFE.MAN