The Point Lot 955 - Fast Track Septic System Information

House	
Foundation	**Crawl**
Design Flow (gpd)	**600**
Primary System LTAR (gpd/ft2)	**0.25**
Primary System Type	**25% Reduction**
No. Lines	See site plan
Total Linear Feet	~~600~~ 630
Trench Width	3' min.
Trench Spacing	9' min.
Pump Required	No for primary
Distribution Device	splitter box and drop boxes
Maintenance Agreement Required	No
Repair System	**25% Redution with 48 inch trench**
Total Linear Feet	800 (conv. Length required)
Repair Loading Rate	0.25

LRP Dist. 7-31-12
PTR

Use 1500 gallon septic tank.