Lot 464 The Farms at Lake Norman Fast Track Septic System Information

Number of Bedrooms	4
Basement or Crawl	Crawl Space
Design Flow (gpd)	480
LTAR (gpd/ft2)	0.3
Primary System Type	25% Reduction
No. Lines	3 @ 134' endfed
Total Ft. Line	402
Pump Required	No
Distribution Device	D Box
Maintenance Agreement Required	No
Repair System	25% Reduction
Total Ft. Line	493
Elevations (Rod Readings)	
Upper Line	Pink 3.64'
Lower Line	Pink 9.5'
Tank	2.7'
House Corner	3.4'
Benchmark	10.4'

Notes: Benchmark is a buffer stake located 258' from 464/465 rear property corner
Additional repair located downslope from last pink repair line