Lot 485 The Farms at Lake Norman Fast Track Septic System Information

Number of Bedrooms	4
Basement or Crawl	Crawl Space
Design Flow (gpd)	480
LTAR (gpd/ft2)	0.25
Primary System Type	25% Reduction
No. Lines	4 @ 120' endfed
Total Ft. Line	480
Pump Required	No
Distribution Device	D. Box
Maintenance Agreement Required	No
Repair System	LP PPBPS
Total Ft. Line	420
Elevations (Rod Readings)	
Upper Line	Pink 3.3'
Lower Line	Blue 8.0'
Tank	5.7'
House Corner	5.2'
Benchmark	4.3'

Notes: Benchmark shot at the base of tree marked with blue flagging on the upper red line