Lot 495 The Farms at Lake Norman Fast Track Septic System Information

Number of Bedrooms	4
Basement or Crawl	Crawl Space
Design Flow (gpd)	480
LTAR (gpd/ft2)	0.3
Primary System Type	25% Reduction
No. Lines	4 @ 100' endfed
Total Ft. Line	400
Pump Required	Yes
Distribution Device	Pressure Manifold
Maintenance Agreement Required	No
Repair System	25% Reduction
Total Ft. Line	443
Elevations (Rod Readings)	
Upper Line	Blue 3.22'
Lower Line	Pink 5.39'
Tank	6.54'
House Corner	4.65'
Benchmark	5.1'

Notes: Benchmark is 35' rear offset stake on 495/496 PL