Lot 597 The Farms Phase 5 Fast Track Septic System Information

Number of Bedrooms	**4**
Basement or Crawl	**Crawl Space**
Design Flow (gpd)	**480**
Primary System Type	**25% Reduction**
LTAR (gpd)/ft2	**0.3**
Total Ft. Line	402
No. Lines	3 (See Table)
Pump Required	No
Distribution Device	Distribution Box
Maintenance Agreement Required	No
Repair System	**LP PPBPS**
Total Ft. Line	296
Repair System Loading Rate	0.3

Table: Summary of Primary and Repair Nitrification Line Specifications

Line No.	Use	Line Color	System Type	Line Length (Ft.)
1	System	Orange	25% Reduction	134 endfed
2	System	Pink	25% Reduction	134 endfed
3	System	Red	25% Reduction	134 endfed
4	Repair	Blue	LP PPBPS	160
5	Repair	White	LP PPBPS	136
				Total System: 402'
				Total Repair: 296'

Tank	Red	1500 gal (2 compartment)
House	Blue	