IREDELL COUNTY HEALTH DEPARTMENT

Statesville Office (704) 878-5305 Mooresville Office (704) 660-3625 PERMIT # 231306

SEPTIC IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM

PIN # 4626823531

APPLICANT/OWNER: Kyle Larson APPLICANT ADDRESS: 209 Wild Harbor Rd Mooresville, NC 28117

SITE ADDRESS: 495 Brawley School Rd Mooresville, NC PHONE: 704 634-1053 Bill Goff ALT. PHONE

SITE DIRECTIONS: Brawley School Rd on left across from Southfork Rd SAP CONTROLLED: ☐ YES ☒ NO

SUBDIVISION: — SECTION: — LOT # — LOT AREA: 6.89 Acre DESIGN FLOW: 360gpd L.T.A.R.: .3I / .27SR

Septic Tank 1000 (gal) STB 794 Date 4-19-18

Pump Tank (gal) PT Date

Pump Make Model Serial #

Nitrification Fields 1 # Lines 3 Linear Ft. 300ft

Trench Width 36" Trench Bottom Depth(Low side) 35" Gravel Depth N/A

☒ New System ☐ Repair ☐ Expansion System Type: I II (III) IV V VI

System Description: Gravity - 25% Reduction

Repair System Description: 25% Reduction

Maintenance Agreement Required: ☐ YES ☒ NO

☒ GRAVITY ☐ PRESSURE

☒ Residence ☐ Business ☐ Other ☒ Slab ☐ Basement w/plumbing

No. Bedrooms 3 No. Persons 6 No. Employees ☐ Crawl Space

Water Supply: ☒ Private ☐ Public ☐ Community ☐ Basement w/o plumbing

Comments / Conditions: Divert storm/surface water along property line as shown on plan

Remove 12" of compaction across drainfield area

INITIAL SITE SKETCH

See attached, approved Septic Plan by Carolina Soil & Septic Consulting, PLLC (dated) 5/10/18

AS BUILT SKETCH

Installed as shown.

Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system. **CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION**

☐ **IMPROVEMENT PERMIT** *with plat valid without expiration* ☒ **IMPROVEMENT PERMIT** *with site plan valid for 60 mos.* ☒ **AUTHORIZATION TO CONSTRUCT** *valid for period equal to IMPROVEMENT PERMIT--not to exceed 60 mo.*

Owner / Applicant Signature: Date: 5/18/18 Installed by: Abernathy

IMPROVEMENT PERMIT by: Date: 5/17/18 OPERATION PERMIT by: Date: 5-23-18

AUTHORIZATION TO CONSTRUCT by: Date: 5/17/18 Existing System Inspected by: Date:

FOR SEPTIC FINAL INSPECTION: CALL 704-664-3703 between 8am-9am the day the inspection is needed. Be sure to speak with an inpsector to confirm your inspection time.

#231306
RECEIVED MAY 14 2018

IREDELL COUNTY DEPARTMENT of ENVIRONMENTAL HEALTH

APPLICATION FORM Revised Application

Application For: ( ) New Well Permit ( ) Well Repair Permit ( ) Well Abandonment
(X) Septic Improvement Permit (X) Authorization to Construct ( ) Existing System Inspection ( ) Septic System Repair

THE ABOVE PERMIT DOCUMENTS WILL BECOME INVALID IF INFORMATION PROVIDED ON THIS APPLICATION IS FALSIFIED OR CHANGED, OR IF THE SITE IS ALTERED. THE IMPROVEMENT PERMIT IS VALID FOR EITHER 60 MONTHS OR WITHOUT EXPIRATION DEPENDING UPON DOCUMENTATION SUBMITTED. APPLICATION WITH SITE PLAN 60 MONTHS, APPLICATION WITH COMPLETE, SCALED PLAT WITHOUT EXPIRATION. SEE 15A NCAC 18A .1937(f) FOR DETAILS.

Page 2: *Site Plan Worksheet* form MUST accompany this application

The following optional attachments may also be submitted: ( ) Survey Plat, scaled no more than 1 inch = 60 feet
Place an (X) beside whichever is submitted if applicable (X) Custom Site Plan, scaled no more than 1 inch = 60 feet

Applicant Information: (PRINT CLEARLY)

Applicant Name: KYLE LARSON Address: 209 WILD HARBOUR RD. MOORESVILLE, NC Zip: 28117
Applicant Email: LBGOFF1@AOL.COM (BILL GOFF) Phone: 704-634-1053 (BILL GOFF) Alt. Phone: _____
Owner Name: KYLE LARSON Address: SAME Zip: SAME
Owner Email: _____ Phone: _____ Alt. Phone: _____

Property Information:

Street Address: 1495 BRAWLEY SCHOOL RD. MOORESVILLE, NC 28117
Subdivision Name: _____ Section/Phase: _____ Lot Number: _____
Driving Directions: BRAWLEY SCHOOL RD ACROSS FROM SOUTHFORK RD., ON RIGHT

Site Development Information: *(check or complete ALL that apply*

CHECK FOUNDATION TYPE

(X) New Single Family Residence — Maximum Number of Bedrooms: 3 — ( ) Crawl Space Foundation
( ) New Multi-Family Residence — Maximum Number of Occupants: 6 — (X) Concrete Slab Foundation
( ) Accessory Building — ( ) Swimming Pool — ( ) Basement with Plumbing
( ) Bedroom(s) Addition — ( ) Other Addition/Structure: _____ — ( ) Basement without Plumbing
( ) Repair to failing septic system ___ Tank ___ Drain lines Describe Problem: _____
Non-Residential Site Development: Type of Business: _____
Square Footage of Building: _____ Max. Number of Employees: _____ Max. Number of Seats/Beds/Other: _____

Water Supply: ( ) Replacement Well – Reason: _____
( ) Multi-connection Well Number of Houses: _____ Number of Persons: _____

( ) New Well (X) Existing Well ( ) Community Well ( ) City Water ( ) Other Public Water

Desired Septic System Type: *(you may rank in order of preference)* Year existing system installed: _____
( ) No Preference (X) Alternative ( ) Conventional ( ) Innovative ( ) Modified Conventional ( ) Other: _____

Please answer the following to the best of your ability:
( ) Yes (X) No Does the site contain any jurisdictional wetlands?
( ) Yes (X) No Is any non-domestic sewage (i.e. industrial) to be generated?
( ) Yes (X) No Is the site subject to approval by any other public agency?

I have read this application and certify that the information provided herein is true, complete, and correct. Authorized county and state officials are granted right of entry to conduct necessary inspections to determine compliance with applicable laws and rules. I understand that I am solely responsible for the proper identification and labeling of all property lines and corners and making the site accessible so that a complete site evaluation can be performed.

Signature: _____ 5-10-18
Property owner or owner's legal representative signature (SIGNATURE REQUIRED) DATE

OWNER INFORMATION

Owner:	Kyle Larson
Address:	209 Wild Harbour Rd. Mooresville, NC 28117
Contact:	Bill Goff
Phone:	704-634-1053
County:	Iredell
Location:	1495 BRAWLEY SCHOOL RD.
Source of Wastewater Flow:	3 Bedroom Single Family Residence
Estimated Gallons Per Day Flow:	360
System Flow:	NA

Approved
5/17/18
MD

25% GRAVITY DESIGN INFORMATION

Drainfield Design Flow (gpd):	360	
Loading/Soil Application Rate (gpd/ft.^{2}):	0.300	
Depth of Gravel in Trench:	NA (25% reduction)	
Gravel Size:	NA (25% reduction)	
Total Lateral Length From Layout:	300	
Total Lateral Length Required:	300	
Trench Depth:	35 in.	Lowside
Trench Width:	36 in.	
TOTAL AREA TRENCH BOTTOM:	900	
Trench Spacing on Center:	9 ft.	
Repair Trench Spacing:	9 ft.	
Repair Trench Depth:	24 in.	Below final graded grade
Septic Tank Size:	1000	gal.
Estimated Supply Line Length:	4	
Supply Line Diameter:	3 in. SCH 40 PVC	
Supply Line Volume:	1.44	
Dosing Volume:	NA	
Supply Manifold:	SERIAL DISTRIBUTION	
Additional Comments:	Soil suitability was performed by CS&SC	

1495 BRAWLEY SCHOOL RD.
FIELD LAYOUT SPECIFICATIONS

LAYOUT FOR 3 BEDROOM RESIDENCE — May 10, 2018


LINE #	FLAG COLOR	FS	ELEVATION	FLAGGED LINE LENGTH	DESIGN LINE LENGTH
TBM			NA		
HOUSE CRN		NA	NA		
P. TANK		NA	NA		
1	ORANGE	*NA*	*NA*	86	86
2	RED	*NA*	*NA*	129	129
3	YELLOW	*NA*	*NA*	167	167
4	***BLUE***	*NA*	*NA*	***164***	***110***
5	***RED***	*NA*	*NA*	***178***	***110***
6	***ORANGE***	NA	NA	***160***	***80***
7	YELLOW	NA	NA	134	134
8	PINK	NA	NA	118	118
9	BLUE	NA	NA	95	95
10	RED	NA	NA	76	76
			Total	**1307**	**1105**


Approved
5/17/18
MD


	LINE LENGTH	SYSTEM TYPE	SOIL LTAR GPD/FT²	TRENCH SYSTEM	DISTRIBUTION
System	***300***	***ACCEPT.***	***0.300***	***25% RED.***	***GRAVITY***
Repair	805	*ACCEPT.*	0.275	25% RED.	GRAVITY

Notes: ** TBM Is Not Required.
**All measures in feet
**Nitrification lines are demonstrated on contour via colored pin flags

Comments: **APPROXIMATLEY 2' OF SOIL TO BE REMOVED FROM ORANGE, RED AND YELLOW LINES.**
PITS 1 AND 2 WERE EVALUATED TO 72 AND 73 INCHES WITH THIS IN CONCIDERATION.
WATER TO BE DIVERTED ALONG PROPERTY LINE AS SHOWN ON PLAN.
REMOVE 12" OF COMPACTION ACROSS DRAINFIELD AREA.
Iredell County has CS&SC's permission to change septic tank location and distribution type


Approved 8/11/15
5+00
10 FT CONC. SIDEWALK
10 FT GARAGE DOOR
15 FT SIDE SETBACK
Found
1.75" IP
Metal
Fence
w/Elect.
10 FT GARAGE DOOR
10 FT GARAGE DOOR
14 FT GARAGE DOOR
14 FT GARAGE DOOR
6+00
1 Story Brick
Residence
Concrete
Pad
71'
WATER DIVERSION
STA 6+94.36
OFF 10.00'
ST
EP: 7+19.36
7+00
7+19
1 O 86'
2 R 129'
3 Y 167'
4 B 110'
5 R 110'
6 O 80'
7 Y 134'
8 P 118'
9 B 95'
10 R 76'
1"=50'
NORTH
345.69'
Metal
Fence
w/Elect.
Asphalt
Drive
Found
#4 Rebar
124.45'
Found
#4 Rebar
225.64'
Metal
Fence
50.06'
Found
IP Bent
Found
#4 Rebar
TAX ID: 4626-82-5116
LOT 351
JAMES P.&
SUSAN M. FIGGINS
PB: 32 PAGE: 114
DB: 1857 PAGE : 1559
ZONED R-20 CUD
TAX ID: 4626-82-6133
LOT 350
DENNIS & ROBERTA MCCABE
PB: 32 PAGE: 114
DB: 1567 PAGE : 1249
ZONED R-20 CUD
TAX ID: 4626827151
LOT 349
POINT OWNERS ASSOCIATION INC
PB: 32 PAGE: 114
DB: 1232 PAGE : 2022
ZONED R-20 CUD
TAX ID: 4626-82-8180
LOT 348
POINT OWNERS ASSOCIATION INC
PB: 32 PAGE: 101
DB: 1232 PAGE : 2022


BRAWLEY SCHOOL RD - SR.1100
90' PUBLIC R/W
(PLAT BOOK 32 PAGE 114)
575.49'
25 FT FRONT SETBACK
387.38'
5 FT SIDE SETBACK
159.81'
5 FT SIDE SETBACK
210.89'
5 FT SIDE SETBACK
559.84'
15 FT SIDE SETBACK
124.45'
225.64'
345.69'
50.06'
6.89 ACRES
1"=100'
NORTH
WELL
Concrete Sidewalk
Metal Fence o/Elect.
Found #4 Rebar
IPS
Found 1.73" IP
Found IP Bent
Shed
Concrete Pad
1 Story Brick Residence
Asphalt Drive
WATER DIVERSION
INV. 831.76
EX. 12" RCP
INV. 830.36
TAX ID: 4629-72-7130
LOT 355
MOONLIGHT KARAOKE PROPERTY TR
PIN: 41 PAGE:37
DB:2302 PAGE :630
ZONED R-20 CUD
TAX ID: 4629-62-0108
LOT 354
JEFFREY C. &
KAREN M. BAHR
PIN: 32 PAGE:114
DB:1918 PAGE :1998
ZONED R-20 CUD
TAX ID: 4629-62-2210
LOT 353
RONALD D.& SHARI GARTNER
PIN: 32 PAGE:114
DB:2368 PAGE :2079
ZONED R-20 CUD
TAX ID: 4629-62-3189
LOT 352
DOYLE PAT INMAN
PIN: 32 PAGE:114
DB:1831 PAGE :301
ZONED R-20 CUD
TAX ID: 4629-62-3119
LOT 351
JAMES P.&
SUSAN M. PIGGINS
PIN: 32 PAGE:114
DB:1597 PAGE :1258
ZONED R-20 CUD
TAX ID: 4629-62-6133
LOT 350
DENNIS & ROBERTA MCCABE
PIN: 32 PAGE:114
DB:1597 PAGE :1249
ZONED R-20 CUD
TAX ID: 4629-62-7131
LOT 349
POINT OWNERS ASSOCIATION INC
PIN: 32 PAGE:114
DB:1232 PAGE :2023
ZONED R-20 CUD
TAX ID: 4629-62-8180
LOT 348
POINT OWNERS ASSOCIATION INC
PIN: 32 PAGE:108
DB:1232 PAGE :2022
ZONED R-20 CUD
TAX ID: 4629-62-3785
WILLIAM H. BUNDY
DB:2191 PAGE :1996
ZONED RA
TAX ID: 4629-62-1638
RAY F. WORSTER & DOROTHY
DB:517 PAGE :1648
ZONED RA
Revised 8/17/15


BRAMLEY SCHOOL RD. -SR.1100
60' PUBLIC R/W
(PLAT BOOK 35 PAGE 114)
575.49'
35 FT FRONT SETBACK
387.98'
15 FT SIDE SETBACK
159.81'
15 FT SIDE SETBACK
210.89'
15 FT SIDE SETBACK
15 FT SIDE SETBACK
559.84'
124.45'
225.64'
345.69'
50.06'
6.69 ACRES
Metal Fence w/Elect.
Concrete Sidewalk
Concrete Pad
Asphalt Drive
Shed
WELL
Found #4 Rebar
Found 1.79" IP
Found IP Bent
IPS
INV. 838.76
EX. 12" RCP
INV. 838.36
WATER DIVERSION
1"=100'
NORTH
TAX ID: 4628-73-7130
LOT 353
MOONLIGHT KARAOKE PROPERTY SR
PB: 41 PAGE:37
DB:2302 PAGE:1530
ZONED R-20 CUD
LOT 354
JEFFREY C. &
KAREN M. BARR
PB: 35 PAGE:114
DB:1918 PAGE:1986
ZONED R-20 CUD
LOT 353
RONALD P.& SHARI GAITHER
PB: 32 PAGE:114
DB:1388 PAGE:2075
ZONED R-20 CUD
LOT 352
DOYLE PAC SHAWN
PB: 32 PAGE:114
DB:1831 PAGE:501
ZONED R-20 CUD
LOT 351
JAMES P.&
SUSAN M. FIGGINS
PB: 32 PAGE:114
DB:1857 PAGE:1056
ZONED R-20 CUD
LOT 350
DORRIS & ROBERTA MCCABE
PB: 32 PAGE:114
DB:1857 PAGE:1248
ZONED R-20 CUD
LOT 349
POINT OWNERS ASSOCIATION INC
PB: 32 PAGE:114
DB:1233 PAGE:2062
ZONED R-20 CUD
LOT 348
POINT OWNERS ASSOCIATION INC
PB: 32 PAGE:101
DB:1233 PAGE:2062
ZONED R-20 CUD

DOSING CALCULATIONS

Location 1495 BRAWLEY SCHL RD
Lot No:
Address: 1495 BRAWEY SCHL RD

Approved
5/17/18
MD

No. of Bedrooms	3
Design Flow	360 $^{gal}/_{day}$
LTAR	0.300 $^{gal}/_{ft^2\,day}$
25% RED. Expansion? (YES OR NO)	YES
Supply Line Length	4 ft.
Supply Line Volume	1.44 gal.
Required Feet of 25% RED. Line	300 ft.
Amount of Line from Layout	300 ft.
Gallons per Minute	NA $^{gal}/_{min}$
Septic Tank Capacity	1000 gal.
Minimum Septic Tank Capacity	1000 gal.
Lateral Line Volume	195.9 gal.

DEPARTMENT OF HEALTH AND HUMAN SERVICES
DIVISION OF PUBLIC HEALTH, ENVIRONMENTAL HEALTH SECTION
ON-SITE WATER PROTECTION BRANCH

PROPERTY ID #: 4626823531
COUNTY: IREDELL

SOIL/SITE EVALUATION
***for* ON-SITE WASTEWATER SYSTEM**
(Complete all fields in full)

Approved 5/17/18 mD

OWNER: KYLE LARSON
ADDRESS: 209 WILD HARBOUR RD. MOORESVILLE, NC 28117
PROPOSED FACILITY: SHOP
PROPOSED DESIGN FLOW (.1949): 390 GPD
LOCATION OF SITE: 1495 BRAWLEY SCHOOL RD. MOORESVILLE, NC 28117

APPLICATION DATE 5-8-18
DATE EVALUATED: 5-7-18
PROPERTY SIZE: 6.89 AC
PROPERTY RECORDED: YES

WATER SUPPLY: ☰ Private ☐ Public ☰ Well ☐ Spring ☐ Other
EVALUATION METHOD: ☐ Auger Boring ☰ Pit ☐ Cut
TYPE OF WASTEWATER: ☰ Sewage ☐ Industrial Process ☐ Mixed

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
PIT 1	LS 6%	0-14	COMPACTED		NA	72"	MANY INC @ 29-72"	72"+	.3
		14-22	RC,S,ABK	FI,S,SP,SEXP					
		22-29	RC,M,ABK	FI,S,SP,SEXP					
		29-72	RCL,W,SBK	FR,SS,SP,SEXP					
PIT 2	LS 5%	0-15	FILL		NA	57"	COM INC @ 15-40"	73"+	.35
		14-40	RCL,M,SBK	FR,SS,SP,SEXP			MANY INC @ 40-57"		
		40-57	RCL,W,SBK	FR,SS,SP,SEXP					
		57-73	LSAP,MASS	VFR,SS,SP,SEXP					
PIT 3	LS 5%	0-11	COMPACTION		NA	65"	MANY INC @ 11-65"	65"+	.35
		11-65	RCL,W,SBK	FR,SS,SP,SEXP					
PIT 4	LS 5%	0-11	COMPACTION	FR,SS,SP,SEXP	FEW Y/BR @ 21-40"	65"	FEW MANG 11-21"	65"+	.275 Repair
		11-21	R/BRC,M,ABK	FI,S,SP,SEXP			MANY SAP @ 40-65"		
		21-40	RC,S,ABK	FI,S,SP,SEXP					
		40-65	RCL,W,SBK	FR,SS,SP,SEXP					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	PS	PS
System Type(s)	25% GRAVITY	25% GRAVITY
Site LTAR	.3	.275

OTHER FACTORS (.1946): NONE
SITE CLASSIFICATION (.1948): PS

EVALUATED BY: BEN ALDRIDGE
OTHER(S) PRESENT: JACOB CONRAD, BART ABERNATHY

COMMENTS:

SOIL/SITE EVALUATION

(Continuation Sheet-Complete all field in full)

Approved
5/17/18 MD

DEPARTMENT OF HEALTH AND HUMAN SERVICES
DIVISION OF PUBLIC HEALTH
ENVIRONMENTAL HEALTH SECTION
ON-SITE WATER PROTECTION BRANCH

PROPERTY ID #: 4626823531
DATE OF EVALUATION: 5-7-18
COUNTY: IREDELL

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	SOIL MORPHOLOGY (.1941) .1941 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS & LTAR
P 5	LS 5%	0-15	COMPACTION		NA	56"	MANY INC @ 40-56 S	73"+	.3
		15-29	BR/RSC,W,SBK	FI,S,SP,SEXP					
		29-40	RC,M,ABK	FI,S,SP,SEXP					
		40-56	CL,W,SBK	FR,SS,SP,SEXP					
		56-73	LSSAP,MASS	VFR,NS,NP,SEXP					

COMMENTS: _____

IREDELL COUNTY DEPARTMENT OF ENVIRONMENTAL HEALTH

DOCUMENTATION TO AUTHORIZE AN OWNER'S LEGAL REPRESENTATIVE

Applications for permits require the "signature of the owner or owner's legal representative" (15A NCAC 18A .1937). If the owner does not sign the application himself or herself, they can submit any one of the following documents to designate their legal representative:

Power of Attorney; Real Estate Contract, Estate executor; Bankruptcy trustee; Court ordered guardianship

In the absence of the above documentation, the property owner may provide the local health department with documentation that designates a legal representative. A property owner may:

Complete this form to document his or her legal representative, or provide his or her own form that contains the information in this form.

If there are multiple property owners, then all property owners must sign the form that designates a legal representative.

By signing a form that designates a legal representative for purposes of 15A NCAC 18A .1937, the property owner authorizes that representative to act on their behalf in matters pertaining to the application and permitting process, including signing or receiving any application, document or permit. The owner retains full responsibility to meet all permit conditions specified by the local health department

I, _____, am the legal owner(s) of the property located at _____, identified as PIN (Parcel Identification Number) _____ _____, located in Iredell County, North Carolina.

I do hereby authorize (print legal representative/company name) _____, to act as an agent on my behalf in applying for/signing/obtaining any of the documents described below

- Application for Improvement Permit (IP) / Authorization to Construct (AC)
- Improvement Permit (IP) / Authorization to Construct (AC)
- Application for soil-site evaluation (new/repair)
- Application/permit for private drinking water well/well abandonment
- Application for Compliance Inspection

I agree to abide by all decisions and/or conditions between the legal representative acting on my behalf and the Iredell County Department of Public Health, Environmental Health Division.


_____ _____ _____ _____

Signature of Owner(s) Date Signature of Witness Date

Please return this signed form to the appropriate office:

Mooresville - Environmental Health
ronda.hartsoe@iredell.nc.us
Fax: 704-662-3239
610 E. Center Avenue, Mooresville, NC 28115

Statesville - Environmental Health
adrienne.shea@co.iredell.nc.us
Fax: 704-871-3483
349 N. Center Street, Statesville, NC 28677



INTERIOR LAYOUT PLAN

SCALE: 1" = 4' 8' 16'

N

INTERIOR LAYOUT PLAN LEGEND

- 2x4 STUDWALL (NON-RATED)
- 2x4 STUDWALL (1 HOUR FIRE RESISTIVE WALL PER IBC TABLE 721.1 (2) ITEM #14-1.3 + ULP U305; SEE DETAIL #3 ON SHEET A5)
- 2x6 STUDWALL (NON-RATED)
- 2x6 STUDWALL (1 HOUR FIRE RESISTIVE WALL PER IBC TABLE 721.1 (2) ITEM #14-1.3 + ULP U305; SEE DETAIL #3 ON SHEET A5)
- 1 HOUR FIRE RESISTIVE FLOOR/CEILING ASSEMBLY PER IBC TABLE 721.1 (3) ITEM #21-1.1 (SEE DETAIL #4 ON SHEET A5)

DESIGN AND EXPLANATORY NOTES

FLOOR PLAN ACCESSIBILITY

1. SINKS.
   - A. SINKS SHALL BE MOUNTED WITH RIM NO HIGHER THAN 34 INCHES ABOVE FINISHED FLOOR.
   - B. KNEE CLEARANCE AT LEAST 27 INCHES HIGH, 30 INCHES WIDE AND 17 INCHES DEEP SHALL BE PROVIDED UNDERNEATH SINKS.
   - C. SINKS SHALL BE A MAXIMUM OF 6-1/2 INCHES DEEP.
   - D. HOT WATER AND DRAIN PIPES EXPOSED UNDER SINKS SHALL BE INSULATED OR OTHERWISE CONFIGURED TO PROTECT AGAINST CONTACT.
   - E. FAUCETS SHALL BE LEVER-OPERATED OR AUTOMATED.
   - F. A CLEAR FLOOR SPACE AT LEAST 30 INCHES WIDE BY 48 INCHES DEEP SHALL BE PROVIDED IN FRONT OF SINKS TO ALLOW FOR FORWARD APPROACH. WHEN FORWARD APPROACH IS REQUIRED, THE CLEAR FLOOR SPACE SHALL EXTEND A MAXIMUM OF 19 INCHES UNDERNEATH THE SURFACE.
2. DOORS.
   - A. DOOR HARDWARE THROUGHOUT BUILDING SHALL HAVE A SHAPE THAT IS EASY TO GRASP WITH ONE HAND AND DOES NOT REQUIRE TIGHT GRASPING, PINCHING, OR TWISTING OF THE WRIST TO OPERATE. THE FORCE REQUIRED TO ACTIVATE CONTROLS SHALL BE NO GREATER THAN 5 LB/FT
3. DINING / WORK SURFACES.
   - A. THE TOP OF THE COUNTER, TABLE, OR WORK STATION RESERVED FOR HANDICAPPED PERSONS SHALL BE 28 TO 34 INCHES ABOVE THE FINISHED FLOOR HEIGHT WITH A MINIMUM WORK SURFACE OF 36 INCHES LONG FOR SIDE APPROACH OR 30 INCHES LONG FOR FRONT APPROACH. KNEE AND TOE CLEARANCE SHALL BE PROVIDED UNDER THE WORKING SURFACES.
   - B. FLOOR SURFACES WITHIN MANEUVERING CLEARANCES SHALL HAVE A SLOPE NOT STEEPER THAN 1:48.
4. SALES AND SERVICE COUNTERS
   - A. PARALLEL APPROACH.
     1) A PORTION OF THE COUNTER SURFACE 36 INCHES MINIMUM IN LENGTH AND 36 INCHES MAXIMUM IN HEIGHT ABOVE THE FLOOR SHALL BE PROVIDED.
     2) WHERE THE COUNTER SURFACE IS LESS THAN 36 INCHES IN LENGTH, THE ENTIRE COUNTER SURFACE SHALL BE 36 INCHES MAXIMUM IN HEIGHT ABOVE THE FLOOR.
     3) A CLEAR FLOOR SPACE POSITIONED FOR A PARALLEL APPROACH ADJACENT TO THE ACCESSIBLE COUNTER SHALL BE PROVIDED
   - B. FORWARD APPROACH.
     1) A PORTION OF THE COUNTER SURFACE 30 INCHES MINIMUM IN LENGTH AND 36 INCHES MAXIMUM IN HEIGHT ABOVE THE FLOOR SHALL BE PROVIDED.
     2) A CLEAR FLOOR SPACE POSITIONED FOR A FORWARD APPROACH TO THE ACCESSIBLE COUNTER SHALL BE PROVIDED.
     3) KNEE AND TOE CLEARANCE SHALL BE PROVIDED UNDER THE ACCESSIBLE COUNTER
5. SIGNAGE.
   - A. SIGNAGE IS REQUIRED AT THE FOLLOWING LOCATIONS:
     1) AT ALL NON-ACCESSIBLE ENTRANCES INDICATING THE LOCATION OF THE ACCESSIBLE ENTRANCES
     2) SIGNS STATING "EXIT" SHALL BE PROVIDED ADJACENT TO EACH DOOR THAT LEADS TO A CORRIDOR, STAIRWELL, OR TO THE EXTERIOR OF THE BUILDING.
     3) SIGNAGE SHOWING THE INTERNATIONAL SYMBOL OF ACCESSIBILITY SHALL BE LOCATED AT ALL RESTROOMS
   - B. ALL SIGNS SHALL INCLUDE TACTILE SIGNAGE INCLUDING ANY OPTIONAL INTERIOR AND EXTERIOR SIGNAGE IDENTIFYING PERMANENT ROOMS AND SPACES
   - C. TACTILE AND BRAILLE SIGNAGE SHALL BE LOCATED 48 INCHES MINIMUM TO 60 INCHES MAXIMUM ABOVE THE FLOOR OR GROUND SURFACE, MEASURED TO THE BASE LINE OF THE HIGHEST TACTILE LETTER.
   - D. TACTILE SIGNAGE SHALL BE LOCATED AT THE LATCH SIDE OF A DOORWAY. AT DOUBLE DOORS SIGNAGE SHALL BE PROVIDED ON THE SIDE OF ANY INACTIVE LEAF. IF BOTH DOORS ARE ACTIVE THE SIGNAGE SHALL BE PLACED TO THE RIGHT SIDE OF THE DOORWAY. IF SPACE IS NOT AVAILABLE FOR SIGNAGE IN THESE LOCATIONS SIGNAGE SHALL BE LOCATED ON THE NEAREST ADJACENT WALL TO THE AREA SPECIFIED.
   - E. A MINIMUM 18 INCHES x 18 INCHES CLEAR FLOOR AREA CENTERED ON THE TACTILE SIGNAGE SHALL BE PROVIDED BEYOND THE ARC OF THE DOORWAY. SIGNAGE SHALL BE ALLOWED ON THE PUSH SIDE OF DOORS WITH CLOSERS WITHOUT HOLD OPEN DEVICES.
   - F. NEW AND EXISTING BUILDINGS SHALL HAVE APPROVED ADDRESS NUMBERS, BUILDING NUMBERS OR APPROVED BUILDING IDENTIFICATION PLACED IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE FROM THE STREET OR ROAD FRONTING THE PROPERTY.
   - G. STREET ADDRESS SHALL BE POSTED IN NOT LESS THAN 4 INCH HIGH LETTERS/NUMBERS (6 INCH RECOMMENDED) WITH A MINIMUM STROKE DEPTH OF 0.5 INCH ON THE BUILDING
6. THRESHOLDS
   - A. ALL DOORS REQUIRED TO BE ACCESSIBLE, SHALL BE PROVIDED WITH LEVER HANDLES OR PUSH/PULL HARDWARE.
   - B. ALL DETAILS SHALL CONFORM TO A117.1
   - C. ACCESSIBLE ROUTES SHALL HAVE SLOPES OF LESS THAN 1:20. CROSS SLOPES SHALL NOT EXCEED 1:48
   - D. DOOR CLOSERS AND GATE CLOSERS SHALL BE ADJUSTED SO THAT FROM AN OPEN POSITION OF 90 DEGREES, THE TIME REQUIRED TO MOVE THE DOOR TO A POSITION OF 12 DEGREES FROM THE LATCH IS 5 SECONDS MINIMUM.
   - E. THE MAXIMUM FORCE FOR PUSHING OR PULLING OPEN ACCESSIBLE INTERIOR HINGED DOORS SHALL BE 5 LB/FT.
   - F. HARDWARE REQUIRED FOR ACCESSIBLE DOOR PASSAGE SHALL BE MOUNTED 34 INCHES MINIMUM TO 48 INCHES MAXIMUM ABOVE THE FINISHED FLOOR
   - G. CHANGES IN LEVEL OF 1/4 INCH HEIGHT SHALL BE PERMITTED TO BE VERTICAL.
   - H. CHANGES IN LEVEL GREATER THAN 1/4 INCH IN HEIGHT AND NOT MORE THAN 1/2 INCH MAXIMUM HIGH SHALL BE BEVELED TO A SLOPE NO STEEPER THAN 1:2.
7. SURFACES
   - A. FLOOR SURFACE SHALL BE STABLE, FIRM AND SLIP RESISTANT.
   - B. FLOOR SURFACES OF A CLEAR FLOOR SPACE SHALL HAVE A SLOPE NOT STEEPER THAN 1:48.
8. EXTERIOR DOOR AND WINDOW LOCATIONS ARE TAKEN FROM THE EXTERIOR FACE OF THE NAILERS AND ARE TO THE CENTER OF THE DOOR AND WINDOW UNITS. VERIFY ALL DOOR, WINDOW, SKYLIGHT AND SIDELIGHT LOCATIONS WITH THE OWNER.
9. INTERIOR COMPONENTS THAT ARE PROVIDED BY MORTON BUILDINGS, INC. OR MORTON BUILDINGS, INC. SUBCONTRACTORS SHALL MEET THE FOLLOWING SPECIFICATIONS
   - A. INTERIOR DIMENSIONS ARE TAKEN FROM THE INSIDE EDGE OF THE INTERIOR STRIPPING.
   - B. INTERIOR STUDWALL DIMENSIONS ARE TAKEN FROM THE CENTERLINE OF THE STUDWALL.
   - C. STUDWALLS ARE 10 @ 2x6's @ 16" O.C. UNLESS SPECIFIED OTHERWISE.
10. ROOMS AND ENCLOSED SPACES SHALL HAVE WALL AND CEILING FINISHES WITH A MINIMUM CLASS C RATING (FLAME SPREAD INDEX 76-200 AND SMOKE DEVELOPED INDEX 0-450). CORRIDORS AND STAIRWAYS SHALL HAVE A MINIMUM CLASS B RATING (FLAME SPREAD INDEX 26-75 AND SMOKE DEVELOPED INDEX 0-450).

Acknowledgement
Plans Submitted
5/17/18
5/18/18

OFFICE: LEXINGTON, NC
JOB NO.: 173-072930

KYLE LARSON RACING, INC.
MOORESVILLE, NC

ALLIED DESIGN ARCHITECTURE & ENGINEERING GROUP, P.C.
120 S. PEDERSEN P.O. BOX 110 MORTON, IL 61550 COA # 184.001580 COA # 184.001581 PHONE NUMBER: 309-560-1108

DRAWN BY:	SISHOP
DATE:	9/17/2017
CHECKED BY:	J. WALLS
DATE:	10/18/2017
REVISED DATE:	2/23/2018
REVISED DATE:	—
REVISED DATE:	—
REVISED DATE:	—

DONALD W. [illegible] REGISTERED ARCHITECT 17907 MORTON, ILLINOIS

SCALE: AS NOTED
SHEET NO.: A2 OF A7

ROOM FINISH SCHEDULE

ROOM NUMBER	DESCRIPTION	NOMINAL SIZE	CEILING HEIGHT	FLOOR FINISH	BASE TRIM	WALL FINISH	CEILING FINISH	ROOM NUMBER
101	LOBBY	10'-5" x 21'-9"	8'-0"	STAINED & POLISHED CONCRETE	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	101
102	OFFICE	10'-5" x 12'-1"	8'-0"	STAINED & POLISHED CONCRETE	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	102
103	OFFICE/BREAKROOM	10'-5" x 11'-8"	8'-0"	STAINED & POLISHED CONCRETE	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	103
104	CLOSET	5'-0" x 4'-1"	8'-0"	STAINED & POLISHED CONCRETE	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	104
105	RESTROOM	12'-2" x 14'-4"	8'-0"	STAINED & POLISHED CONCRETE	CERAMIC COVE	MOIST. RESIST. 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED W/ 48" HIGH CERAMIC TILE	(2) LAYERS MOIST. RESIST. 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	105
106	HALLWAY	5'-0" x 41'-9"	8'-0"	STAINED & POLISHED CONCRETE	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	106
107	SHOP	7558 SF	18'-7" TO 22'-9"	SEALED CONCRETE	STEEL	HI-RIB STEEL	HI-RIB STEEL	107
108	COMPRESSOR ROOM	9'-9" x 9'-9"	8'-0"	SEALED CONCRETE	-	HI-RIB STEEL (COMMON WALL ONLY)	-	108
201	HALLWAY	144 SF	8'-0"	3 1/4" WHITE OAK	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	201
202	BEDROOM	12'-8" x 13'-10"	8'-0"	3 1/4" WHITE OAK	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	202
203	BATHROOM	17'-8" x 5'-4"	8'-0"	3 1/4" WHITE OAK	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	203
204	LAUNDRY/ BATHROOM	12'-8" x 6'-1"	8'-0"	3 1/4" WHITE OAK	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	204
205	KITCHEN	11'-0" x 17'-4"	8'-0"	3 1/4" WHITE OAK	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	205
206	GREAT ROOM	17'-7" x 24'-4"	8'-0"	3 1/4" WHITE OAK	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	206
207	BATHROOM	15'-1" x 5'-4"	8'-0"	3 1/4" WHITE OAK	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	207
208	BEDROOM	11'-1" x 13'-4"	8'-0"	3 1/4" WHITE OAK	OAK	5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	(2) LAYERS 5/8" TYPE 'X' GYP. BD., TAPED, PRIMED & PAINTED	208
209	STORAGE MEZZANINE	28'-10" x 41'-0"	9'-1" TO 13'-0"	5/4" T&G PLYWOOD	STEEL	HI-RIB STEEL	HI-RIB STEEL	209


DOOR SCHEDULE

DOOR #	QTY.	SIZE	STYLE	TYPE	FIRE RATING	GLAZING	FRAME	TRIM	CLOSER	HARDWARE/ACCESSORIES	DOOR #
1	1	6068	FIBERSTEEL	9P2	-	22" x 36" INSULATED 9-LITE	PULTRUDED FIBERGLASS	OAK	YES	LEVER LOCKSET & FIXED ASTRAGAL (RIGHT PANEL FIXED) W/ INTERCONNECTED DEADBOLT	1
2	1	3068	FIBERSTEEL	F	-	-	PULTRUDED FIBERGLASS	STEEL	YES	LEVER LOCKSET W/ INTERCONNECTED DEADBOLT	2
3	1	6068	FIBERSTEEL	F2	-	-	PULTRUDED FIBERGLASS	STEEL	YES	LEVER LOCKSET & FIXED ASTRAGAL (RIGHT PANEL FIXED) W/ INTERCONNECTED DEADBOLT	3
4	1	6068	FIBERSTEEL	F2	-	-	PULTRUDED FIBERGLASS	STEEL	YES	LEVER LOCKSET & FIXED ASTRAGAL (RIGHT PANEL FIXED) W/ INTERCONNECTED DEADBOLT	4
5	1	3068	FIBERSTEEL	F	-	-	PULTRUDED FIBERGLASS	STEEL	YES	LEVER LOCKSET W/ INTERCONNECTED DEADBOLT	5
6	1	3068	FIBERSTEEL	F	-	-	PULTRUDED FIBERGLASS	STEEL	YES	LEVER LOCKSET W/ INTERCONNECTED DEADBOLT	6
7	1	3068	FIBERSTEEL	9P	-	22" x 36" INSULATED 9-LITE	PULTRUDED FIBERGLASS	OAK	YES	LEVER LOCKSET W/ INTERCONNECTED DEADBOLT	7
8	1	3068	6 PANEL OAK	6P	60 MIN.	-	WOOD	OAK	YES	LEVER HARDWARE	8
9	1	3068	6 PANEL OAK	6P	-	-	WOOD	OAK	NO	LEVER HARDWARE	9
10	1	3068	6 PANEL OAK	6P	-	-	WOOD	OAK	NO	LEVER HARDWARE	10
11	1	3068	6 PANEL OAK	6P	-	-	WOOD	OAK	NO	LEVER HARDWARE	11
12	1	2668	6 PANEL OAK	6P	-	-	WOOD	OAK	NO	LEVER HARDWARE	12
13	1	3068	6 PANEL OAK	6P	45 MIN.	-	WOOD	OAK/STEEL	YES	LEVER HARDWARE	13
14	1	3068	6 PANEL OAK	6P	-	-	WOOD	OAK	YES	LEVER HARDWARE	14
15	1	3068	6 PANEL OAK	6P	45 MIN.	-	WOOD	OAK/STEEL	YES	LEVER HARDWARE	15
16	1	3068	6 PANEL OAK	6P	-	-	WOOD	OAK	NO	LEVER HARDWARE	16
17	1	5068	6 PANEL OAK	6P-5F	-	-	WOOD	OAK	NO	LEVER HARDWARE	17
18	1	3068	6 PANEL OAK	6P	-	-	WOOD	OAK	NO	LEVER HARDWARE	18
19	1	3068	6 PANEL OAK	6P	-	-	WOOD	OAK	NO	LEVER HARDWARE	19
20	1	3068	6 PANEL OAK	6P	-	-	WOOD	OAK	NO	LEVER HARDWARE	20
21	1	4068	6 PANEL OAK	6P-8F	-	-	WOOD	OAK	NO	LEVER HARDWARE	21
22	1	3068	6 PANEL OAK	6P	-	-	WOOD	OAK	NO	LEVER HARDWARE	22
23	1	3068	6 PANEL OAK	6P-8F	-	-	WOOD	OAK	NO	LEVER HARDWARE	23
24	1	3068	6 PANEL OAK	6P	-	-	WOOD	OAK	NO	LEVER HARDWARE	24
25	1	3068	6 PANEL OAK	6P	45 MIN.	-	WOOD	OAK	YES	LEVER HARDWARE	25
C	1	12' x 12'	SECTIONAL OVERHEAD	OH	-	(3) 24" x 8" VIEW LITES	STANDARD LIFT TRACK	STEEL	-	4" x 4" JAMB PROTECTORS	C
D	1	14' x 16'	SECTIONAL OVERHEAD	OH	-	(3) 24" x 8" VIEW LITES	STANDARD LIFT TRACK	STEEL	-	4" x 4" JAMB PROTECTORS	D
E	1	16' x 16'	SECTIONAL OVERHEAD	OH	-	(3) 24" x 8" VIEW LITES	STANDARD LIFT TRACK	STEEL	-	4" x 4" JAMB PROTECTORS	E

WINDOW SCHEDULE

WINDOW #	QTY.	SIZE	MANUFACTURER	STYLE	CATALOG #	GLAZING	FRAME	TRIM	ACCESSORIES	WINDOW #
A	2	40" x 36"	LINDSAY	FIXED	MB3430	LOW E W/ ARGON	VINYL	OAK	GRIDS BETWEEN GLASS & 1/4" x .59" OPEN LOUVERED SHUTTERS	A
A	5	40" x 60"	LINDSAY	FIXED	MB3450	LOW E W/ ARGON	VINYL	OAK	GRIDS BETWEEN GLASS & 1/4" x .59" OPEN LOUVERED SHUTTERS	A
A	3	40" x 60"	LINDSAY	FIXED	MB3450	LOW E W/ ARGON	VINYL	NONE	GRIDS BETWEEN GLASS & 1/4" x .59" OPEN LOUVERED SHUTTERS	A
A	4	40" x 60"	LINDSAY	SINGLE HUNG	MB3450	LOW E W/ ARGON	VINYL	OAK	GRIDS BETWEEN GLASS & 1/4" x .59" OPEN LOUVERED SHUTTERS	A

① - EMERGENCY ESCAPE AND RESCUE OPENING MEETING OR EXCEEDING A NET CLEAR OPENING OF 5.7 SQUARE FEET WITH A MIN NET CLEAR WIDTH OF 20" AND A NET CLEAR HEIGHT OF 24" WITH THE SILL NOT MORE THAN 44" ABOVE THE FLOOR.




MEZZANINE LAYOUT PLAN

SCALE: 1" = 8'

N

MEZZANINE LAYOUT PLAN LEGEND

- 2x4 STUDWALL (NON-RATED)
- 2x4 STUDWALL (1 HOUR FIRE RESISTIVE WALL PER IBC TABLE 721.1 (2) ITEM #14-1.5 + UL# U305; SEE DETAIL #3 ON SHEET A5)
- 2x6 STUDWALL (NON-RATED)
- 2x6 STUDWALL (1 HOUR FIRE RESISTIVE WALL PER IBC TABLE 721.1 (2) ITEM #14-1.5 + UL# U305; SEE DETAIL #3 ON SHEET A5)
- 1 HOUR FIRE RESISTIVE FLOOR/CEILING ASSEMBLY PER IBC TABLE 721.1 (3) ITEM #21-1.1 (SEE DETAIL #4 ON SHEET A5)



Acknowledgement of Plans Submittal ONLY!

Date 5/11/18

Date 5/12/18

OFFICE: LEXINGTON, NC
JOB NO. 125-072930

KYLE LARSON RACING, INC.
MOORESVILLE, NC

ALLIED DESIGN ARCHITECTURE & ENGINEERING GROUP, P.C.
1305 S. PERSHING P.O. BOX 110 MORTON, IL 61550 COA # 31966 (AR) PHONE NUMBER: 309-263-4105

DRAWN BY:	BISHOP
DATE:	9/17/2017
CHECKED BY:	J. WALLS
DATE:	10/16/2017
REVISED DATE:	2/23/2018
REVISED DATE:	—
REVISED DATE:	—
REVISED DATE:	—

SCALE: AS NOTED
SHEET NO. A3 OF A7

Ronda Hart

From: Mark Baker
Sent: Friday, May 11, 2018 10:40 AM
To: Matthew Todd; Rebecca Harper; William Allison; Richard Hoffman
Cc: Ronda Hart; Robby Wilkinson; Lorrie Moore; Deborah Williams; Amanda Horton
Subject: 1495 BRAWLEY SCHOOL / 231806

Hey everyone,
I have changed this project in MUNIS from an accessory building to a New Single Family dwelling. I have updated the square footage and fees based on a new application I received today. I received a new Zoning application as well. All are in TCM. I am also going to copy this email into TCM.

I had a conversation with Bill Goff, who is Kyle Larson's project manager, and he stated that the intention was not to have a "race shop". The building will be a home with a large garage for personal use and to store Mr. Larson's personal car collection.

Adrian Pruitt also called me and said he will be submitting a new septic application that will not include "race shop" or "employees". He had just assumed this information based on who the project was for.

Thanks,

Mark R Baker
Central Permitting Supervisor
Iredell County Development Services

PO Box 788 / 349 N Center St
Statesville NC 28687
704-878-3113 ext. 1842

mark.baker@co.iredell.nc.us