Lot 601 The Farms Phase 5 Fast Track Septic System Information

Number of Bedrooms	**4**
Basement or Crawl	**Crawl Space**
Design Flow (gpd)	**480**
Primary System Type	**25% Reduction**
LTAR (gpd)/ft2	**0.25**
Total Ft. Line	480
No. Lines	5 (See Table)
Pump Required	No
Distribution Device	Drop Boxes
Maintenance Agreement Required	No
Repair System	**25% Reduction**
Total Ft. Line	547
Repair System Loading Rate	0.25

Table: Summary of Primary and Repair Nitrification Line Specifications

Line No.	Use	Line Color	System Type	Line Length (Ft.)
1	System	Red	25% Reduction	96 endfed
2	System	Pink	25% Reduction	96 endfed
3	System	Blue	25% Reduction	96 endfed
4	System	Orange	25% Reduction	96 endfed
5	System	Red	25% Reduction	96 endfed
6	Repair	Pink	25% Reduction	113
7	Repair	Blue	25% Reduction	113
8	Repair	Orange	25% Reduction	109
9	Repair	Red	25% Reduction	107
10	Repair	Pink	25% Reduction	105
				Total System: 480'
				Total Repair: 547'

Tank	Red	1500 gal (2 compartment)
House	Blue	