DELLINGER SEPTIC TANK CO.,INC.
8151 WEBBS ROAD
DENVER,NC 28037
704-483-2868

TO WHOM IT MAY CONCERN:

IN REFERENCE TO PIEDMONT BACKHOE'S PROJECT:

OUR SEPTIC TANKS ARE MANUFACTURED WITH 3/8" REBAR 12" ON CENTER IN TOP AND CONTAIN FIBERMESH FOR ADDED STRENGTH. MY RECOMMENDATION FOR A TANK SET 4' UNDERGROUND WOULD BE TO POUR 6" OF CONCRETE ON THE TOP OF THE TANK AND EXTEND A MINIMUM OF 6" OF CONCRETE ON THE SIDES. THIS SHOULD ALL BE REINFORCED WITH 3/8" REBAR.

SINCERELY,

Gary Dellinger

GARY DELLINGER

OWNER