Lot 23 Villages at Isle of Pines Fast Track Septic System Information

Number of Bedrooms	3
Basement or Crawl	crawl space
Design Flow (gpd)	360
LTAR (gpd/ft2)	0.3
Primary System Type	LP PPBPS
No. Lines	3 @ 70'
Total Ft. Line	210
Pump Required	yes
Distribution Device	valve box with LPP dist.
Maintenance Agreement Required	yes
Repair System Type	LP PPBPS
Total Ft. Line	202
Pump Required	yes
Elevations	
Upper Line	blue 1'5"
Lower Line	yellow 6'1"
Tank	5'6"
House Corner	rt. Rear 4'2"
Reference Pt.	lot 23/24 rear corner 7'0"

Notes