


LEGEND

- Areas contain soils with 24 inches or more of useable material and have potential for conventional, modified conventional and low-pressure pipe (lpp) septic systems.
- Unsuitable areas.
- System lines.
- Repair lines.
- Temporary Bench Mark (TBM)
- Well Location.

GRAPHIC SCALE

1" = 40'

40 0 40 80

FOR PRELIMINARY PLANNING PURPOSES ONLY. ALL LOTS WILL REQUIRE FINAL APPROVAL BY THE COUNTY HEALTH DEPARTMENT ON A LOT BY LOT BASIS. THIS MAP SHOULD BY USED AS A GENERAL GUIDE, SOME ADJUSTMENTS WILL BE NECESSARY IN THE FIELD DUE TO SOIL VARIABILITY AND COMPLEX TOPOGRAPHIC FEATURES. THIS MAP ONLY REFLECTS EXISTING SOIL SUITABILITY FOR ON-SITE SEPTIC TANK SYSTEMS.

PLEASE REFER TO ATTACHED SOIL REPORT FOR ADDITIONAL SITE SPECIFIC INFORMATION

ROLLANS SOIL & ENVIRONMENTAL SERVICES
2120 GRAHAM ROAD
MOUNT ULLA, NC 28125
PHONE/FAX: (704) 278-0689
ASHLEY ROLLANS, NC LICENSED SOIL SCIENTIST
MOBILE: (704) 746-5046
EMAIL: ROLLANSFORTCJ@AOL.COM

MAP TITLE: SITE PLAN & DRAINFIELD AREAS

PROJECT NAME: PRIDE HOMES / NORMAN WOODS

LOCATION/DATE: WOODSTREAM IREDELL COUNTY, NORTH CAROLINA JUNE 2006

JOB # : 01-1005
FILE: C:\JOBS\01-1005
PROJECT MGR.: CBF
FIELD WORK: CBF & AP
DRAWN BY: CBF

CALCULATIONS

Location NORMAN WOODS

Project Number

Lot No: Lot 44

No. of Bedrooms	4	
Design Flow	480	$^{gal}/_{day}$
LTAR	0.25	$^{gal}/_{ft^2\,day}$
50% RED.? (YES OR NO)	YES	
Supply Line Length	5	ft.
Supply Line Volume	0.87	gal.
Required Feet of Line	320	ft.
Amount of Line from Layout	320	ft.
Gallons per Minute	NA	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Minimum Standard Tank Size	1000	
Lateral Line Volume	208.96	gal.
Dosing Volume	NA	gal.

Note: Dosing Volume based on70% of lateral line volume

Tank Draw Down	NA	*Generic Draw Down of 21 gal.per in.*
Pump Run Time	NA	minutes
Elevation Head	NA	ft.
Pressure Head	NA	ft.
Friction Factor	NA	ft./100 ft. *(From the interpolater.)*
Friction Head	NA	ft.
Total Dynamic Head (+15%)	NA	ft.

FRICTION FACTOR INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42