## Lot 3 Vista Bluff Septic System Information

| | | |
|---|---|---|
| **Number of Bedrooms** | **3** | |
| **Basement or Crawl** | **Basement** | |
| **Design Flow (gpd)** | **360** | |
| **Septic Tank Size** | **1000 gal. min.** | ( 2 existing tanks) |
| **Primary System Type** | **T&J Panel** | |
| **LTAR (gpd)/ft2** | **0.3** | |
| Total Ft. Line | *200 ft. | Replace 50 ft. Impacted by pool |
| No. Lines | 5 (See Site Plan) | |
| Pump Required | No | |
| Distribution Device | D-Box and one Flow Divider to the 2 - 25 ft. lines | |
| Maintenance Agreement Required | No | |
| **Repair System** | **T&J Panel** | |
| Total Ft. Line | 240+ | (200 required) |
| Repair System Loading Rate | 0.3 | |

* use 11 panels on the new 50 ft. line
The 25 ft. existing lines will use 5 of the existing panels.

**Notes:** **Use Trench Bottom Depth specified by ICHD**
**Install Per ICHD Permit and T&J Panel Speciations**