IREDELL COUNTY HEALTH DEPARTMENT

Statesville Office (704) 878-5305 | BB Mooresville Office (704) 660-3625

SEPTIC IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM

PERMIT # AP-302200

APPLICANT/OWNER: GARY FAKER

APPLICANT ADDRESS: 438 WILLIAMSON ROAD, SUITE C, MOORESVILLE, N.C. 28117

PIN # 4637043877

SITE ADDRESS: 295 RIVERWOOD ROAD, MOORESVILLE, N.C. 28117

PHONE: 704-605-2260 ALT. PHONE 704-360-2251

SITE DIRECTIONS: (S) ON 77, (R) ON 150, (L) ON MCCRARY, (R) ON RIVERWOOD, LOT ON (L)

SUBDIVISION: CLIFT

SAP CONTROLLED: ☐ YES ☑ NO

SECTION: 510 LOT # 76 LOT AREA: 0.78 AC

DESIGN FLOW: 480 GPD L.T.A.R.: 0.3

Septic Tank	1000 (gal)	STB	Date		
Pump Tank	1000 (gal)	PT	Date		
Pump Make		Model	Serial #		
# Nitrification Fields	1	# Lines	3	Linear Ft:	270FT
Trench Width	24IN	Trench Bottom Depth(Low side)	38 IN	Gravel Depth	-

☑ New System ☐ Repair ☐ Expansion System Type: I II III IV V VI

System Description: PPBPS-LPP

Repair System Description: PPBPS-LPP

Maintenance Agreement Required: ☑ YES ☐ NO

☐ GRAVITY ☑ PRESSURE

☑ Residence ☐ Business ☐ Other ☐ Slab ☑ Crawl Space ☐ Basement w/plumbing ☐ Basement w/o plumbing

No. Bedrooms 4 No. Persons 8 No. Employees —

Water Supply: ☑ Private ☐ Public ☐ Community

Comments / Conditions: INSTALL ON CONTOUR, INSTALL ON 8FT CENTERS, UTILIZE LOW-PRESSURE DISTRIBUTION, DO NOT EXCEED A TRENCH BOTTOM OF 4 6IN MAX OF PANELS WILL NEED TO BE VENTED

INSTALL TOP OF PRODUCT DEEPER THAN 16IN TO KEEP UNDER OLD WATER LINE (NOT IN SERVICE), SITE PLAN MUST REMAIN ATTACHED AT ALL TIMES OR PERMIT IS INVALID, 50FT BUFFER MUST BE MARKED

INITIAL SITE SKETCH

PLEASE SEE ATTACHED

SITE PLAN FROM

MICHAEL ATHANAS AND

ASSOCIATES, LSS #1252

AS BUILT SKETCH

AT TIME OF INSTALL, OLD WELL MUST BE ABANDONED PRIOR TO ISSUANCE OF AUTHORIZATION TO CONSTRUCT,

REMOVE WATERLINE AT INSTALLATION,

POWERLINES MUST BE RELOCATED PRIOR TO ISSUANCE OF A/C

WELL ABANDONED 12-5-2019

POWER LINES REMOVED AS OF 12-4-2019

3BR FLOOR PLANS PROVIDED

4BR SYSTEM MUST BE INSTALLED

	Date	Initials
Drain Lines Checked	5-5-20	BB
Tanks Checked	5-5-20	BB.
Pressure Manifold or Valve Box Checked	5-5-20	BB
Pressure Head Set	7/14/20	MD
Electrical Checked		
Floats Set		
Alarm Checked		
Maintenance Contract Y / N		
Comments:		

* 5-4-2020 Inspection - Tanks - Pressure line - 4 per 2 Drainlines Checked. First Line 54 Ft from neighbors well. 5-5 - Checked Bottom lines all Connections BB

COPY

Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system. CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION

☐ IMPROVEMENT PERMIT *with plat valid without expiration.* ☑ IMPROVEMENT PERMIT *with site plan valid for 60 mos.* ☑ AUTHORIZATION TO CONSTRUCT *valid for period equal to IMPROVEMENT PERMIT--not to exceed 60 mo.*

Owner / Applicant Signature: Brenda Smith Date: 12/10/19 Installed by: Specialty Septic

IMPROVEMENT PERMIT by: Burkett C. White Date: 11-25-2019 OPERATION PERMIT by: Maria Dolson Date: 7/14/2020

AUTHORIZATION TO CONSTRUCT by: Burkett C. White Date: 12-9-2019 Existing System Inspected by: Date:


FOR SEPTIC FINAL INSPECTION: CALL 704-664-3703 between 8am-9am the day the inspection is needed. Be sure to speak with an inpsector to confirm your inspection time.

plat book 15, page 9, that the ratio of precision is 1':10,000, that this map was prepared in accordance with the General Statutes of North Carolina Chapter 89C.

my hand and seal on the 15, day of OCTOBER, A.D. 20 19.

WILLIAM M. ALLEN, PLS

NORTH CAROLINA PROFESSIONAL SEAL L-3499 LAND SURVEYOR WILLIAM M. ALLEN



LAKE NORMAN

760 CONTOUR LINE PER ACTUAL FIELD SURVEY

S67°01'18"W 30.85'

S89°02'00"W 65.49'

N79°33'00"W 15.81'

S78°00'00"W 71.18'

NAIL AT BASE OF #5 REBAR

FLOOD LINE

#5 REBAR

PB. 15 PG. 9

50' BUFFER FROM THE 780 CONTOUR

PT 17.5'

ST

Proposed Well

25'

Pit 4

PROPOSED HOUSE

PROPOSED HOUSE BOX Staked

LOT 75 WILLIAM J. REEVES 614/564

220.23'

S08°42'31"E

15' SETBACK

HC 10.8'

36.6'

29.5'

80.00'

52.3'

39.8'

70.00'

50.5'

52.5'

15' SETBACK

N04°45'00"E (BASE BEARING)

209.10'

LOT 77 N. SHARON JUNE 972/2104

LOT 76 0.75 AC.

Pit 3

Pit 2

Y6

B5

W4

P3

Y2

B1

PIT6 1CHD

72.8'

76.4'

35' SETBACK

Pit 5

CVB

Pit 1

OVERHEAD POWER

PROPOSED DRIVE

B1	90' - 4.5'
Y2	90' - 5.4'
P3	90' - 6.1'
W4	95' - 7.0'
B5	95' - 7.8'
Y6	95' - 8.7'

2" Well To Be Abandoned

#4 REBAR

50' R/W

Well

NAIL AT BASE OF #4 REBAR

L=95.91'

R=265.53'

(CHORD BEARING) N72°04'35"E 95.39'

N82°23'00"E 37.97'

R/W

BM 1.7'

RIVERWOOD ROAD 60' PUBLIC R/W

PK NAIL

OLD DRIVEWAY BETWEEN PITS 1 & 3/5 & 2

Scale 1"=40'

0' 20' 40' 100'

SCALE IN FEET


NOTES

1) THIS PROPERTY MAY BE SUBJECT TO ANY EASEMENT AND/OR RIGHTS-OF-WAY OF RECORD.
2) AREA COMPUTED BY THE COORDINATE METHOD.
3) EXISTING 760' & 761' CONTOUR ELEVATION BASED ON LAKE NORMAN LAKE

LEGEND

P.P. = POWER POLE
POWER TRANS.
E.I.P. = EXISTING IRON FOUND
I.P.S. = #4 REBAR SET
R/W = RIGHT-OF-WAY
W = WELL
LP = LIGHT POLE

PLOT PLAN SURVEY




MICHAEL ATHANAS & ASSOCIATES
LICENSED SOIL SCIENTIST
561 Ennis Rd.
Weddington, NC 28173
(704) 576-3887
10/22/2019

Reference: Data Sheet for 295 Riverwood Rd, CL&T Sec 10, Lot 76
House Footprint: See attached plan
Building Setbacks: 35' front/rear, 15' side, 50' lake
Water Source: Private well
Number of Bedrooms/Daily Flow: 4/480 GPD
Proposed LTAR: 0.3 GPD/FT^2
Proposed System Type: Horizontal PPBPS
Proposed Repair System Type: Horizontal PPBPS
Distribution: Low Pressure-CVB
Flow per Orifice: 0.41 GPM
Orifice Size: 5/32"
System Flow: 25.8 GPM
Dosing Volume: 226.8 gallons
Pump Run Time: 8.8 minutes
Elevation Head: 18'
Friction Head: 2'
Pressure Head: 2'
Total Dynamic Head: 22'
Supply Line Length: 155' of 2" PVC
Septic/Pump Tank Size: 1000/1000 gallons
Proposed Trench Bottom: 40"

Line	Design Length	# of Panels	Actual Length	Elevation
Blue 1	**90'**	**21**	**95'**	**4.5'**
Yellow 2	**90'**	**21**	**95'**	**5.4'**
Pink 3	**90'**	**21**	**95'**	**6.1'**
White 4			95'	7.0'
Blue 5			95'	7.8'
Yellow 6			95'	8.7'


Initial System: 270' **Repair System:** 285'
Pump Tank: 17.5' **House Corner:** 10.8' **Benchmark:** 1.7'

Comments:
The old 2" well must be abandoned. The power poles in the drainfield must be relocated.



MICHAEL ATHANAS & ASSOCIATES
LICENSED SOIL SCIENTIST
561 Ennis Rd.
Weddington, NC 28173
(704) 576-3887
10/22/2019

Reference: Data Sheet for 295 Riverwood Rd, CL&T Sec 10, Lot 76
House Footprint: See attached plan
Building Setbacks: 35' front/rear, 15' side, 50' lake
Water Source: Private well
Number of Bedrooms/Daily Flow: 4/480 GPD
Proposed LTAR: 0.3 GPD/FT^2
Proposed System Type: PPBPS
Proposed Repair System Type: PPBPS
Distribution: Low Pressure-CVB
Flow per Orifice: 0.59 GPM
Orifice Size: 3/16"
System Flow: 37.2 GPM
Dosing Volume: 226.8 gallons
Pump Run Time: 6.1 minutes
Elevation Head: 18'
Friction Head: 5'
Pressure Head: 2'
Total Dynamic Head: 25'
Supply Line Length: 155' of 2" PVC
Septic/Pump Tank Size: 1000/1000 gallons
Proposed Trench Bottom: ~~36" maximum~~ 38" GM 11/15/2019



Line	Design Length	# of Panels	Actual Length	Elevation
Blue 1	**90'**	**21**	**95'**	**4.5'**
Yellow 2	**90'**	**21**	**95'**	**5.4'**
Pink 3	**90'**	**21**	**95'**	**6.1'**
White 4			95'	7.0'
Blue 5			95'	7.8'
Yellow 6			95'	8.7'

Initial System: 270' **Repair System:** 285'
Pump Tank: 17.5' **House Corner:** 10.8' **Benchmark:** 1.7'

Comments:
The old 2" well must be abandoned. The power poles in the drainfield must be relocated.

PROPERTY ID #: 4637043877
COUNTY: Iredell

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

OWNER: Gary Eaker APPLICATION DATE
ADDRESS: 295 Riverwood Rd, Mooresville, NC 28117 DATE EVALUATED: 10/2019
PROPOSED FACILITY: 4 BDRM PROPOSED DESIGN FLOW (.1949): 480 GPD PROPERTY SIZE: 0.75 AC
LOCATION OF SITE: 295 Riverwood Rd, CL&T SEC 10 LOT 76 PROPERTY RECORDED: 5/9/1977
WATER SUPPLY: Ξ Private ☐ Public Ξ Well ☐ Spring ☐ Other
EVALUATION METHOD: ☐ Auger Boring Ξ Pit ☐ Cut TYPE OF WASTEWATER: Ξ Sewage ☐ Industrial Process ☐ Mixed

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	SOIL MORPHOLOGY (.1941) .1941 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS & LTAR
1	LS 5%	0-3	Br CL WSBK	FR SS SP SXP	N/A	60"	N/A	N/A	PS 0.3
		3-43	R C SBK	FR SS SP SXP	OLD WATER LINE @ 16" ICHD				
		43-60	R CL WSBK	FR SS SP SXP					
2	LS 8%	0-36	R C SBK	FR SS SP SXP	N/A	70"	N/A	N/A	PS 0.3
		36-70	R CL WSBK	FR SS SP SXP	[illegible] SAPING THRUOUT OLD WATER LINE @ 16" ICHD				
3	LS 8%	0-6	Br CL WSBK	FR SS SP SXP	N/A	59"	F-C SAP	N/A	PS 0.3
		6-36	R C SBK	FR SS SP SXP	[illegible]				
		36-59	R CL WSBK	FR SS SP SXP					
4	LS 5%	0-24	R C SBK	FR SS SP SXP	N/A	65"	F-C SAP	N/A	PS 0.3
		24-65	R CL WSBK	FR SS SP SXP	NON-CONTINUES QUARTZ VEIN ICHD 30"-58"				

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	810 FT^2	855 FT^2
System Type(s)	PPBPS	PPBPS
Site LTAR	0.3	0.3

OTHER FACTORS (.1946):
SITE CLASSIFICATION (.1948): PS
EVALUATED BY: MA&A
OTHER(S) PRESENT:

COMMENTS:

SOIL/SITE EVALUATION

(Continuation Sheet)

PROPERTY ID #: _4637043877____
DATE OF EVALUATION: _____
COUNTY: __IREDELL____

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	SOIL MORPHOLOGY (.1941) .1941 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	OTHER PROFILE FACTORS .1943 SOIL DEPTH	OTHER PROFILE FACTORS .1956 SAPRO CLASS	OTHER PROFILE FACTORS .1944 RESTR HORIZ	PROFILE CLASS & LTAR
5	LS 5%	0-5	Br CL WSBK	FR SS SP SXP	N/A	58"	N/A	N/A	PS 0.3
		5-48	R C SBK	FR SS SP SXP	STANDING H_2O @ 56" ON 11-7-19 1CHD				
		48-58	R CL WSBK	FR SS SP SXP					

DEPARTMENT OF HEALTH AND HUMAN SERVICES
DIVISION OF PUBLIC HEALTH, ENVIRONMENTAL HEALTH SECTION
ON-SITE WATER PROTECTION BRANCH

Sheet 1 of 1
PROPERTY ID #: 4637043877
COUNTY: IREDELL

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM
(Complete all fields in full)

OWNER: GARY EAKER
ADDRESS: 295 RIVERWOOD ROAD, MOORESVILLE, N.C, 28117
PROPOSED FACILITY: 4BR
PROPOSED DESIGN FLOW (.1949): 480GPD
LOCATION OF SITE: 295 RIVERWOOD ROAD, MOORESVILLE, N.C, 28117
APPLICATION DATE: 10-30-19
DATE EVALUATED: 11-15-19
PROPERTY SIZE: 0.78AC
PROPERTY RECORDED: YES
WATER SUPPLY: ☑ Private ☐ Public ☑ Well ☐ Spring ☐ Other
EVALUATION METHOD: ☐ Auger Boring ☑ Pit ☐ Cut
TYPE OF WASTEWATER: ☑ Sewage ☐ Industrial Process ☐ Mixed

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	SOIL MORPHOLOGY (.1941) .1941 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS & LTAR
1	8%	0-8	GRAVEL	DRIVEWAY	MICA COMMON SAP INC THRU OUT	60"+	NA	NA	PS .3
		8-24	C, SBK	FR, S, P, SEXP					
		24-60	CL MSBK	FR, SS, SP, SEXP					
2			SEE ATTACHED						
3									
4									

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)		
System Type(s)	SEE ATTACHED	
Site LTAR		

OTHER FACTORS (.1946):
SITE CLASSIFICATION (.1948):
EVALUATED BY: FROM MAPA LSS#1251 Bryant C. Miller
OTHER(S) PRESENT:

COMMENTS:

RECEIVED OCT 3 0 2019 # ZR 000 676

IREDELL COUNTY DEPARTMENT of ENVIRONMENTAL HEALTH

APPLICATION FORM Paid $350.00 AP- 302200

Application For: ( ) New Well Permit ( ) Well Repair Permit ( ) Well Abandonment
(✓) Septic Improvement Permit ( ) Authorization to Construct ( ) Existing System Inspection ( ) Septic System Repair

THE ABOVE PERMIT DOCUMENTS WILL BECOME INVALID IF INFORMATION PROVIDED ON THIS APPLICATION IS FALSIFIED OR CHANGED, OR IF THE SITE IS ALTERED. THE IMPROVEMENT PERMIT IS VALID FOR EITHER 60 MONTHS OR WITHOUT EXPIRATION DEPENDING UPON DOCUMENTATION SUBMITTED. APPLICATION WITH SITE PLAN 60 MONTHS, APPLICATION WITH COMPLETE, SCALED PLAT WITHOUT EXPIRATION. SEE 15A NCAC 18A .1937(f) FOR DETAILS.

Page 2: *Site Plan Worksheet* form MUST accompany this application

The following optional attachments may also be submitted: (✓) Survey Plat, scaled no more than 1 inch = 60 feet
Place an (X) beside whichever is submitted if applicable ( ) Custom Site Plan, scaled no more than 1 inch = 60 feet

Applicant Information: (PRINT CLEARLY)

Applicant Name: Gary Eaker **Address:** 295 Riverwood Rd, Mooresville, NC **Zip:** 28117

Applicant Email: _____ **Phone:** Jonathan-704-650-2260 **Alt. Phone:** _____

Owner Name: Same **Address:** _____ **Zip:** _____

Owner Email: _____ **Phone:** _____ **Alt. Phone:** _____

Property Information:

Street Address: 295 Riverwood Rd

Subdivision Name: CL&T **Section/Phase:** 10 **Lot Number:** 76

Driving Directions: _____

Site Development Information: *(check or complete ALL that apply*

CHECK FOUNDATION TYPE

(✓) New Single Family Residence — Maximum Number of Bedrooms: 4 — (✓) Crawl Space Foundation
( ) New Multi-Family Residence — Maximum Number of Occupants: _____ — ( ) Concrete Slab Foundation
( ) Accessory Building — ( ) Swimming Pool — ( ) Basement with Plumbing
( ) Bedroom(s) Addition — ( ) Other Addition/Structure: _____ — ( ) Basement without Plumbing
( ) Repair to failing septic system ___ Tank ___ Drain lines Describe Problem: _____
Non-Residential Site Development: Type of Business: _____
Square Footage of Building: _____ Max. Number of Employees: _____ Max. Number of Seats/Beds/Other: _____

Water Supply: ( ) Replacement Well – Reason: _____
( ) Multi-connection Well Number of Houses: _____ Number of Persons: _____

(✓) New Well ( ) Existing Well ( ) Community Well ( ) City Water ( ) Other Public Water

Desired Septic System Type: *(you may rank in order of preference)* Year existing system installed: _____
( ) No Preference ( ) Alternative ( ) Conventional ( ) Innovative (✓) Modified Conventional ( ) Other: _____

Please answer the following to the best of your ability:

( ) Yes (✓) No Does the site contain any jurisdictional wetlands?
( ) Yes (✓) No Is any non-domestic sewage (i.e. industrial) to be generated?
( ) Yes (✓) No Is the site subject to approval by any other public agency?

I have read this application and certify that the information provided herein is true, complete, and correct. Authorized county and state officials are granted right of entry to conduct necessary inspections to determine compliance with applicable laws and rules. I understand that I am solely responsible for the proper identification and labeling of all property lines and corners and making the site accessible so that a complete site evaluation can be performed.

Signature: _____ 10/30/2019
Property owner or owner's legal representative signature (SIGNATURE REQUIRED) DATE

IREDELL COUNTY DEPARTMENT OF ENVIRONMENTAL HEALTH

DOCUMENTATION TO AUTHORIZE AN OWNER'S LEGAL REPRESENTATIVE

Applications for permits require the "signature of the owner or owner's legal representative" (15A NCAC 18A .1937). If the owner does not sign the application himself or herself, they can submit any one of the following documents to designate their legal representative:

Power of Attorney; Real Estate Contract; Estate executor; Bankruptcy trustee; Court ordered guardianship

In the absence of the above documentation, the property owner may provide the local health department with documentation that designates a legal representative. A property owner may:

Complete this form to document his or her legal representative, or provide his or her own form that contains the information in this form.

If there are multiple property owners, then all property owners must sign the form that designates a legal representative.

By signing a form that designates a legal representative for purposes of 15A NCAC 18A .1937, the property owner authorizes that representative to act on their behalf in matters pertaining to the application and permitting process, including signing or receiving any application, document or permit. The owner retains full responsibility to meet all permit conditions specified by the local health department.

I, Gary Eaker, am the legal owner(s) of the property located at 295 Riverwood Rd, Mooresville, NC 28117, identified as PIN (Parcel Identification Number) 4637043877.000, located in Iredell County, North Carolina.

I do hereby authorize (**print legal representative/company name**) Michael Athanas & Associates, to act as an agent on my behalf in applying for/signing/obtaining any of the documents described below.

- Application for Improvement Permit (IP) / Authorization to Construct (AC)
- Improvement Permit (IP) / Authorization to Construct (AC)
- Application for soil-site evaluation (new/repair)
- Application/permit for private drinking water well/well abandonment
- Application for Compliance Inspection

I agree to abide by all decisions and/or conditions between the legal representative acting on my behalf and the Iredell County Department of Public Health, Environmental Health Division.


X Gary Eaker 10-22-19 Margaret Monk 10/22/19

Signature of Owner(s) Date Signature of Witness Date


Please return this signed form to the appropriate office:

Mooresville - Environmental Health
ronda.hart@co.iredell.nc.us
Fax: 704-662-3239
610 E. Center Avenue, Mooresville, NC 28115

Statesville - Environmental Health
adrienne.shea@co.iredell.nc.us
Fax: 704-871-3483
349 N. Center Street, Statesville, NC 28677




FIRST FLOOR PLAN



BONUS OVER GARAGE PLAN

Acknowledgement Of
Plans Submittal ONLY!
Barbara C. White Date 12-9-2019
Date

A3.0



FIRST FLOOR PLAN

FLOORING

Acknowledgement Of
Plans Submittal ONLY!

_____ Date_____

_____ Date_____

Burkhart C. White 12-9-2019

A4.0

IREDELL COUNTY · NC

IREDELL COUNTY

PO Box 788
349 North Center St.
Statesville, NC 28677

APPLICATION NUMBER

302200
Issue Date: 10/30/2019

Permit Type: ZONING RESIDENTIAL - IREDELL COUNTY

Parcel Number	Street Address
4637043877.000	295 RIVERWOOD RD
Zone Code	**Jurisdiction**
RA	

Owner Information	Applicant Information
Name: EAKER GARY+DEBORAH	Name: MICHAEL ATHANAS & ASSOCIATES
Phone:	Phone: (704)576-3887

Contractor Information

Name: MICHAEL ATHANAS & ASSOCIATES
Address: 561 ENNIS RD
Phone: (704)576-3887

Project Description

SFD

Building Information

Proposed Use:
Construction Type:
Number of Stories: 0
Estimated Cost of Construction:

Heated Sq. Ft: 0
Unheated Sq. Ft: 0
Gross Sq. Ft: 0

Conditions	Fees		
	ZONING PERMIT	Amount:	$75.00
	TECHNOLOGY FEE - PLANNIN	Amount:	$2.25

Permit Details

I hereby certify that all information in this application is correct and all work will comply with the state code and all other applicable state and local laws, ordinances and regulations. The respective department will be notified of any changes in the approved plans, a change of contractor, and/or specifications for the project permitted herein. This application becomes a permit only when validated and approved.

Date: 10/30/2019

Signature of Owner/Contractor

ANY PERMIT ISSUED EXPIRES SIX (6) MONTHS AFTER ISSUANCE IF NO INSPECTIONS HAVE BEEN MADE. ANY PERMIT ISSUED SHALL EXPIRE TWELVE (12) MONTHS AFTER LAST INSPECTION IF THE WORK IS DISCONTINUED.

Permit Number	000676	TOTAL FEES:	$77.25