Thomas Wilson & Assoc. Con't:

Lots 36, 37, 39, 41-47:	These lots are provisionally suitable and will accomodate some type of ground absorption sewage disposal system.
Lot 48:	This lot is provisionally suitable and probably will need either a low pressure conventional or low pressure panel system.
Lots 38 & 40:	Each lot has a provisionally suitable area at the rear of the lot that would accomodate some type of low pressure system.
Lots 1-2: (Block B)	These lots are provisionally suitable and will accomodate some type of ground absorption sewage disposal systems.

The following lots will have to be combined in order to accomodate a sewage disposal system.

Lots 31 & 32:	System type to be determined at the time an improvements permit is requested.
Lots 33 & 34:	A low pressure panel system will be necessary and is to be located near the street and across the area where originally the lot line of 33 & 34 is shown.
Lots 35 & 1:	A low pressure panel will be necessary and is to be located near the street and across the area where the lot line of 35 and 1 is shown.
Lots 2 & 3:	A low pressure panel system will be necessary and is to be located near the street and on lot 2. Lot 3 has very limited use for repair only at the road right of way and border with lot 2.

In summary, each of these lots or combined lots classified provisionally suitable should be able to accomodate some type of system (or as specified in certain cases) for 3 bedroom single family dwellings. However, classification is subject to change depending on changes in regulations, detrimental modifications made to lots, or wells not being properly located so as to render specific areas on adjacent lots unusable.

Before any development of the sites classified provisionally suitable proceeds, improvements permits must be obtained from this department. Please contact me if you have any questions.

Sincerely,

David R. Hinson, RS.

DH:fr