Lot 1 Normandy Creek Subdivision Fast Track Septic System Information

Number of Bedrooms	**4**
Basement or Crawl	**Crawl Space**
Design Flow (gpd)	**480**
Primary System Type	**25% Reduction**
LTAR (gpd)/ft2	**0.25**
Total Ft. Line	480
No. Lines	4 (See Table)
Pump Required	No
Distribution Device	Drop Boxes
Maintenance Agreement Required	No
Repair System	**25% Reduction**
Total Ft. Line	495
Repair System Loading Rate	0.25

Table: Summary of Primary and Repair Nitrification Line Specifications

Line No.	Use	Line Color	System Type	Line Length (Ft.)
1	Repair	Red	25% Reduction	75
2	Repair	Blue	25% Reduction	123
3	System	Orange	25% Reduction	120 endfed
4	System	Pink	25% Reduction	120 endfed
5	System	White	25% Reduction	120 endfed
6	Repair	White	25% Reduction	35
7	System	Blue	25% Reduction	120 endfed
8	Repair	Blue	25% Reduction	35
9	Repair	Orange	25% Reduction	77
10	Repair	Pink	25% Reduction	80
11	Repair	NF	25% Reduction	35
12	Repair	NF	25% Reduction	35
				Total System: 480'
				Total Repair: 495'

Tank	Red	1000 gal (2 compartment)
House	Blue	

Notes: **Lot requires some shaping to remove low areas and minor gullies**
Additional repair located in back of lot