Lot 3 Normandy Creek Subdivision Fast Track

Number of Bedrooms	**4**
Basement or Crawl	**Basement with Plumbing**
Design Flow (gpd)	**480**
Primary System LTAR (gpd/ft2)	**0.325**
Primary System Type	**25% Reduction**
No. Lines	4 (See Table)
Total Linear Feet	368
Trench Width	3' min.
Trench Spacing	9' min.
Pump Required	Yes
Distribution Device	Pressure Manifold
Maintenance Agreement Required	No
Length and Diameter of Supply Pipe	240' of 2" SCH 40 PVC
Flow Rate through the system	22 gpm
Elevation head	Approx. 12.3'
Pressure head	2.0'
Friction head	1.8'
20% Contingency	3.2'
Total Head	19.3'
Pump Requirements	22 gpm @ 19.3' of head To be designed by installer.
Maximum Dosing Volume	240 gal -2.0 doses/day @ design flow
Volume of water pumped per dose	Calculated to specific tank by measure or dealer engineering specifications (1 cubic ft. of water equals 7.48 gal.)
Pump Run per dose	approx. 10.9 min.
Check Valve	Yes
Siphon Break hole	No
Repair System	**LP PPBPS**
Total Linear Feet	258
Repair Loading Rate	0.325