Bob Gido Fast Track System Specifications 2-11-14

Number of Bedrooms	4 + 2
Basement or Crawl	Crawl/Slab
Design Flow (gpd)	720
LTAR (gpd/ft2)	0.3
Septic Tank	1500 gallon existing
Primary System Type	**25% Reduction**
No. Lines	5 existing + 1 new
Total Linear Feet	500 + 100 new
Trench Width	3' min.
Trench Spacing	9' min.
Pump Required	no
Distribution Device	Serial per operation permit
Maintenance Agreement Required	No
Repair System	**LP PPBPS**
Total Linear Feet	556 shown (400 required)
Repair LTAR	0.3

Note: **Installer and ICHD shall verify all line locations, tank locations, and elevations prior to installation.**
System is to be installed according to any other ICHD requirements or policies.
These specifications are to satisfy the ICHD Fast Track LSS checklist and are not intended to represent an Engineered System Design.
Use trench depth on ICHD IP.