CALCULATIONS

Location LAKEWOOD CROSSING SUBDIVISION

Project Number 01-1089

Lot No: Lot 21

No. of Bedrooms	4	
Design Flow	480	$^{gal}/_{day}$
LTAR	.3 gpd/ft²	
25% RED.? (YES OR NO)	YES	
Supply Line Length	179	ft.
Supply Line Volume	31.146	gal.
Required Feet of Line	400	ft.
Amount of Line from Layout	400	ft.
Gallons per Minute	28.44	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Minimum Standard Tank Size	1000	
Lateral Line Volume	261.2	gal.
Dosing Volume	182.84	gal.

Note: Dosing Volume based on70% of lateral line volume

Tank Draw Down	8.7	*Generic Draw Down of 21 gal.per in.*
Pump Run Time	6.43	minutes
Elevation Head	13	ft.
Pressure Head	2	ft.
Friction Factor	1.78	ft./100 ft. *(From the interpolater.)*
Friction Head	3.19	ft.
Total Dynamic Head (+15%)	20.91	ft.

FRICTION FACTOR INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42