Lot 11 Woodleaf Subdivision Fast Track Septic System Information

Number of Bedrooms	**4**
Basement or Crawl	**Crawl Space**
Design Flow (gpd)	**480**
Primary System Type	**25% Reduction**
LTAR (gpd)/ft2	**0.25**
Total Ft. Line	490
No. Lines	7 (See Table)
Pump Required	No
Distribution Device	Drop Boxes
Maintenance Agreement Required	No
Repair System	**LP PPBPS**
Total Ft. Line	375'
Repair System Loading Rate	0.25

Table: Summary of Primary and Repair Nitrification Line Specifications

Line No.	Use	Line Color	System Type	Line Length (Ft.)
1	System	Pink	25% Reduction	70' endfed
2	System	White	25% Reduction	70' endfed
3	System	Red	25% Reduction	70' endfed
4	System	Pink	25% Reduction	70' endfed
5	System	White	25% Reduction	70' endfed
6	System	Red	25% Reduction	70' endfed
7	Repair	Orange	25% Reduction	70' endfed
8	Repair	Pink	LP PPBPS	75'
9	Repair	White	LP PPBPS	75'
10	Repair	Red	LP PPBPS	75'
11	Repair	Orange	LP PPBPS	75'
12	Repair	White	LP PPBPS	75'
				Total System: 490'
				Total Repair: 375'

Tank	Red	1000 gal (2 compartment)
House	Blue	