IREDELL COUNTY HEALTH DEPARTMENT

Statesville Office (704) 878-5305 Mooresville Office (704) 660-3625 PERMIT # 2/6981

IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM

PIN # 4639-63-8572.000

APPLICANT: TBCSC APPLICANT ADDRESS: 2524 Reliance Ave. Apex NC 27539

SITE ADDRESS: 347 S. San Agustin Dr. Mooresville NC PHONE: 704-658-8616 ALT. PHONE:

SITE DIRECTIONS: 150 W/I IR North, R Bells Crossing, TL S. San Agustin, Lot on L

SUBDIVISION: Bells Crossing SECTION: PH LOT # 155 LOT AREA: 1.290 Acre DESIGN FLOW: 600 GPD L.T.A.R.: .3

Septic Tank 1250 (gal) STB 904 Date 2-2-17
Pump Tank 1500 (gal) PT Date
Pump Make Model Serial #
Nitrification Fields 1 # Lines 7 Linear Ft: 500'
Trench Width 36" Max. Trench Bottom Depth* 32" Considered Gravel Depth N/A

☒ New System ☐ Repair ☐ Expansion System Type: I II ☒ III IV V VI
System Description: 25% Reduction - Gravity
Repair System Description: LP-PPBPS
Maintenance Agreement Required: ☐ YES ☒ NO
☒ GRAVITY ☐ PRESSURE

☒ Residence ☐ Business ☐ Other ☐ Slab ☒ Basement w/plumbing
No. Bedrooms 5 No. Persons 10 No. Employees
☐ Crawl Space ☐ Basement w/o plumbing

Water Supply: ☐ Private ☐ Public ☒ Community

Comments / Conditions: No foundation drain to be within 10' of septic drainfield. "Rough Top" is to be filled prior to issuance of OP.

INITIAL SITE SKETCH

See Attached Approved Design By BSCC

Dated APPROVED MAY 16 2016

AS BUILT SKETCH

* Divert drain to right of septic tank/drain field
* Installed as shown on attachment

Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system. CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION

☐ IMPROVEMENT PERMIT *with plat* valid without expiration. ☒ IMPROVEMENT PERMIT *with site plan* valid for 60 mos. ☒ AUTHORIZATION TO CONSTRUCT valid for period equal to IMPROVEMENT PERMIT--not to exceed 60 mo.

Owner / Applicant Signature: Date: 5-20-16 Installed by: Brian, w/ Carolina Pipe

IMPROVEMENT PERMIT by: APPROVED MAY 16 2016 OPERATION PERMIT by: Date: 7-7-17

AUTHORIZATION TO CONSTRUCT by: Date: 1-11-17 Existing System Inspected by: Date:

Health Dept. Copy - WHITE Applicant (Final Approval) - YELLOW Applicant (Conditional Approval) - PINK

LINE SCHEDULE

LINE NUMBER	COLOR	FIELD ELEVATION	LENGTH (FT)
1	BLUE	0.6	~~118~~ 118
2	RED	2.1	50
3	PINK	4.2	90
4	ORANGE	5.3	90
5	BLUE	7.5	~~120~~ 122
6	RED	8.5	66
7	PINK	10.5	66
8	ORANGE	12.2	60
9	YELLOW	14.5	60
10	PINK	16.3	28
11	ORANGE	17.7	65
12	WHITE	18.2	32
13	BLUE	19.3	60
14	GREEN	20.6	33
15	PINK	21.0	47
			885


LOT 155 BELLS CROSSING SUBDIVISION

5-BEDROOM ACCEPTED GRAVITY SYSTEM
LINES 1-7 TOTAL 501 LINEAR FEET(USE 500')
EZFLOW OR CHAMBER
30-36" MAX TRENCH DEPTH
LTAR 0.3
25% REDUCTION

5-BEDROOM LPP FED PANEL BLOCK REPAIR
LINES 8-15 TOTAL 385 LINEAR FEET
LTAR 0.3
50% REDUCTION

FOR GENERAL USE NOT A SURVEY
PRELIMINARY NOT FOR CONSTRUCTION

SOIL ANALYSIS AND APPLICATION RATES PROVIDED BY CENTRAL CAROLINA SOIL CONSULTING



OK ICHD
APPROVED MAY 16 2016

Bateman Civil Survey Company
Engineers • Surveyors • Planners
200 N. Main Street, Holly Springs, NC 27540 Ph: 919.577.1080 Fax 919.577.1081
www.batemancivilsurvey.com info@batemancivilsurvey.com
NCBELS Firm No. C-2378

MeritageHomes

LOT 155
BELLS CROSSING SUBDIVISION
MOORESVILLE, NC
IREDELL COUNTY

DATE:5/3/16 DRAWN BY: MDB CHECKED BY: TMB

DEPARTMENT OF HEALTH AND HUMAN SERVICES
DIVISION OF PUBLIC HEALTH, ENVIRONMENTAL HEALTH SECTION
ON-SITE WATER PROTECTION BRANCH

PROPERTY ID #: 8572
COUNTY: Iredell

SOIL/SITE EVALUATION
for **ON-SITE WASTEWATER SYSTEM**
(Complete all fields in full)

OWNER: Meritage Homes — APPLICATION DATE: 3/2/16
ADDRESS: Troy NC — DATE EVALUATED: 3/5/16
PROPOSED FACILITY: SFR — PROPOSED DESIGN FLOW (.1949): 600 GPD — PROPERTY SIZE: 1.290 Acre
LOCATION OF SITE: 347 S. San Agustin Dr. Mtn. NC Lot 155 — PROPERTY RECORDED: YES
WATER SUPPLY: ☐ Private ☐ Public ☑ Well ☐ Spring ☑ Other Comm.
EVALUATION METHOD: ☐ Auger Boring ☑ Pit ☐ Cut — TYPE OF WASTEWATER: ☑ Sewage ☐ Industrial Process ☐ Mixed

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	SOIL MORPHOLOGY (.1941) .1941 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS & LTAR
1	LS 10%	0-8	BSCL, WSBK	FR, SS, SP	/	16"	US Splitted Rock	16"	US
		8-16	C/CL, WSBK	FR, SS, SP					
2	CV 10%	0-18	RC, SBK	FR, SS SP	/	30"	PS C-M SAP INCL 12"-30"	/	.35
		18-30	RCL, SBK/MSBK	" " "					
		30-60	Mass L SAP	VFR, " "					
3	LS 12%	0-18	RC, SBK	FR, SS SP	/	29"	PS C-M 16"-29"	/	.3 0-18" .35 18"-60"
		18-29	RCL, WSBK	" " "					
		29-60	Mass L SAP	VFR, SS, SP					
4	LS 6%	0-16	RC, SBK	FR, SS, SP	/	21"	PS C-M SAP INCL 12"-21"	/	.3 0-21" .4 21-70"
		16-21	RCL, WSBK	V " "					
		21-70	Mass SL SAP	VFR, " "					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	PS	PS
System Type(s)	Approved	Approved
Site LTAR		

OTHER FACTORS (.1946): —
SITE CLASSIFICATION (.1948): PS
EVALUATED BY: SL
OTHER(S) PRESENT: M. Bonfield, D. Beane

COMMENTS:

SOIL/SITE EVALUATION

(Continuation Sheet-Complete all field in full)

DEPARTMENT OF HEALTH AND HUMAN SERVICES
DIVISION OF PUBLIC HEALTH
ENVIRONMENTAL HEALTH SECTION
ON-SITE WATER PROTECTION BRANCH

PROPERTY ID #: 8572
DATE OF EVALUATION: 3/5/16
COUNTY: IREDELL

LOT 155

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	SOIL MORPHOLOGY (.1941) .1941 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS & LTAR
P5	LS 15%	0-56"	RL, SBK	FR, SS, SP	/	56"	M SAP INCL 32-56"	/	.3
P6	LS 25%	0-12	RL, SBK	FR, SS, SP	/	43"	M SAP INCL. 14"-43" M QUARTZ INCL.	/	.3

COMMENTS:

RECEIVED JAN 1 1 2016

IREDELL COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
Application for IMPROVEMENT PERMIT, AUTHORIZATION TO CONSTRUCT, or EXISTING SYSTEM INSPECTION

(THE ABOVE PERMIT DOCUMENTS WILL BECOME INVALID IF INFORMATION PROVIDED ON THIS APPLICATION IS FALSIFIED OR CHANGED, OR IF THE SITE IS ALTERED. THE IMPROVEMENT PERMIT IS VALID FOR EITHER 60 MONTHS OR WITHOUT EXPIRATION DEPENDING UPON DOCUMENTATION SUBMITTED - APPLICATION WITH SITE PLAN 60 MONTHS, APPLICATION WITH COMPLETE, SCALED PLAT WITHOUT EXPIRATION. SEE 15A NCAC 18A .1937(f) FOR DETAILS)

1. APPLICATION FOR: ☐ Improvement Permit ☑ Authorization To Construct ☐ BOTH ☐ Existing System Inspection

2. Page 2: *Site Plan Worksheet* Form MUST Accompany This Application
The following optional attachments may also be submitted: ☑ Survey Plat, Scaled no more than 1 Inch = 60 Feet
Place check ( ) beside whichever is submitted if applicable ☑ Custom Site Plan, Scaled no more than 1 Inch = 60 Feet

3. Applicant Information:

Applicant Name	Mailing Address	Home Phone #	Alternate Phone #
Meritage Homes of the Carolinas, Inc	11605 North Community House Road Suite 250 Charlotte, NC 28277	704.944.8918	
Owner Name	**Mailing Address**	**Home Phone #**	**Alternate Phone #**
Meritage Homes of the Carolinas, Inc	same		

4. Property Information:

Street Address	Subdivision Name	Section/Phase and Lot Number
347 S. San Agustin Dr.	Bells Crossing	Lot 155

Driving Directions: 150 W - Right on Perth Road - Left into Bells Crossing

5. RESIDENTIAL Site Development Information: *(Check or Complete ALL that apply)*

- ☑ New, Single Family Residence
- ( ) New, Multi-Family Residence
- ☐ Expansion of Existing Septic System
- ( ) Repair To Failing Septic System
- ( ) Other

Maximum Number of Bedrooms 4
Maximum Number of Occupants 8
If Expansion, Current Number of Bedrooms ___

- ☐ Crawl Space Foundation?
- ☐ Concrete Slab Foundation?
- ☑ Basement w/Plumbing?
- ☐ Basement w/out Plumbing?

IF Non- Residential Site Development:
Type of Business
Square Footage of Building
Maximum Number of Employees
Maximum Number of Seats

6. Proposed Water Supply:

( ) New Well ( ) Existing Well ☑ Community Well ( ) City Water ( ) Other Public Water

7. Desired Septic System Type: *(You may rank in order of preference, if any)*

☐) Alternative ☑) Conventional ☐) Innovative ( ) Modified Conventional ( ) Other_Excepted__ ( ) No Preference

8. Please Answer The Following To The Best of Your Ability:

( ) Yes ☑ No Does the site contain any jurisdictional wetlands?
( ) Yes ☑ No Is any non-domestic sewage (i.e. industry) to be generated?
( ) Yes ☑ No Is the site subject to approval by any other public agency?

I have read this application and certify that the information provided herein is true, complete, and correct. Authorized county and state officials are granted right of entry to conduct necessary inspections to determine compliance with applicable laws and rules. I understand that I am solely responsible for the proper identification and labeling of all property lines and corners and making the site accessible so that a complete site evaluation can be performed.

9. Signature: _____ Robert Ruthenberg _____ 12/14/16
Property owner or owner's legal representative signature (SIGNATURE REQUIRED) DATE

SKIP (GRAZERS HOME RUN OVER FLAG)

RECEIVED MAR 18 2016

IREDELL COUNTY HEALTH DEPARTMENT ENVIRONMENTAL HEALTH DIVISION

Not Eva. Yet. 4-20-16

(THE ABOVE PERMIT DOCUMENTS WILL BECOME INVALID IF INFORMATION PROVIDED ON THIS APPLICATION IS FALSIFIED OR CHANGED, OR IF THE SITE IS ALTERED. THE IMPROVEMENT PERMIT IS VALID FOR EITHER 60 MONTHS OR WITHOUT EXPIRATION DEPENDING UPON DOCUMENTATION SUBMITTED - APPLICATION WITH SITE PLAN 60 MONTHS, APPLICATION WITH COMPLETE, SCALED PLAT WITHOUT EXPIRATION. SEE 15A NCAC 18A .1937(f) FOR DETAILS)

Paid $500.00

1. APPLICATION FOR: ✓ **Improvement Permit** ___ **Authorization To Construct** ___ **Existing System Inspection**

Paid $100.00 site revisit #216981

2. Page 2: *Site Plan Worksheet* Form MUST Accompany This Application

The following optional attachments may also be submitted: ✓ Survey Plat, Scaled no more than 1 Inch = 60 Feet; ✓ Custom Site Plan, Scaled no more than 1 Inch = 60 Feet

Place check ( ) beside whichever is submitted if applicable

3. Applicant Information:

BCSC	2524 Reliance Ave Apex NC 27539		7046588616
Applicant Name	**Mailing Address**	**Home Phone #**	**Alternate Phone #**
Meritage Homes	11605 N Community House Rd Charlotte NC 28277		
Owner Name	**Mailing Address**	**Home Phone #**	**Alternate Phone #**

4. Property Information:

347 S San Agustine	Bells Crossing	4 155
Street Address	**Subdivision Name**	**Section/Phase and Lot Number**

Driving Directions: 150 W, R onto Perth, L into Bells Crossing, L onto San Agustine Pass Ph 3 (Abbeville CT) 19th Lot on the left

5. RESIDENTIAL Site Development Information: *(Check or Complete ALL that apply)*

(✓) New, Single Family Residence
( ) New, Multi-Family Residence
( ) Expansion of Existing Septic System
Repair To Failing Septic System due to _____
( ) Other _____

Maximum Number of Bedrooms 5
Maximum Number of Occupants 10
If Expansion, Current Number of Bedrooms ___

( ) Crawl Space Foundation?
MB (✓) Concrete Slab Foundation?
(✓) Basement w/Plumbing?
( ) Basement w/out Plumbing?

IF Non- Residential Site Development:
Type of Business _____
Square Footage of Building _____
Maximum Number of Employees _____
Maximum Number of Seats _____

6. Proposed Water Supply:

( ) New Well ( ) Existing Well (✓) Community Well ( ) City Water ( ) Other Public Water

7. Desired Septic System Type: *(You may rank in order of preference, if any)* ( ) EXISTING SYSTEM installed _____ (Year)

( ) Alternative ( ) Conventional ( ) Innovative ( ) Modified Conventional (✓) Other _____

8. Please Answer The Following To The Best of Your Ability:
( ) Yes (✓) No Does the site contain any jurisdictional wetlands?
( ) Yes (✓) No Is any non-domestic sewage (i.e. industry) to be generated?
( ) Yes ( ) No Is the site subject to approval by any other public agency?

I have read this application and certify that the information provided herein is true, complete, and correct. Authorized county and state officials are granted right of entry to conduct necessary inspections to determine compliance with applicable laws and rules. I understand that I am solely responsible for the proper identification and labeling of all property lines and corners and making the site accessible so that a complete site evaluation can be performed.

9. Signature: _____ 3-18-16

Property owner or owner's legal representative signature (SIGNATURE REQUIRED) — DATE

AUTHORIZATION TO ACT AS AGENT FOR OWNER

Any application/document/permit requiring a signature must be signed by the property owner or their authorized agent. This form shall be provided by the owner to allow specified individuals to act as agents for the owner. This form allows the specified individuals to sign or receive any application/document/permit on behalf of the owner. This form allows the authorized agent to make decisions on behalf of the owner pertaining to modifications of permits in the field. It is the responsibility of the owner to assure that any/all permit conditions specified on permits issued by this Division are followed.

I, Robert Price (Meritage Homes), am the legal owner of the property located at Bells Crossing, identified as PIN(Parcel Identification Number) Lot 155, located in Iredell County, North Carolina.

I do hereby authorize (print authorized agent/company name) Bateman Civil Survey Company, Michael Benfield, Matt Burdette, _____, _____, to act as an agent on my behalf in applying for/signing/obtaining any of the documents described below.

1. Improvement Permit (IP)/ Authorization to Construct (AC).
2. Application for soil-site evaluation (new/repair).
3. Application/permit for water well/well abandonment.
4. Application for existing system.
5. Application for Improvement Permit (IP)/ Authorization to Construct (AC).

I agree to abide by any and all decisions and/or conditions between the agent acting on my behalf and the Iredell County Department of Public Health, Environmental Health Division. This form must be fully executed before the individual's specified above will be recognized as the authorized agent.

Signature of Owner — Date: 3/10/15

Signature of Witness — Date: 3/10/15

IREDELL COUNTY HEATLH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
PAGE 2: *SITE PLAN WORKSHEET*

SEE THE "SAMPLE SITE PLAN" BELOW. *INCOMPLETE SITE PLANS WILL BE RETURNED TO YOU FOR COMPLETION AND MAY RESULT IN A DELAY IN THE ISSUANCE OF YOUR SEPTIC SYSTEM PERMIT!!!*

Place an (X) beside each item as you complete the site plan:

X	**Property Line measurements are clearly identified...**
X	**All proposed structures are indicated...** *SHOW: proposed house or business footprint, wells, water lines, patios, pools and decks, and any other item that will occupy space on the site*
X	**Front and side setbacks from property line...**
X	**Preferred driveway location and configuration, preferred well location...**
X	**Area you prefer your septic system to be placed...**
X	**North arrow, or other sufficient indicator of direction...**

Circle N/A on the following if appropriate:

X	**Location of septic systems and wells within 100' of your property...**	**N/A**
X	**Location of easements and rights of ways on your property...**	**N/A**
X	**Location of any designated wetlands on the property...**	**N/A**

Signature: Rob Kelly _____ 12/14/16
***REQUIRED* property owner or owner's legal representative signature.** **DATE**

USE THIS SPACE TO DRAW YOUR SITE PLAN

Please See Attached Plot Plan and IP Documents Attached

IREDELL COUNTY HEALTH DEPARTMENT *ENVIRONMENTAL HEALTH DIVISION*:

SITE PLAN WORKSHEET

SEE THE "SAMPLE SITE PLAN" BELOW. ***INCOMPLETE SITE PLANS WILL BE RETURNED TO YOU FOR COMPLETION AND MAY RESULT IN A DELAY IN THE ISSUANCE OF YOUR SEPTIC SYSTEM PERMIT!!!***

Place an (X) beside each item as you complete the site plan:

__X__ Property Line measurements are clearly identified… **__/__ All proposed structures are indicated…**

SHOW: proposed house or business footprint, wells, water lines, patios, pools and decks, and any other item that will occupy space on the site


__X__ Front and side setbacks from property line… **__X__ Preferred driveway location and configuration, preferred well location…**

__X__ Area you prefer your septic system to be placed… **__X__ North arrow, or other sufficient indicator of direction…**

Circle N/A on the following if appropriate:

____ Location of septic systems and wells within 100' of your property… N/A

____ Location of easements and rights of ways on your property… N/A **____ Location of any designated wetlands on the property… N/A**



USE THIS SPACE TO DRAW YOUR SITE PLAN


See Attached

Signature: Will Bell

REQUIRED **property owner or owner's legal representative signature.**

3-18-16

DATE



INSET SCALE: 1"=30'

LOT INFORMATION:

PARCEL #: 4639638572.000
TOTAL LOT AREA = 1.29 AC = 56,253 SF
HOUSE = 3,039 SF
PORCH = 108 SF
SIDEWALK = 260 SF
DRIVEWAY = 1,171 SF
SCREENED PORCH = 120 SF
PROPOSED IMPERVIOUS = 4,698 SF
PERCENT IMPERVIOUS = 8.4 %

NOTE:

ALL DIMENSIONS, LOCATIONS AND FEATURES SHOWN ON THIS PLOT PLAN ARE APPROXIMATE AND ARE ONLY AN ARTISTS RENDITION, EXACT LOCATION OF ALL FEATURES ARE SUBJECT TO CHANGE AND MAY NOT BE INSTALLED EXACTLY AS SHOWN ON PLANS AND/OR IN MODELS. PLACEMENT OF HOME, DRIVEWAY, SIDEWALKS AND EXTERIOR FEATURES ARE SUBJECT TO MODIFICATION AS DEEMED NECESSARY BY FIELD PERSONNEL.

CUSTOMER _____ DATE _____

CUSTOMER _____ DATE _____

MERITAGE REPRESENTATIVE _____ DATE _____


NOTES:

1. THIS SURVEY WAS PREPARED BY BATEMAN CIVIL SURVEY CO., UNDER THE SUPERVISION OF STEVEN P. CARSON, PLS.
2. THIS PLAN HAS BEEN PREPARED FOR LAYOUT AND PERMITTING PURPOSES ONLY.
3. THIS IS NOT A BOUNDARY SURVEY. PROPERTY LINES SHOWN WERE TAKEN FROM EXISTING FIELD EVIDENCE, EXISTING DEEDS AND PLATS OF PUBLIC RECORD, AND INFORMATION SUPPLIED TO THE SURVEYOR BY THE CLIENT
4. VERTICAL DATUM IS ASSUMED. THE LATITUDE, LONGITUDE AND STATE PLANE COORDINATES, IF SHOWN, ARE GIVEN IN NORTH AMERICAN DATUM OF 1983 (NAD83).
5. FIELD EQUIPMENT USED: NIKON TOTAL STATION, EPOCH 35.
6. ALL DISTANCES ARE HORIZONTAL GROUND DISTANCES AND ALL BEARINGS ARE NORTH CAROLINA STATE PLANE COORDINATE SYSTEM UNLESS OTHERWISE SHOWN.
7. THIS MAP IS NOT A CERTIFIED SURVEY AND HAS NOT BEEN REVIEWED BY A LOCAL GOVERNMENT AGENCY FOR COMPLIANCE WITH ANY APPLICABLE LAND DEVELOPMENT REGULATIONS.
8. THE PROPERTY LIES IN ZONES "X" PER NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP NUMBER 3710463900J & 3710464900J, DATED MARCH 18, 2008.
9. ZONING IS RA.
10. ALL LOT LINES HAVE A 10' UTILITY/STORM EASEMENT ALONG LOT LINES.
11. PROPERTY OWNER: MERITAGE HOMES OF THE CAROLINAS INC.
    11605 NORTH COMMUNITY HOUSE ROAD
    CALHOUN BUILDING, STE. 250
    CHARLOTTE, NC 28277


SCALE:
1" = 50 ft.

CURVE TABLE				
CURVE	LENGTH	RADIUS	CHORD BEARING	CHORD
C54	94.06'	725.00'	S19°08'08"E	93.99'

LINE TABLE		
L47	N05°57'28"E	10.95'
L48	N11°47'13"W	33.44'
L49	N08°13'13"W	37.20'
L50	N01°33'02"W	45.40'
L51	N23°54'29"W	28.78'
L52	N27°23'07"E	42.95'
L53	N23°30'20"E	26.86'



Bateman Civil Survey Company
Engineers • Surveyors • Planners
2524 Reliance Avenue, Apex, NC 27539 Ph: 919.577.1080 Fax: 919.577.1081
www.batemancivilsurvey.com info@batemancivilsurvey.com
NCBELS Firm No. C-2378



VICINITY MAP

(Not to Scale)

LEGEND

PO = PORCH
CP = COVERED PORCH
P = CONCRETE PATIO
WD = WOOD DECK
SW = SIDEWALK
DW = CONC DRIVEWAY
⊗ = COMPUTED POINT
○ = IRON PIPE FOUND
● = IRON PIPE SET
● = DRILL HOLE FOUND
WM = WATER METER
CO = CLEAN OUT
AC = AIR CONDITIONER
S = SEWER MANHOLE
EB = ELECTRIC BOX
CB = CABLE BOX
TP = TELEPHONE PEDESTAL
CI = CURB INLET
SP = SCREENED PORCH
☼ = LIGHT POLE

BUILDING SETBACKS:

FRONT = 35 ft
SIDE = 15 ft
REAR = 35 ft
SIDE STREET = 25 ft
LAKE BUFFER = 50ft

I hereby certify that this map is correct and that the building lies wholly on the lot and that there are no visible encroachments on said lot.

PRELIMINARY

Steven P. Carson, PLS 4752
Date

This map is of an existing parcel of land and is only intended for the parties and purposes shown. This map not for recordation. No title report provided.

APPROVAL FOR STAKING:

THIS PLOT PLAN AS PREPARED BY BATEMAN CIVIL SURVEY CO., IS CORRECT AND IS HEREBY APPROVED FOR STAKING ON THE DATE AS SHOWN BELOW.

MERITAGE HOMES REPRESENTATIVE _____ DATE _____

PRELIMINARY PLOT PLAN

FOR

MeritageHomes

BELLS CROSSING - PHASE FOUR - LOT 155
347 SOUTH SAN AGUSTIN DRIVE, MOORESVILLE, NC
DAVIDSON TOWNSHIP, IREDELL COUNTY

DATE: 12/15/16 DRAWN BY: DMH CHECKED BY: SPC


REF: PB 63, PGS 146-151 BCS# 120314 SCALE: 1" = 50'

P:\2012 MLS\120314 Bells Phase 4\dwg\120314 Bells PH4 Plat MLS.dwg, 12/15/2016 4:25:41 PM, dhunter

Acknowledgement of
Plans Submittal ONLY!

Date 1-11-17

Date 1-11-17



Optional Walkout Basement - C

0 2' 4' 8'

FOUNDATION NOTES

SCHE_FOUNDATION

1. STRUCTURAL FOUNDATION PLANS SHALL BE BY OTHERS. SEE STRUCTURAL FOUNDATION AND FRAMING PLANS FOR STEEL COLUMN, STEEL BEAM, WOOD POST SIZES, AND DIMENSIONS.
2. DROP TOP OF FOUNDATION AT GARAGE DOOR.
3. EMERGENCY EGRESS: WINDOWS SHALL COMPLY WITH GOVERNING FIRE & BUILDING CODES. MAXIMUM SILL HEIGHT OF EGRESS WINDOW SHALL NOT BE MORE THAN 44" A.F.F.
4. WINDOW WELL AS SPECIFIED BY BUILDER. CLEAR DIMENSIONS OF WELL SHALL BE 36"x36" MINIMUM W/ LADDER AT EGRESS WINDOWS.
5. DROP TOP OF FOUNDATION AT PORCH STOOP.
6. LINE OF FRAMING ABOVE.
7. LINE OF STOOP ABOVE.
8. WINDWALL
9. SUMP PIT LOCATION AS REQUIRED BY SOILS ENGINEER.
10. 30"x30" CRAWL SPACE ACCESS PANEL, AS REQUIRED BY CODE.
11. APPLY 10 MIL. POLYVINYL GROUND COVER OVER FINISH GRADE OF CRAWL SPACE, OR PER BUILDERS SPECIFICATIONS. INSULATE PER RES. CHECK REQUIREMENTS.
12. MECHANICAL CRAWL SPACE VENTILATION PER LOCAL CODE.
13. OPTIONAL 3 WIRE SHELF LINEN
14. OPTIONAL WIRE SHELVING PER BUILDER SPEC.
15. OPTIONAL VANITY
16. FLOOR DRAIN
17. BEAM POCKET
18. LINE OF SLAB ABOVE.
19. PROVIDE MIN. 1/2" GYPSUM BOARD ON WALLS UNDER STAIR SURFACE, AND ON SOFFITS OF ENCLOSED ACCESSIBLE SPACE UNDER STAIRS.
20. STANDARD BEARING WALL

FLOOR PLAN NOTES:

SCHE_FLOOR

8 THE FOLLOWING KEYNOTES REFERENCE THE SYMBOLS AS SHOWN ON PLANS

1. IF RAILING / GUARDRAIL IS PROVIDED, ALL RAILING / GUARDRAIL BALUSTERS TO BE SPACED SUCH THAT A 4" SPHERE CANNOT PASS BETWEEN BALUSTERS. RAILING/HANDRAILS ARE TO BE AT A 34" MINIMUM TO 38" MAXIMUM HEIGHT A.F.F. FOR STAIRS AND 36" MINIMUM ON HORIZONTAL SURFACE GUARDS.
2. LINE OF OVERHEAD GARAGE DOOR IN OPEN POSITION.
3. SLOPE GARAGE FLOOR 1/8" PER FOOT TOWARD OVERHEAD GARAGE DOOR OPENING.
4. FIREPLACE, AS SPECIFIED BY BUILDER. INSTALL PER MANUFACTURERS SPECIFICATIONS. ALL FACTORY BUILT FIREPLACES SHALL COMPLY WITH LOCAL CODES
5. SINK W/ GARBAGE DISPOSAL
6. DISHWASHER
7. RANGE
8. COOK TOP
9. OVEN
10. REFRIGERATOR SPACE.
11. PANTRY
12. PROFESSIONAL SINK
13. SHOWER (SIZE AS NOTED)
14. VIF
15. 42" X 60" TUB 20" TO TOP OF DECKING
16. 60"X 60" CORNER TUB
17. 30" X 60" SHOWER
18. 32" X 60" SHOWER
19. LINEN SHELVING PER BUILDER SPECS.)
20. WASHER SPACE
21. DRYER, VENT
22. OPTIONAL LAUNDRY SINK.
23. PROVIDE NON-COMBUSTIBLE PLATFORM ELEVATED 8" ABOVE GARAGE FLOOR FOR WATER HEATER.
24. 5 SHELVES PER BUILDER SPECS.
25. 60"L AND SHELF PER LINEN SPEC
26. ATTIC ACCESS (22 1/2"x30" UNO.)
27. ATTIC ACCESS W/ STAIRS (25 1/2"x54 1/2")
28. GYPSUM BOARD SOFFIT @ 8'-0" AT HVAC FLOOR & 1'-0" AT UPPER FLOOR UNO.
29. GYPSUM BOARD ARCH @ 1'-2" TO 8'-0".
30. GYPSUM BOARD LOW WALL, 36" A.F.F. (UNO.) W/ MDF CAP.
31. SOFFIT, REFER TO EXTERIOR ELEVATIONS FOR HEIGHTS & ARCHITECTURAL DETAILS FOR FINISH.
32. PLANT SHELF, SEE EXTERIOR ELEVATIONS.
33. WALL WALL W/ WOOD CAP OR OPTIONAL LOW WALL WITH RAILING ABOVE.
34. PORCH RAIL, SEE ELEVATION.
35. 36"x36" CONCRETE STOOP.
36. 8x8 BEAM.
37. OPTIONAL UPPER CABINETS.
38. OPTIONAL CABINETS.
39. OPTIONAL COFFERED CEILING @ 8'-6" PER BUILDER SPEC.
40. LINE OF FRAMING ABOVE.
41. LINE OF FRAMING WALL BELOW.
42. 2x4 LOW WALL 42" A.F.F.
43. 2x6 LOW WALL 42" A.F.F.
44. ART NICHE
45. HORIZONTAL LAUNDRY CHUTE
46. LOW WALL 24" A.F.F.
47. GYPSUM BOARD ARCH @ 8'-0" TO 8'-6"
48. LOW WALL 30" A.F.F.
49. NO HARD LATCH OR LOCKING KNOB

TYPICAL CONSTRUCTION ASSEMBLIES:

A. TYPICAL ROOF CONSTRUCTION:
ASPHALT ROOF SHINGLES.

B. TYPICAL FRAME FLOOR CONSTRUCTION:
FINISH FLOORING ON 3/4" TONGUE & GROOVE FLOOR SHEATHING ON FLOOR TRUSSES OR FLOOR JOISTS AS NOTED ON STRUCTURAL DRAWINGS.

C. SLAB ON GRADE FLOOR CONSTRUCTION:
4" CONCRETE SLAB, EXCEPT AS SPECIFIED BY SOIL REPORT, AND STRUCTURAL ENGINEER. INCLUDE VAPOR BARRIER PER SECTION N.C.R.C.

D. WINDOWS:
A. ALL WINDOWS SHALL COMPLY WITH MINIMUM STANDARDS OUTLINED IN APPLICABLE RES. CHECKS.
B. WINDOW SUPPLIER TO VERIFY AT LEAST ONE WINDOW IN ALL BEDROOMS TO HAVE A CLEAR EGRESS OPENING OF 5.7 SQ. FT. MIN MIN. DIMENSION OF 24" IN HEIGHT AND 20" IN WIDTH, SILL HEIGHT NOT GREATER THAN 44" ABOVE FLOOR.
C. TYPICAL WINDOW HEAD HEIGHT:
7'-0" A.F.F @ 8'-1 1/8" PLATE HEIGHT (UNO.)
8'-0" A.F.F @ 9'-1 1/8" PLATE HEIGHT (UNO.)

E. ELECTRICAL:
ALL ELECTRICAL AND MECHANICAL EQUIPMENT & METERS ARE SUBJECT TO RELOCATION DUE TO FIELD CONDITIONS. CONTRACTOR TO VERIFY.

F. VENTS:
PROVIDE BACK DRAFT DAMPERS @ DRYER VENT, HOOD VENT, & EXHAUST FANS.

G. STONE SILLS:
INSTALL PER LOCAL CODE.

H. DIMENSIONS ARE TO THE FACE OF STUD, UNO.

I. ALL EXTERIOR DIMENSIONS ARE TO FACE OF STUDS UNLESS OTHERWISE NOTED.

M. ALL ANGLED PARTITIONS ARE 45 DEGREES UNLESS OTHERWISE NOTED.

N. BRICK SILLS:
INSTALL PER LOCAL CODE.

ISSUE DATE: 01/17/2014
REVISIONS

5400 Trinity Road
Suite 107
Raleigh,
North Carolina 27607
919-322-2285 Phone

Meritage Homes

Meritage Homes

BSB DESIGN


www.bsbdesign.com
4021 Westerre Parkway, Suite 209
West Des Moines, Iowa 50266
515.633.0467

JOB NO. 93210228 PROJ. MGR. JF
DRAWN: DESIGNER: JF/JG

WALKOUT BASEMENT PLAN - C

259 - 3740


A0.1C




Main Floor Plan - Opt Kitchen



Main Floor Plan - Opt O.E.




Main Floor Plan
Opt Fireplace



Opt. Owner's Shower
Main Floor Plan

SQUARE FOOTAGES	
0	
MAIN FLOOR	2356
UPPER FLOOR	1421
BONUS ROOM	0
FINISHED BASEMENT	1,186
UNFINISHED BASEMENT	1,070
GARAGE	418
PORCH	105
DECK	0
OPT EXTENDED DECK	301
OPT SCREEN PORCH	301
TOTAL	5,586



Main Floor Plan - C

ALL EXTERIOR HOUSE WALLS MAY BE OPTIONAL 2X6 STUD WALLS - SEE STRUCTURAL PLANS FOR DETAILS.

FLOOR PLAN NOTES:

[NOTE_FLOOR]

0 THE FOLLOWING KEYNOTES REFERENCE THE SYMBOLS AS SHOWN ON PLANS.

1. 9" RAILING / GUARDRAIL IS PROVIDED. ALL RAILING / GUARDRAIL BALUSTERS TO BE SPACED SUCH THAT A 4" SPHERE CANNOT PASS BETWEEN BALUSTERS. RAILING/HANDRAILS ARE TO BE AT A 34" MINIMUM TO 38" MAXIMUM HEIGHT A.F.F. FOR STAIRS AND 36" MINIMUM ON HORIZONTAL SURFACE GUARDS.
2. LINE OF OVERHEAD GARAGE DOOR IN OPEN POSITION.
3. SLOPE GARAGE FLOOR 1/8" PER FOOT TOWARD OVERHEAD GARAGE DOOR OPENING.
4. FIREPLACE, AS SPECIFIED BY BUILDER. INSTALL PER MANUFACTURERS SPECIFICATIONS. ALL FACTORY BUILT FIREPLACES SHALL COMPLY WITH LOCAL CODES.
5. SINK W/ GARBAGE DISPOSAL
6. DISHWASHER
7. RANGE
8. COOK TOP
9. OVEN
10. REFRIGERATOR SPACE.
11. PANTRY
12. PEDESTAL SINK
13. SHOWER (SIZE AS NOTED)
14. [illegible]
15. 42" X 60" TUB 21" TO TOP OF DECKING
16. 60"X 60" STONED TUB
17. 30" X 60" TUB/SHOWER
18. 32" X 60" TUB/SHOWER
19. LINEN SHELVING PER BUILDER SPECS.)
20. WASHER SPACE
21. DRYER, VENT
22. OPTIONAL LAUNDRY SINK.
23. PROVIDE NON-COMBUSTIBLE PLATFORM ELEVATED 6" ABOVE GARAGE FLOOR FOR WATER HEATER.
24. 5 SHELVES PER BUILDER SPECS.
25. [illegible]
26. ATTIC ACCESS (22 1/2"x32" U.N.O.)
27. ATTIC ACCESS W/ STAIRS (25 1/2"x54 1/2")
28. GYPSUM BOARD CEILING @ 9'-0" HT MAIN FLOOR & 7'-0" AT UPPER FLOOR U.N.O.
29. GYPSUM BOARD ARCH @ 1'-2" TO 8'-0".
30. GYPSUM BOARD LOW WALL, 36" A.F.F. U.N.O. W/ HDF CAP.
31. SOFFIT, REFER TO EXTERIOR ELEVATIONS FOR HEIGHTS & ARCHITECTURAL DETAILS FOR FINISH.
32. PLANT SHELF, SEE EXTERIOR ELEVATIONS.
33. HALF WALL W/ WOOD CAP OR OPTIONAL LOW WALL WITH RAILING ABOVE.
34. PORCH RAIL, SEE ELEVATION.
35. 36"x36" CONCRETE STOOP.
36. 8x8 BEAM.
37. OPTIONAL UPPER CABINETS.
38. OPTIONAL CABINETS.
39. OPTIONAL COFFERED CEILING @ 8'-6" PER BUILDER SPEC.
40. LINE OF FRAMING ABOVE.
41. LINE OF FRAMING WALL BELOW.
42. 2X4 LOW WALL 42" A.F.F.
43. 2X6 LOW WALL 42" A.F.F.
44. ART NICHE
45. HORIZONTAL LAUNDRY CHUTE
46. LOW WALL 34" A.F.F.
47. GYPSUM BOARD ARCH @ 8'-0" TO 8'-6"
48. LOW WALL 32" A.F.F.
49. NO HARD LATCH OR LOCKING KNOB

TYPICAL CONSTRUCTION ASSEMBLIES:

A. TYPICAL ROOF CONSTRUCTION:
ASPHALT ROOF SHINGLES

B. TYPICAL FRAME FLOOR CONSTRUCTION:
FINISH FLOORING ON 3/4" T&G OR 1 GROOVE FLOOR SHEATHING ON FLOOR TRUSSES OR FLOOR JOISTS AS NOTED ON STRUCTURAL DRAWINGS.

C. SLAB ON GRADE FLOOR CONSTRUCTION:
4" CONCRETE SLAB, EXCEPT AS SPECIFIED BY SOIL REPORT AND STRUCTURAL ENGINEER. INCLUDE VAPOR BARRIER PER SECTION N, C, 3 a.

D. WINDOWS:
A. ALL WINDOWS SHALL COMPLY WITH MINIMUM STANDARDS OUTLINED IN APPLICABLE RES. CHECKS.
B. WINDOW SUPPLIER TO VERIFY AT LEAST ONE WINDOW IN ALL BEDROOMS TO HAVE A CLEAR EGRESS OPENING OF 5.7 SQ. FT. WITH MIN. DIMENSION OF 24" IN HEIGHT AND 20" IN WIDTH SILL HEIGHT NOT GREATER THAN 44" ABOVE FLOOR.
C. TYPICAL WINDOW HEAD HEIGHT:
7'-0" A.F.F. @ 8'-1 1/8" PLATE HEIGHT (U.N.O.)
8'-0" A.F.F. @ 9'-1 1/8" PLATE HEIGHT (U.N.O.)

E. ELECTRICAL:
ALL ELECTRICAL AND MECHANICAL EQUIPMENT & METERS ARE SUBJECT TO RELOCATION DUE TO FIELD CONDITIONS/ CONTRACTOR TO VERIFY.

F. HVAC:
PROVIDE BACK DRAFT DAMPERS @ DRYER VENT, HOOD VENT, & EXHAUST FANS.

G. STONE SILLS:
INSTALL PER LOCAL CODE.

H. DIMENSIONS ARE TO THE FACE OF STUD, U.N.O.

I. ALL EXTERIOR DIMENSIONS ARE TO FACE OF SHEATHING UNLESS OTHERWISE NOTED.

J. ALL ANGLED PARTITIONS ARE 45 DEGREES UNLESS OTHERWISE NOTED.

K. [illegible]

L. INSULATION:
INSTALL PER LOCAL CODE.

Acknowledgement of Plans Submittal ONLY!

Date 1-11-17

Date 1-11-17

ISSUE DATE: 01/17/2014
REVISIONS

5400 Trinity Road
Suite 107
Raleigh,
North Carolina 27607
919-322-2285 Phone

Meritage Homes

Meritage Homes

BSB DESIGN

www.bsbdesign.com
6021 Westcott Parkway, Suite 208
West Des Moines, Iowa 50266
515.222.2323

JOB NO: 03.12035 PROJ MGR: JT
DRAWN: DESIGNER: SF-JD

MAIN FLOOR PLAN - C


259 - 3740

A2.1C

Acknowledgement of
Plans Submittal ONLY!

Date 1-11-17


Date 1-11-17




Opt. Storage - C



Opt. Hobby - C



Opt. Shower - Bath 2



Upper Floor Plan - C

ALL EXTERIOR HOUSE WALLS MAY BE OPTIONAL 2X6 STUD WALLS - SEE STRUCTURAL PLANS FOR DETAILS.

SQUARE FOOTAGES	
0	
MAIN FLOOR	2756
UPPER FLOOR	1421
SUBTOTAL	4177
FINISHED BASEMENT	1268
UNFINISHED BASEMENT	1070
GARAGE	439
PORCH	326
DECK	00
OPT EXTENDED DECK	307
OPT SCREEN PORCH	307
TOTAL	3566

FLOOR PLAN NOTES:

(BOTH FLOORS)

1. THE FOLLOWING KEYNOTES REFERENCE THE SYMBOLS AS SHOWN ON PLANS:
2. IF RAILING / GUARDRAIL IS PROVIDED, ALL RAILING / GUARDRAIL BALUSTERS TO BE SPACED SUCH THAT A 4" SPHERE CANNOT PASS BETWEEN BALUSTERS. RAILING/HANDRAILS ARE TO BE AT A 34" MINIMUM TO 36" MAXIMUM HEIGHT A.F.F. FOR STAIRS AND 36" MINIMUM ON HORIZONTAL SURFACE GUARDS.
3. LINE OF OVERHEAD GARAGE DOOR IN OPEN POSITION.
4. SLOPE GARAGE FLOOR 1/8" PER FOOT TOWARD OVERHEAD GARAGE DOOR OPENING.
5. FIREPLACE, AS SPECIFIED BY BUILDER. INSTALL PER MANUFACTURERS SPECIFICATIONS. ALL FACTORY BUILT FIREPLACES SHALL COMPLY WITH LOCAL CODES.
6. SINK W/ GARBAGE DISPOSAL
7. DISHWASHER
8. RANGE
9. COOK TOP
10. OVEN
11. REFRIGERATOR SPACE.
12. PANTRY
13. PEDESTAL SINK.
14. SHOWER (SIZE AS NOTED)
15. N/A
16. 42" X 80" TUB 20" TO TOP OF DECKING
17. 60" X 60" CORNER SHOWER
18. 30" X 60" TUB/SHOWER
19. 32" X 60" TUB/SHOWER
20. LINEN SHELVING PER BUILDER SPECS.)
21. WASHER SPACE
22. DRYER, VENT
23. OPTIONAL LAUNDRY SINK.
24. PROVIDE NON-COMBUSTIBLE PLATFORM ELEVATED 8" ABOVE GARAGE FLOOR FOR WATER HEATER.
25. 5 SHELVES PER BUILDER SPECS.
26. ~~ATTIC ACCESS (22 1/2"x30" MIN.).~~
27. ATTIC ACCESS W/ STAIRS (25 1/2"x54 1/2")
28. ~~SYPSUM BOARD SOFFIT @ 8'-0" A.F.F. MAX FLOOR & 7'-0" AT UPPER FLOOR MIN.~~
29. GYPSUM BOARD ARCH @ 11'-2" TO 8'-0".
30. GYPSUM BOARD LOW HALL, 38" A.F.F. (MIN.) W/ MDF CAP.
31. SOFFIT, REFER TO EXTERIOR ELEVATIONS FOR HEIGHTS & ARCHITECTURAL DETAILS FOR FINISH.
32. PLANT SHELF, SEE EXTERIOR ELEVATIONS.
33. HALF WALL W/ WOOD CAP OR OPTIONAL LOW WALL WITH RAILING ABOVE.
34. PORCH RAIL, SEE ELEVATION.
35. 36"x36" CONCRETE STOOP.
36. 8x8 BEAM.
37. OPTIONAL UPPER CABINETS.
38. OPTIONAL CABINETS.
39. OPTIONAL SOFFERED CEILING @ 8'-0" PER BUILDER SPEC.
40. LINE OF FRAMING ABOVE.
41. LINE OF FRAMING WALL BELOW.
42. 2X4 LOW WALL 42" A.F.F.
43. 2X8 LOW WALL 42" A.F.F.
44. ART NICHE
45. HORIZONTAL LAUNDRY CHUTE
46. LOW WALL <24" A.F.F.
47. GYPSUM BOARD ARCH @ 8'-0" TO 8'-6"
48. LOW WALL 32" A.F.F.
49. NO HARD LATCH OR LOCKING KNOBS

TYPICAL CONSTRUCTION ASSEMBLIES:

A. TYPICAL ROOF CONSTRUCTION.
ASPHALT ROOF SHINGLES

B. TYPICAL FRAME FLOOR CONSTRUCTION.
T&G FLOORING OR 3/4" TONGUE & GROOVE FLOOR SHEATHING ON FLOOR TRUSSES OR FLOOR JOISTS AS NOTED OR STRUCTURAL DRAWINGS.

C. SLAB ON GRADE FLOOR CONSTRUCTION.
4" CONCRETE SLAB, EXCEPT AS SPECIFIED BY SOIL REPORT AND STRUCTURAL ENGINEER. INCLUDE VAPOR BARRIER PER SECTION N, G, 3, a.

D. WINDOWS.
A. ALL WINDOWS SHALL COMPLY WITH MINIMUM STANDARDS OUTLINED IN APPLICABLE RES. CHECKS.
B. WINDOW SUPPLIER TO VERIFY AT LEAST ONE WINDOW IN ALL BEDROOMS TO HAVE A CLEAR EGRESS OPENING OF 5.7 SQ. FT. WITH MIN. DIMENSION OF 24" IN HEIGHT AND 20" IN WIDTH. SILL HEIGHT NOT GREATER THAN 44" ABOVE FLOOR.
C. TYPICAL WINDOW HEAD HEIGHT:
7'-0" A.F.F. @ 8'-1 1/8" PLATE HEIGHT (MAIN)
8'-0" A.F.F. @ 9'-1 1/8" PLATE HEIGHT (MAIN)

E. ELECTRICAL.
ALL ELECTRICAL AND MECHANICAL EQUIPMENT & METERS ARE SUBJECT TO RELOCATION DUE TO FIELD CONDITIONS. CONTRACTOR TO VERIFY.

F. VENT.
PROVIDE DRYER DRAFT DAMPERS @ DRYER VENT, HOOD VENT, & EXHAUST FANS.

G. STONE SILLS.
INSTALL PER LOCAL CODE.

H. DIMENSIONS ARE TO THE FACE OF STUD, U.N.O.

I. ALL EXTERIOR DIMENSIONS ARE TO FACE OF STUDS UNLESS OTHERWISE NOTED.

J. ALL ANGLED PARTITIONS ARE 45 DEGREES UNLESS OTHERWISE NOTED.

K. DECK RAILING.
INSTALL PER LOCAL CODE.

ISSUE DATE: 01/17/2014

5400 Trinity Road
Suite 107
Raleigh,
North Carolina 27607
919-322-2295 Phone

Meritage Homes

Meritage Homes

BSB DESIGN

www.bsbdesign.com
4521 Wisdom Parkway, Suite 258
West One Metrex, Reno, NV89518
775.972.3393

JOB NO: 03/12035 PROJECT: 2
DRAWN: DESIGNER: JF-JD

UPPER FLOOR PLAN - C

259 - 3740

A2.2C

Lot 155

IREDELL COUNTY

PO Box 788
349 North Center St.
Statesville, NC 28677

APPLICATION NUMBER
216981
Issue Date: 03/02/2016

ZONING PERMIT

Parcel Number	Street Address	Jurisdiction
4639638572.000	3475 SAN AGUSTIN DRIVE, MOORESVILLE, NC	IREDELL COUNTY

Owner Information	Applicant Information
Owner: MERITAGE HOMES	Applicant: MERITAGE HOMES
Address: 11605 N COMMUNITY HOUSE RD. #250 CHARLOTTE, NC 28277	Address: 11605 N COMMUNITY HOUSE RD. #250 CHARLOTTE, NC 28277
Phone: 704-944-8933	Phone: 704-944-8933

Use Requested	Zone Code
SFD	RA

Lot Acreage	F Setback	B Setback	L Setback	R Setback	Watershed	Flood Zone
1.290	35.00	50.00	15.00	15.00	CACL	AE

Remarks:

PAID
✓7050995 7725
✓7050997 500.00
3-4-16

The applicant certifies that there are no deed restrictions, contractual agreements or governmental regulations of any kind that interfere with or prohibit the use of the property or the use for which this permit is requested. The applicant further acknowledges that enforcement of deed restrictions, plat conditions and other contractual agreements will not be undertaken by Iredell County and is the sole responsibility of the affected parties.

Applicant: _____ Date: _____

Permit Number	61687	TOTAL FEES:	$ 77.25