25% REDUCTION SYSTEM
FOR WASTEWATER TREATMENT

Owner:	Bells Crossing, LLC
Address:	127B Promenade Dr. Mooresville, NC 28117
Phone:	704 361 1084
County:	Iredell
Location:	BELLS CROSSING LOT 77
Source of Wastewater Flow:	4 Bedroom Single Family Residence
Estimated Daily Wastewater Production:	480 gpd
System Flow:	N/A

Design Specifications

Drainfield Size:	400
Loading Rate:	0.3
Depth of Gravel in Trench:	NA (25% reduction)
Gravel Size:	NA (25% reduction)
Trench Depth:	36 in.
Trench Width:	36 in.
Septic Tank Size:	1000
Pump Tank Size:	N/A
Estimated Supply Line Length:	26
Supply Line Diameter:	3 in. SCH 40 PVC
Supply Line Volume:	4.52
Dosing Volume:	N/A
Supply Manifold:	DROP BOX
Supply Manifold Length:	N/A
Supply Manifold Volume:	N/A
Recommended Float Controls:	N/A N/A
Recommended Control Panel:	N/A N/A
Pressure Head:	N/A
Friction Head:	N/A
Elevation Head:	N/A
Total Dynamic Head:	N/A
Threaded Union:	NA
Gate Valves:	NA NA
Check Valves:	NA
Anti-Siphon Hole:	NA
Additional Comments:	Soil suitability was performed by Rollans Soil & Environmental Services.

BELLS CROSSING LOT 77
GRAVITY DISTRIBUTION DESIGN

DESIGN FLOW:	480	
SOIL APPLICATION RATE:	0.3	
TOTAL AREA TRENCH BOTTOM:	1200	
TOTAL LATERAL LENGTH:	400	
NUMBER OF FIELDS:	1	
LATERAL LENGTH REQUIRED PER FIELD:	400	
SUPPLY LINE LENGTH:	26	
TOTAL DYNAMIC HEAD:	N/A	
MANIFOLD SIZE:	N/A	
DOSING VOLUME:	N/A	
PUMP TANK DRAW DOWN*:	N/A	
SEPTIC TANK SIZE:		1000
PUMP TANK SIZE:	N/A	

BELLS CROSSING LOT # 77

Project #: 01-1429

LAYOUT FOR 4 BEDROOM HOME

September 4, 2008

LINE #	FLAG COLOR	BS	HI	FS	ELEVATION	FLAGGED LINE LENGTH	DESIGN LINE LENGTH
TBM		N/A			N/A		
INSTR. 1			N/A				
HOUSE CNR				N/A	N/A		
P. TANK				N/A	N/A		
1	RED			N/A	N/A	39	35
2	ORANGE			N/A	N/A	60	60
3	***BLUE***			***N/A***	***N/A***	***81***	***80***
4	***PINK***			***N/A***	***N/A***	***102***	***100***
5	***RED***			***N/A***	***N/A***	***130***	***110***
6	***ORANGE***			***N/A***	***N/A***	***131***	***110***
7	BLUE			N/A	N/A	129	129
8	PINK			N/A	N/A	130	130
9	RED			N/A	N/A	127	127
10	ORANGE			N/A	N/A	122	122
11	BLUE			N/A	N/A	113	113
					Total	**1164**	**1116**

	LINE LENGTH	LTAR GPD/FT^2	SYSTEM TYPE	SOIL LTAR GPD/FT^2	TRENCH SYSTEM	DISTRIBUTION
**** System***	***400***	***0.300***	***ACCEPT.***	***0.300***	***25% RED.***	**GRAVITY DISTRIBUTION**
Repair	716	0.350	MOD.	0.350	PPBPS	LOW PRESSURE

Notes:

**All measures in feet

**Nitrification lines are demonstrated on contour via colored pin flags

**BS, HI, and FS indicate rod readings