IREDELL COUNTY HEALTH DEPARTMENT


ENVIRONMENTAL HEALTH DIVISION

PAGE 2: *SITE PLAN WORKSHEET*

SEE THE "SAMPLE SITE PLAN" BELOW. ***INCOMPLETE SITE PLANS WILL BE RETURNED TO YOU FOR COMPLETION AND MAY RESULT IN A DELAY IN THE ISSUANCE OF YOUR SEPTIC SYSTEM PERMIT!!!***

Place an (X) beside each item as you complete the site plan:

( ) Property Line measurements are clearly identified
( ) All proposed structures are indicated
( ) Front and side setbacks from property line
( ) Preferred driveway location and well location
( ) Area you prefer your septic system to be placed
( ) North arrow, or other sufficient indicator of direction



Circle N/A on the following if appropriate:

Location of septic systems and wells within 100' of your property N/A
Location of easements and rights of ways on your property N/A
Location of any designated wetlands on the property N/A

USE THIS SPACE TO DRAW YOUR SITE PLAN

Show: proposed house or business footprint, wells, water lines, patios, pools and decks, and any other item that will occupy space on the site

See Attached

Signature: _____ _____

Property owner or owner's legal representative signature (SIGNATURE REQUIRED)

12-9-15

DATE

RECEIVED DEC 2 9 2015

LINE SCHEDULE

LINE NUMBER	COLOR	FIELD ELEVATION	LENGTH (FT)
1	YELLOW	0.7	102
2	RED	2.4	102
3	BLUE	4.2	102
4	YELLOW	5.7	102
5	RED	7.7	102
6	WHITE	10.1	102

APPROVED JAN 04 2016
ALP

LOT 136 BELLS CROSSING SUBDIVISION

5-BEDROOM ACCEPTED GRAVITY SYSTEM
LINES 1-6 TOTAL 612 LINEAR FEET
EZFLOW OR CHAMBER
LTAR 0.25
25% REDUCTION
15" TRENCH DEPTH MAX 3" OF COVER (DOWN HILL SIDE OF TRENCH)

Pre-treated MOB

5-BEDROOM DRIP IRRIGATION REPAIR
AREA REQUIRED 6000 SF
AREA PROPOSED 6789 SF
LTAR 0.1
6" TRENCH DEPTH

FOR GENERAL USE NOT A SURVEY
PRELIMINARY NOT FOR CONSTRUCTION


SOIL PROFILES AND ANALYSIS PROVIDED BY
PRICE ENVIRONMENTAL RESOURCE CONSULTING, PC

PRIMARY SYSTEM

REPAIR SYSTEM

REPAIR LINES (NOT USED)

PIT OR AUGER BORING A




0 30 60

SCALE:
1" = 60 ft.

Bateman Civil Survey Company
Engineers • Surveyors • Planners
200 N. Main Street, Holly Springs, NC 27540 Ph: 919.577.1080 Fax: 919.577.1081
www.batemancivilsurvey.com info@batemancivilsurvey.com
NCBELS Firm No. C-2378

Z:\projects\2011 MLS\110315 INWOOD FOREST\vantage logo.gif

LOT 136
BELLS CROSSING SUBDIVISION
MOORESVILLE, NC
IREDELL COUNTY
REVISED 12/28/2015
DATE: 12/23/15 DRAWN BY: MDB CHECKED BY:TMB



BATEMAN CIVIL SURVEY COMPANY
ENGINEERS • SURVEYORS • PLANNERS
2001 NORTH MAIN STREET, SALISBURY, NC 28144
PHONE (704) 637-1555 FAX (704) 637-1551
WEBSITE WWW.BATEMANCIVIL.COM
NCBELS FIRM C-2378

EXCLUSIVELY FOR:
MERITAGE HOMES OF THE CAROLINAS INC.
11605 NORTH COMMUNITY HOUSE ROAD
CALHOUN BUILDING, SUITE 250
CHARLOTTE, NC 28277

SUBDIVISION PLAT FOR:
BELLS CROSSING, PHASE 4
DAVIDSON TOWNSHIP
IREDELL COUNTY, NORTH CAROLINA
FINAL PLAT

Designed By: N / A	
Drawn By: JRD	
Drawn By: SPC	
SCALE: 1"=80'	
Date: 03/11/2015	
Project # 120314	

SHEET
4 OF 6