CALCULATIONS

Location BELLS CROSSING

Project Number ~~01-1429~~

Lot No: Lot 198

No. of Bedrooms 4

Design Flow 480 $^{gal}/_{day}$

LTAR 0.25 $^{gpd/ft^2}$

25% RED.? (YES OR NO) YES

Supply Line Length 11 ft.

Supply Line Volume 1.914 gal.

Required Feet of Line 480 ft.
Amount of Line from Layout 480 ft.

Gallons per Minute N/A $^{gal}/_{min}$

Required Septic Tank Capacity 1000 gal.
Minimum Standard Tank Size 1000

Lateral Line Volume 313.44 gal.

Dosing Volume N/A gal.

Note: Dosing Volume based on70% of lateral line volume

Tank Draw Down N/A *Generic Draw Down of 31 gal.per in.*

Pump Run Time N/A minutes

Elevation Head N/A ft.
Pressure Head N/A ft.
Friction Factor N/A ft./100 ft. *(From the interpolater.)*
Friction Head N/A ft.

Total Dynamic Head (+15%) N/A ft.

FRICTION FACTOR
INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42