CALCULATIONS

Location BELLS CROSSING

Project Number 01-1429

Lot No: Lot 71

No. of Bedrooms	4	
Design Flow	480	$^{gal}/_{day}$
LTAR	0.3	$^{gpd}/_{ft^2}$
25% RED.? (YES OR NO)	YES	
Supply Line Length	11	ft.
Supply Line Volume	1.914	gal.
Required Feet of Line	400	ft.
Amount of Line from Layout	402	ft.
Gallons per Minute	N/A	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Minimum Standard Tank Size	1000	
Lateral Line Volume	262.506	gal.
Dosing Volume	N/A	gal.

Note: Dosing Volume based on70% of lateral line volume

Tank Draw Down	N/A	*Generic Draw Down of 31 gal.per in.*
Pump Run Time	N/A	minutes
Elevation Head	N/A	ft.
Pressure Head	N/A	ft.
Friction Factor	N/A	ft./100 ft. *(From the interpolater.)*
Friction Head	N/A	ft.
Total Dynamic Head (+15%)	N/A	ft.

FRICTION FACTOR INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42