FOR WASTEWATER TREATMENT

Owner:	Bells Crossing, LLC
Address:	127B Promenade Dr. Mooresville, NC 28117
Phone:	704 361 1084
County:	Iredell
Location:	BELLS CROSSING LOT 194
Source of Wastewater Flow:	4 Bedroom Single Family Residence
Estimated Daily Wastewater Production:	480 gpd
System Flow:	N/A

Design Specifications

Drainfield Size:	537
Loading Rate:	0.225
Depth of Gravel in Trench:	NA (25% reduction)
Gravel Size:	NA (25% reduction)
Trench Depth:	30 in.
Trench Width:	36 in.
Septic Tank Size:	1000
Pump Tank Size:	N/A
Estimated Supply Line Length:	6
Supply Line Diameter:	3 in. SCH 40 PVC
Supply Line Volume:	1.04
Dosing Volume:	N/A
Supply Manifold:	DROP BOX
Supply Manifold Length:	N/A
Supply Manifold Volume:	N/A
Recommended Float Controls:	N/A N/A
Recommended Control Panel:	N/A N/A
Pressure Head:	N/A
Friction Head:	N/A
Elevation Head:	N/A
Total Dynamic Head:	N/A
Threaded Union:	NA
Gate Valves:	NA NA
Check Valves:	NA
Anti-Siphon Hole:	NA
Additional Comments:	Soil suitability was performed by Rollans Soil & Environmental Services.

BELLS CROSSING LOT 194
GRAVITY DISTRIBUTION DESIGN

DESIGN FLOW:	480	
SOIL APPLICATION RATE:	0.225	
TOTAL AREA TRENCH BOTTOM:	1611	
TOTAL LATERAL LENGTH:	537	
NUMBER OF FIELDS:	1	
LATERAL LENGTH REQUIRED PER FIELD:	533.3333333	
SUPPLY LINE LENGTH:	6	
TOTAL DYNAMIC HEAD:	N/A	
MANIFOLD SIZE:	N/A	
DOSING VOLUME:	N/A	
PUMP TANK DRAW DOWN*:	N/A	
SEPTIC TANK SIZE:		1000
PUMP TANK SIZE:	N/A	

BELLS CROSSING LOT # 194

Project #: 01-1429

LAYOUT FOR 4 BEDROOM HOME

July 24, 2008

LINE #	FLAG COLOR	BS	HI	FS	ELEVATION	FLAGGED LINE LENGTH	DESIGN LINE LENGTH
TBM		N/A			N/A		
INSTR. 1			N/A				
HOUSE CNR				N/A	N/A		
P. TANK				N/A	N/A		
1	PINK			N/A	N/A	70	~~70~~ 95
2	RED			N/A	N/A	103	~~103~~ 65
3	PINK			N/A	N/A	112	112
4	***BLUE***			***N/A***	***N/A***	***92***	***92***
5	ORANGE			N/A	N/A	57	57
6	***RED***			***N/A***	***N/A***	***123***	***120***
7	BLUE			N/A	N/A	31	31
8	***ORANGE***			***N/A***	***N/A***	***115***	***115***
9	***PINK***			***N/A***	***N/A***	***92***	***92***
10	***BLUE***			***N/A***	***N/A***	***70***	***70***
11	***RED***			***N/A***	***N/A***	***48***	***48***
					Total	**913**	**910**

	LINE LENGTH	LTAR GPD/FT²	SYSTEM TYPE	SOIL LTAR GPD/FT²	TRENCH SYSTEM	DISTRIBUTION
**** System***	***537***	***0.225***	***ACCEPT.***	***0.225***	***25% RED.***	**GRAVITY**
Repair	373 → 360 → 355	0.225	*MOD.*	0.225	PPBPS	**DISTRIBUTION** LOW PRESSURE → 310

Notes:

**All measures in feet

**Nitrification lines are demonstrated on contour via colored pin flags

**BS, HI, and FS indicate rod readings