# BELLSCROSSING LOT 100
## GRAVITY DISTRIBUTION

| | |
|---|---|
| **DESIGN FLOW (gpd):** | 480 |
| **SOIL APPLICATION RATE (gpd/ft.$^2$):** | 0.3 |
| **TOTAL AREA TRENCH BOTTOM:** | 1200 |
| **TOTAL LATERAL LENGTH:** | 400 |
| **NUMBER OF FIELDS:** | 1 |
| **LATERAL LENGTH REQUIRED PER FIELD:** | 400 |
| **SUPPLY LINE LENGTH:** | 23 |
| **TOTAL DYNAMIC HEAD:** | NA |
| **MANIFOLD SIZE:** | NA |
| **DOSING VOLUME:** | NA |
| **PUMP TANK DRAW DOWN*:** | NA |
| **SEPTIC TANK SIZE:** | 1000 |
| **PUMP TANK SIZE:** | NA |