Lot 104 Bells Crossing Subdivision Fast Track Septic System Information

Number of Bedrooms	5
Basement or Crawl	Crawl Space
Design Flow (gpd)	600
Primary System Type	25% Reduction
LTAR (gpd)/ft2	.3 per ICHD
Total Ft. Line	500
No. Lines	5 - see attached site plan
Pump Required	No
Distribution Device	Drop Boxes
Maintenance Agreement Required	No
Repair System	LP PPBPS - LPP 25 % Reduction
Total Ft. Line	595
Repair System Loading Rate	.3 per ICHD
Tank Red	1500 gal (2 compartment)

Notes: Smooth minor topo irregularities in old road bed and head slope at lowest blue, red, and pink repair lines.

S&ME, INC. / 385 Timber Road, Suite 104 / Mooresville, NC 28115-7899 / *p* 704.662.8625 *f* 704.662.8735 / www.smeinc.com