Paid $350.00 10-22-13

IREDELL COUNTY HEALTH DEPARTMENT Statesville

ENVIRONMENTAL HEALTH DIVISION

RECEIVED JUN 27 2014

PAGE 1: *APPLICATION FORM*

Application For:

( ) New Well Permit ( ) Well Repair Permit ( ) Well Abandonment

(✓) Septic Improvement Permit (✓) Authorization to Construct ( ) Existing System Inspection ( ) Septic System Repair

THE ABOVE PERMIT DOCUMENTS WILL BECOME INVALID IF INFORMATION PROVIDED ON THIS APPLICATION IS FALSIFIED OR CHANGED, OR IF THE SITE IS ALTERED. THE IMPROVEMENT PERMIT IS VALID FOR EITHER 60 MONTHS OR WITHOUT EXPIRATION DEPENDING UPON DOCUMENTATION SUBMITTED APPLICATION WITH SITE PLAN 60 MONTHS, APPLICATION WITH COMPLETE, SCALED PLAT WITHOUT EXPIRATION. SEE 15A NCAC 18A .1937(f) FOR DETAILS.

Page 2: *Site Plan Worksheet* form MUST accompany this application

The following optional attachments may also be submitted: (✓) Survey Plat, scaled no more than 1 inch = 60 feet

Place an (X) beside whichever is submitted if applicable (✓) Custom Site Plan, scaled no more than 1 inch = 60 feet

Applicant Information:

Applicant Name: Meritage Homes **Address:** 11605 N Community Rd St 250 Charlotte NC 28217 **Phone:** 7048096577

Owner Name: // **Address:** // **Phone:** 7046588616

Property Information:

Street Address: 141 Leaning Tower Dr

Subdivision Name: Bells Crossing **Section/Phase:** 2 **Lot Number:** 42

Driving Directions: 150 W, R onto Peeler Rd, L into Bells Crossing, R onto San Agustine Dr, R onto Leaning Tower Dr. 8th Lot on Left

Site Development Information: *(check or complete ALL that apply)*

(✓) New Single Family Residence
( ) New Multi-Family Residence
( ) Accessory Building
( ) Bedroom(s) Addition

Maximum Number of Bedrooms: 5
Maximum Number of Occupants: 10
( ) Swimming Pool
( ) Other Addition/Structure:

(✓) Crawl Space Foundation
( ) Concrete Slab Foundation
( ) Basement with Plumbing
( ) Basement without Plumbing

Non-Residential Site Development:

Type of Business:
Square Footage of Building:
Maximum Number of Employee:
Maximum Number of Seats/Beds/Other:

Water Supply:

( ) New Well ( ) Existing Well (✓) Community Well ( ) City Water ( ) Other Public Water

Desired Septic System Type: *(you may rank in order of preference)* **Year existing system installed:**

(✓) No Preference ( ) Alternative ( ) Conventional ( ) Innovative ( ) Modified Conventional ( ) Other:

Please answer the following to the best of your ability:

( ) Yes (✓) No Does the site contain any jurisdictional wetlands?
( ) Yes (✓) No Is any non-domestic sewage (i.e. industrial) to be generated?
( ) Yes (✓) No Is the site subject to approval by any other public agency?

I have read this application and certify that the information provided herein is true, complete, and correct. Authorized county and state officials are granted right of entry to conduct necessary inspections to determine compliance with applicable laws and rules. I understand that I am solely responsible for the proper identification and labeling of all property lines and corners and making the site accessible so that a complete site evaluation can be performed.

Signature: Will Bell — 6-25-14

Property owner or owner's legal representative signature (SIGNATURE REQUIRED) — DATE

IREDELL COUNTY HEALTH DEPARTMENT


ENVIRONMENTAL HEALTH DIVISION

PAGE 2: *SITE PLAN WORKSHEET*

SEE THE "SAMPLE SITE PLAN" BELOW. ***INCOMPLETE SITE PLANS WILL BE RETURNED TO YOU FOR COMPLETION AND MAY RESULT IN A DELAY IN THE ISSUANCE OF YOUR SEPTIC SYSTEM PERMIT!!!***

Place an (X) beside each item as you complete the site plan:

- (✓) Property Line measurements are clearly identified
- (✓) All proposed structures are indicated
- (✓) Front and side setbacks from property line
- (✓) Preferred driveway location and well location
- (✓) Area you prefer your septic system to be placed
- (✓) North arrow, or other sufficient indicator of direction



Circle N/A on the following if appropriate:

Location of septic systems and wells within 100' of your property	N/A
Location of easements and rights of ways on your property	N/A
Location of any designated wetlands on the property	N/A

USE THIS SPACE TO DRAW YOUR SITE PLAN

Show: proposed house or business footprint, wells, water lines, patios, pools and decks, and any other item that will occupy space on the site

See Attached

Signature: _____ 6-05-14

Property owner or owner's legal representative signature (SIGNATURE REQUIRED) — DATE

IREDELL COUNTY

PO Box [illegible]
349 North C[illegible]
Statesville, N[illegible]

APPLICATION NUMBER
181568
Issue Date: 11/13/2013

ZONING PERMIT
Residential

Lot 42

Parcel Number	Street Address		Jurisdiction
4639955462.000	141 LEANING TOWER DRIVE, [illegible]	NC 28117	MOORESVILLE

Owner Information	Applicant Information
Owner: MERITAGE HOMES OF NC INC	[illegible] ERITAGE HOMES OF NC I
Address: 17851 N 85TH ST SCOTTSDALE, AZ 85255	[illegible] 351 N 85TH ST COTTSDALE, AZ 85255
Phone:	[illegible]

Use Requested	Zone Code
SINGLE FAMILY HOUSE	RA

Lot Acreage	F Setback	B Setback	L Setback	R [illegible]	Watershed	Flood Zone
39.150	35.00	35.00	15.00		PACL	X

Remarks:
UPDATED ZONING 6-4-14 DW

The applicant certifies that there are no deed restr[illegible] contractual agreements or governmental regulations of any kind that interfere with or prohibit [illegible] the property or the use for which this permit is requested. The applicant further acknowle[illegible] enforcement of deed restrictions, plat conditions and other contractual agreements will not [illegible] ken by Iredell County and is the sole responsibility of the affected parties.

Applicant: _____ Date: _____

Permit Number	571	[illegible] ES	$ 77.25

LINE SCHEDULE

LINE NUMBER	COLOR	FIELD ELEVATION	LENGTH (FT)
1	RED	2.7	77
2	YELLOW	2.9	75
3	BLUE	3.5	32
4	WHITE	3.7	72
5	RED	3.9	22
6	BLUE	4.2	43
7	WHITE	1.5	36
8	RED	2.5	58
9	YELLOW	3.8	77
10	BLUE	4.7	85
11	RED	6	86
12	ORANGE	7.1	88
13	YELLOW	8	93
14	BLUE	8.9	66
15	RED	9.9	35

Total 78.1


LOT 42 BELLS CROSSING SUBDIVISION

5-BEDROOM ACCEPTED STATUS GRAVITY SYSTEM
LINES 7-13 TOTAL 523 LINEAR FEET
EZFLOW OR CHAMBER
LTAR 0.3
25% REDUCTION
~~36~~" TRENCH DEPTH MAX
23"

5-BEDROOM LPP FED PANEL BLOCK REPAIR
LINES 1-6 14-15 422 TOTAL LINEAR FEET
LTAR 0.3
25% REDUCTION
~~36~~" TRENCH DEPTH MAX
23"

FOR GENERAL USE NOT A SURVEY
PRELIMINARY NOT FOR CONSTRUCTION

SOIL PROFILES AND ANALYSIS PROVIDED BY
CENTRAL CAROLINA SOIL CONSULTING PLLC



PRIMARY SYSTEM

REPAIR SYSTEM

REPAIR LINES (NOT USED)

PIT OR AUGER BORING [1]

0 30 60

SCALE:
1" = 60 f t

504

APPROVED JUL 01 2014
AZP

Bateman Civil Survey Company
Engineers • Surveyors • Planners
200 N. Main Street, Holly Springs, NC 27540 Ph: 919.577.1080 Fax: 919.577.1081
www.batemancivilsurvey.com info@batemancivilsurvey.com
NCBELS Firm No. C-2378

Z:\projects\2011 MLS\110315 INWOOD FOREST\sewage logos.gif

LOT 42
BELLS CROSSING SUBDIVISION
MOORESVILLE, NC
IREDELL COUNTY

DATE: 5/6/14 DRAWN BY AH CHECKED BY: TMB

Property ID:
Lot #: 42
File #:
AppID:

CCSC SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

Owner: Meritage Homes
Address: 11605 N Community House Rd. Charlotte NC 28277
Proposed Facility: Design Flow (.1949)
Location of Site: Bells Crossing Lot 42

Applicant: Steve
Date Evaluated: 08/14/12
Property Size: 0.90ac
Property Recorded: 2013

Water Supply: [X] Public [ ] Individual [ ] Well [ ] Spring [ ] Other
Evaluation Method: [ ] Auger Boring [X] Pit [ ] Cut
Type of Wastewater: [X] Sewage [ ] Industrial Process [ ] Mixed

PROFILE #	.1940 Landscape Position/ Slope%	Horizon Depth (IN.)	SOIL MORPHOLOGY .1941 .1941 Structure/ Texture	.1941 Consistence Mineralogy	b PROFILE FACTORS .1942 Soil Wetness/ Color	.1943 Soil Depth (IN.)	.1958 Sapro Class	.1944 Restr. Horiz.	Profile Class & LTAR
A	SS 8% A	0-5"	Gr SL	VFR NS NP	5YR 4/6				
	BT	5-28	SBK Clay	FI SS SP	2.5YR 4/8	PS			PS .3
	C	28-51	Mass SL	VFR SS NP	2.5YR 4/8 5YR 5/8 20% 5YR 7/6 20%	PS	S		S, .4
B	SS 8% A	0-4	Gr SL	VFR NS NP	5YR 4/6				
	BT	4-38"	SBK Clay	FI SS SP	2.5YR 4/8 10YR 6/6 5%	PS			PS .3
	BC	38-46"	WE SBK SCL	FR SS SP	5YR 5/8 10YR 8/2 Relict	PS			PS, 0.33
C	R 3% A	0-1	Gr SL	VFR NS NP	10YR 3/2				
	BT	1-26	SBK, Clay	FI SS SP	2.5YR 4/8	PS			PS 0.3
	BC	26-49"	WE SBK, SCL	FR, SS SP	5YR 5/8 10YR 8/4, 20%	S			S .33
D	R 3%	AE 0-6"	Gr SL	VFR NS NP	7.5YR 4/4				
	BT1	6-38"	SBK clay	FI SS SP	2.5YR 4/8	PS			0.3
	BT2	38-51"	SBK clay	FI SS SP	2.5YR 4/8 10YR 6/8 5%				


Description	Initial System	Repair System
Available Space (.1945)	Yes	
System Type(s)	Accepted	Panel Block
Site LTAR	0.3	0.3

Other Factors (.1946):
Soil Evaluation By: JH, MB
Others Present:
Site Classification (.1948):
Site Evaluation By: SWM
Others Present:

LICENSED SOIL SCIENTIST
JASON M. HAL
1248
STATE OF NORTH CAROLINA

24"

APPROVED JUL 01 2014
APPROVED JUL 01 2014
HLP



Upper Floor Plan - C

0 2' 4' 8'

TYPICAL CONSTRUCTION ASSEMBLIES:

A. TYPICAL ROOF CONSTRUCTION:
ASPHALT ROOF SHINGLES

B. TYPICAL FRAME FLOOR CONSTRUCTION:
WOOD FLOORING ON 3/4" TONGUE & GROOVE FLOOR SHEATHING ON FLOOR TRUSSES OR FLOOR JOISTS AS NOTED ON STRUCTURAL DRAWINGS.

C. SLAB ON GRADE FLOOR CONSTRUCTION:
4" CONCRETE SLAB, EXCEPT AS SPECIFIED BY SOIL REPORT, AND STRUCTURAL ENGINEER. INCLUDE VAPOR BARRIER PER SECTION N, C, 5, a.

D. WINDOWS:
A. ALL WINDOWS SHALL COMPLY WITH MINIMUM STANDARDS OUTLINED IN APPLICABLE RES. CHECKS.
B. WINDOW SUPPLIER TO VERIFY AT LEAST ONE WINDOW IN ALL BEDROOMS TO HAVE A CLEAR EGRESS OPENING OF 5.7 SQ. FT. WITH MIN. DIMENSION OF 24" IN HEIGHT AND 20" IN WIDTH, SILL HEIGHT NOT GREATER THAN 44" ABOVE FLOOR.
C. TYPICAL WINDOW HEAD HEIGHT:
7'-0" A.F.F @ 8'-1 1/8" PLATE HEIGHT (U.N.O.)
8'-0" A.F.F @ 9'-1 1/8" PLATE HEIGHT (U.N.O.)

E. ELECTRICAL:
ALL ELECTRICAL AND MECHANICAL EQUIPMENT & METERS ARE SUBJECT TO RELOCATION DUE TO FIELD CONDITIONS. CONTRACTOR TO VERIFY.

F. HVAC:
PROVIDE BACK DRAFT DAMPERS @ DRYER VENT, HOOD VENT, & EXHAUST FANS.

G. ROOF PITCH:
INSTALL PER LOCAL CODE.

H. DIMENSIONS ARE TO THE FACE OF STUD, U.N.O.

I. ALL EXTERIOR DIMENSIONS ARE TO FACE OF STUDS UNLESS OTHERWISE NOTED.

M. ALL ANGLED PARTITIONS ARE 45 DEGREES UNLESS OTHERWISE NOTED.

N. BRICK SOLDIER:
INSTALL PER LOCAL CODE.

FLOOR PLAN NOTES:

(UPPER FLOOR)

(#) THE FOLLOWING KEYNOTED REFERENCE THE SYMBOLS AS SHOWN ON PLANS.

1. IF RAILING / GUARDRAIL IS PROVIDED, ALL RAILING / GUARDRAIL BALUSTERS TO BE SPACED SUCH THAT A 4" SPHERE CANNOT PASS BETWEEN BALUSTERS. RAILING/HANDRAILS ARE TO BE AT A 34" MINIMUM TO 38" MAXIMUM HEIGHT A.F.F., WITH RETURNS PER LOCAL CODE. RAILING AT GUARDRAIL LOCATIONS TO BE AT 42" MINIMUM A.F.F., OPT. RAILING.
2. LINE OF OVERHEAD GARAGE DOOR IN OPEN POSITION.
3. SLOPE GARAGE FLOOR 1/8" PER FOOT TOWARD OVERHEAD GARAGE DOOR OPENING.
4. FIREPLACE, AS SPECIFIED BY BUILDER. INSTALL PER MANUFACTURERS SPECIFICATIONS. ALL FACTORY BUILT FIREPLACES SHALL COMPLY WITH LOCAL CODES.
5. SINK IN GARBAGE DISPOSAL
6. DISHWASHER
7. RANGE
8. COOK TOP
9. OVEN
10. REFRIGERATOR SPACE.
11. PANTRY
12. PEDESTAL SINK
13. 42" X 42" SHOWER
14. 42" X 60" SHOWER
15. 42" X 60" TUB
16. 60" X 60" CORNER TUB
17. 30" X 60" TUB/SHOWER
18. 32" X 60" TUB/SHOWER
19. LINEN (SHELVING PER BUILDER SPECS.)
20. WASHER SPACE
21. DRYER VENT
22. OPTIONAL LAUNDRY SINK
23. PROVIDE NON-COMBUSTIBLE PLATFORM ELEVATED 8" ABOVE GARAGE FLOOR FOR WATER HEATER.
24. 5 SHELVES PER BUILDER SPECS.
25. ROD AND SHELF PER BUILDER SPECS.
26. ATTIC ACCESS (22"X36" U.N.O.).
27. ATTIC ACCESS W/ STAIRS (22 1/2"x54" U.N.O.).
28. GYPSUM BOARD OPENING @ 8'-0" AT MAIN FLOOR & 7'-0" AT UPPER FLOOR U.N.O.
29. GYPSUM BOARD ARCH @ 7'-0" TO 8'-0".
30. GYPSUM BOARD LOW WALL, 30" A.F.F. (U.N.O.) W/ HDF CAP.
31. SOFFIT, REFER TO EXTERIOR ELEVATIONS FOR HEIGHTS & ARCHITECTURAL DETAILS FOR FASCIA.
32. PLANT SHELF, SEE EXTERIOR ELEVATIONS.
33. HALF WALL W/ HDCP CAP OR OPTIONAL LOW WALL WITH RAILING ABOVE.
34. PORCH RAIL, SEE ELEVATION.
35. 36"x36" CONCRETE STOOP.
36. 6x6 BEAM.
37. OPTIONAL UPPER CABINETS.
38. OPTIONAL CABINETS.
39. OPTIONAL COVERED PORCH @ 8'-0" PER BUILDER SPEC.
40. LINE OF FRAMING ABOVE.
41. LINE OF FRAMING WALL BELOW.
42. 2x4 LOW WALL 42" A.F.F.
43. 2x6 LOW WALL 42" A.F.F.
44. ART NICHE
45. HORIZONTAL LAUNDRY CHUTE
46. LOW WALL 42"A" A.F.F.
47. GYPSUM BOARD ARCH @ 8'-0" TO 8'-6"
48. LOW WALL 30" A.F.F.
49. NO HARD LATCH OR LOCKING KNOB

ALL EXTERIOR HOUSE WALLS MAY BE OPTIONAL 2X6 STUD WALLS - SEE STRUCTURAL PLANS FOR DETAILS.

Acknowledgement Of Plans Submittal ONLY!

Date 6-27-14

Date 7-1-14

ISSUE DATE: 03/18/2014
REVISIONS

5400 Trinity Road
Suite 107
Raleigh,
North Carolina 27607
919-322-9265 Phone

Meritage Homes

Meritage Homes

BSB DESIGN


www.bsbdesign.com
8911 Westmoor Parkway, Suite 300
West Des Moines, Iowa 50266
515.278.1000

JOB NO. 03/18/2014 PROJ MGR. JF
DRAWN BY: MVDH DESIGNED: JF/JG

UPPER FLOOR PLAN - C

Plan - 4226

A2.2C



Main Floor Plan - C

TYPICAL CONSTRUCTION ASSEMBLIES:

A. TYPICAL ROOF CONSTRUCTION: ASPHALT ROOF SHINGLES

B. TYPICAL FRAME FLOOR CONSTRUCTION: FINISH FLOORING ON 3/4" TONGUE & GROOVE FLOOR SHEATHING ON FLOOR TRUSSES OR FLOOR JOISTS AS NOTED ON STRUCTURAL DRAWINGS.

C. SLAB ON GRADE FLOOR CONSTRUCTION: 4" CONCRETE SLAB, EXCEPT AS SPECIFIED BY SOIL REPORT, AND STRUCTURAL ENGINEER. INCLUDE VAPOR BARRIER PER SECTION IV, C, 5, a.

D. WINDOWS:
A. ALL WINDOWS SHALL COMPLY WITH MINIMUM STANDARDS OUTLINED IN APPLICABLE IRC CHECKS.
B. WINDOW SUPPLIER TO VERIFY AT LEAST ONE WINDOW IN ALL BEDROOMS TO HAVE A CLEAR EGRESS OPENING OF 5.1 SQ. FT. WITH MIN. DIMENSION OF 24" IN HEIGHT AND 20" IN WIDTH SILL HEIGHT NOT GREATER THAN 44" ABOVE FLOOR.
C. TYPICAL WINDOW HEAD HEIGHT: 7'-0" A.F.F @ 8'-1 1/8" PLATE HEIGHT (U.N.O.) 8'-0" A.F.F @ 9'-1 1/8" PLATE HEIGHT (U.N.O.)

E. ELECTRICAL: ALL ELECTRICAL AND MECHANICAL EQUIPMENT & METERS ARE SUBJECT TO RELOCATION DUE TO FIELD CONDITIONS; CONTRACTOR TO VERIFY.

F. DUCTS: PROVIDE BACK DRAFT DAMPERS @ DRYER VENT, HOOD VENT, & EXHAUST FANS.

G. STONE SILLS: INSTALL PER LOCAL CODE. DIMENSIONS ARE TO THE FACE OF STUD, U.N.O.

I. ALL EXTERIOR DIMENSIONS ARE TO FACE OF STUDS UNLESS OTHERWISE NOTED.

M. ALL ANGLED PARTITIONS ARE 45 DEGREES UNLESS OTHERWISE NOTED.

N. BRICK SILLS: INSTALL PER LOCAL CODE.

FLOOR PLAN NOTES: (MAIN FLOOR)

4 THE FOLLOWING KEYNOTES REFERENCE THE SYMBOLS AS SHOWN ON PLANS.

1. IF RAILING / HANDRAIL IS PROVIDED, ALL RAILING / GUARDRAIL BALUSTERS TO BE SPACED SUCH THAT A 4" SPHERE CANNOT PASS BETWEEN BALUSTERS. RAILING/HANDRAILS ARE TO BE AT A 34" MINIMUM TO 38" MAXIMUM HEIGHT A.F.F., WITH RETURNS PER LOCAL CODE. RAILING AT GUARDRAIL LOCATIONS TO BE AT 42" MINIMUM A.F.F. OPT. RAILING.
2. LINE OF OVERHEAD GARAGE DOOR IN OPEN POSITION.
3. SLOPE GARAGE FLOOR 1/8" PER FOOT TOWARD OVERHEAD GARAGE DOOR OPENING.
4. FIREPLACE, AS SPECIFIED BY BUILDER. INSTALL PER MANUFACTURERS SPECIFICATIONS. ALL FACTORY BUILT FIREPLACES SHALL COMPLY WITH LOCAL CODES
5. SINK W/ GARBAGE DISPOSAL
6. DISHWASHER
7. RANGE
8. COOK TOP
9. OVEN
10. REFRIGERATOR SPACE.
11. PANTRY
12. PEDESTAL SINK
13. 42" X 42" SHOWER
14. 43" X 60" SHOWER
15. 42" X 60" TUB
16. 60" X 60" CORNER TUB
17. 60" X 60" TUB/SHOWER
18. 32" X 60" TUB/SHOWER
19. LINEN SHELVING PER BUILDER SPECS.)
20. WASHER SPACE
21. DRYER, VENT
22. OPTIONAL LAUNDRY SINK.
23. PROVIDE NON-COMBUSTIBLE PLATFORM ELEVATED 8" ABOVE GARAGE FLOOR FOR WATER HEATER.
24. 5 SHELVES PER BUILDER SPECS.
25. ROD AND SHELF PER BUILDER SPECS.
26. ATTIC ACCESS (22"X30" U.N.O.
27. ATTIC ACCESS W/ STAIRS (22 1/2"x54" U.N.O.
28. GYPSUM BOARD OPENING @ 8'-0" AT MAIN FLOOR & 7'-0" AT UPPER FLOOR (U.N.O.
29. GYPSUM BOARD ARCH @ 11'-2" TO 8'-0".
30. GYPSUM BOARD LOW WALL 36" A.F.F. (U.N.O.) W/ PEF CAP.
31. SOFFIT, REFER TO EXTERIOR ELEVATIONS FOR HEIGHTS & ARCHITECTURAL DETAILS FOR FINISH.
32. PLANT SHELF, SEE EXTERIOR ELEVATIONS.
33. HALF WALL W/ WOOD CAP OR OPTIONAL LOW WALL WITH RAILING ABOVE.
34. PORCH WALL, SEE ELEVATION.
35. 36"x36" CONCRETE STOOP.
36. 6x8 BEAM.
37. OPTIONAL UPPER CABINETS.
38. OPTIONAL CABINETS.
39. OPTIONAL COFFERED CEILING @ 8'-0" PER BUILDER SPEC.
40. LINE OF FRAMING ABOVE.
41. LINE OF FRAMING WALL BELOW.
42. 2x4 LOW WALL 42" A.F.F.
43. 2x6 LOW WALL 42" A.F.F.
44. ART NICHE
45. HORIZONTAL LAUNDRY CHUTE
46. LOW WALL +24" A.F.F.
47. GYPSUM BOARD ARCH @ 9'-0" TO 8'-6"
48. LOW WALL 30½" A.F.F.
49. 10 HARD LATCH OR LOCKING KNOB

SQUARE FOOTAGES	
MAIN FLOOR	3491
UPPER FLOOR	1156
TOTAL	2308
GARAGE	453
PORCH	56
BASEMENT	975
FINISHED BASEMENT	975
OPT. HOBBY ROOM	210
OPT. SCREENED PORCH	150
TOTAL	1844

ALL EXTERIOR HOUSE WALLS MAY BE OPTIONAL 2X6 STUD WALLS - SEE STRUCTURAL PLANS FOR DETAILS.

Acknowledgement Of
Plans Submittal ONLY!
Date 6-27-14
Date 7-1-14

ISSUE DATE: COMMENTS
REVISIONS

5400 Trinity Road
Suite 107
Raleigh,
North Carolina 27607
919-322-2295 Phone

Meritage Homes

Meritage Homes

BSB DESIGN
www.bsbdesign.com
8081 Wallace Parkway, Suite 810
West Des Moines, Iowa 50266
515 875 5810

JOB NO: 03-13024 PROJECT: 4F
DRAWN: DJ CHECKED: JF-JG
MAIN FLOOR PLAN - C

Plan - 4226
A2.1C