Lot 16 Lakeshore Estates Fast Track Septic System Information

Carolina Custom Homes of Burlington - S&ME Job No. 1584-13-094

Number of Bedrooms	**4**
Basement or Crawl	**Crawl Space**
Design Flow (gpd)	**480**
Primary System Type	**25% Reduction**
LTAR (gpd)/ft2	**0.25**
Total Ft. Line	480
No. Lines	8 7 (See Table)
Pump Required	No
Distribution Device	drop boxes or as specified by ICHD
Maintenance Agreement Required	No
Repair System	**Repair exempt***

The ICHD should reserve any potential repair areas on the Improvement Permit

Table: Summary of Primary Nitrification Line Specifications

Line No.	Use	Line Color	System Type	Line Length (Ft.)
1	System	yellow	25% Reduction	~~60~~ 55
2	System	blue	25% Reduction	75 70
3	System	orange	25% Reduction	75 70
4	System	white	25% Reduction	75 70
5	System	blue	25% Reduction	75 70
6	System	orange	25% Reduction	75 70
7	System	white	25% Reduction	45 45
8	11	NF		Total System: 480'

+ 30

Tank	orange	1000 gal (2 compartment)