ON-SITE WASTEWATER SECTION

PROPERTY ID #: _____
COUNTY: _____

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

OWNER: _____ APPLICATION DATE _____
ADDRESS: _____ DATE EVALUATED: _____
PROPOSED FACILITY: _____ PROPOSED DESIGN FLOW (.1949): _____ PROPERTY SIZE: _____
LOCATION OF SITE: Lot 64 Sundown PROPERTY RECORDED: _____
WATER SUPPLY: ☐ Private ☐ Public ☐ Well ☐ Spring ☐ Other _____
EVALUATION METHOD: ☐ Auger Boring ☐ Pit ☐ Cut
TYPE OF WASTEWATER: ☐ Sewage ☐ Industrial Process ☐ Mixed

PROFILE #	.1940 LAND-SCAPE POSITION/ SLOPE %	HORI-ZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	SOIL MORPHOLOGY (.1941) .1941 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS & LTAR
1		0-21	RC MSBK	fi SP					PS 1.3
		21-56	YRCL WSBK	fi SSSP	few SAP				
2		0-24	BRC SGR/MASBK	fi SP					~~.2~~ to .36
		24-36	YRC ABK	fi SP - YB's					
		36-50	YRC ABK	fi SP - 2 chroma	@ 36"				
3		0-8	BSCL WSBK	fi SSSP					.3
		8-24	RC WSBK	fi SP					
		24-53	YRCL WSBK	fi SSSP - common	SAP				
4		0-8	BSCL WSBK	fi SSSP					.2 to .36
		8-24	YB/YRC ABK	fi SP - common YB's					
		24-50	YRCL/C ABK	ABK fi SP - 2 chroma @ 36"					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)		
System Type(s)		
Site LTAR		

OTHER FACTORS (.1946): _____
SITE CLASSIFICATION (.1948): _____
EVALUATED BY: _____
OTHER(S) PRESENT: _____

COMMENTS: _____

CORONA CIRCLE
61
25,000.00 sq.ft.
62
25,000.00 sq.ft.
63
25,000.00 sq.ft.
64
25,000.00 sq.ft.
65
25,000.00 sq.ft.
250.00'
100.00'
S87° 58'58"
695.32'
4' SIDEWALK