## Lot 9 Jess Court Fast Track

| | |
|---|---|
| **Number of Bedrooms** | **3** |
| **Basement or Crawl** | **Crawl Space** |
| **Design Flow (gpd)** | **360** |
| **Primary System LTAR (gpd/ft2)** | **0.25** |
| **Primary System Type** | **25% Reduction** |
| No. Lines | 4 (See Table) |
| Total Linear Feet | 360 |
| Trench Width | 3' min. |
| Trench Spacing | 9' min. |
| Distribution Device | Drop Boxes |
| Tank Size | 1000 gallon tank |
| Maintenance Agreement Required | No |
| Length and Diameter of Supply Pipe | 15' of 2" SCH 40 PVC |
| **Repair System** | **LP PPBPS** |
| Total Linear Feet | 270 |
| Repair Loading Rate | 0.25 |

### Table: Summary of Primary and Repair Nitrification Line Specifications

| Line No. | Use | Line Color | System Type | Line Length (Ft.) |
|---|---|---|---|---|
| 1 | Repair | Orange | LP PPBPS | 30 |
| 2 | Repair | White | LP PPBPS | 70 |
| 3 | System | Red | 25% Reduction | 60 endfed |
| 4 | System | Pink | 25% Reduction | 100 endfed |
| 5 | System | White | 25% Reduction | 105 endfed |
| 6 | System | Orange | 25% Reduction | 95 endfed |
| 7 | Repair | Blue | LP PPBPS | 90 |
| 8 | Repair | Red | LP PPBPS | 55 |
| 9 | Repair | Pink | LP PPBPS | 25 |
| | | | | Total System: 360' |
| | | | | Total Repair: 270' |

**Note:** 24" TB Depth KMS 6/20/12