ROLLANS *SOIL & ENVIRONMENTAL SERVICES*

2120 Graham Road, Mount Ulla, NC 28125 *Phone/Fax (704) 278 – 0989*

Ashley Rollans, NC Licensed Soil Scientist
Mobile: (704) 746-5046
E-mail: Rollansfortcj@aol.com

Brady Freeman, Registered Sanitarian
Mobile: (704) 746-6497
E-mail: bfree209@yahoo.com

Attached is a proposed design for a PPBPS Septic System with low pressure distribution for a 3 bedroom single family residence on Lot #14 in THE ORCHARDS Subdivision, Iredell County, North Carolina.

Contents: **Page**

Information for the Installer---------- 1

Design Information
- Design Specifications---------- 2-3
- Layout Specifications---------- 4
- System Tapsheet---------- 5

Site Plan/System Plan---------- 6

Calculations---------- 7

Profile Descriptions---------- 8

August 30, 2006
Project #: 01-1195
Design By: Rollans Soil & Environmental Services

LP PPBPS SYSTEM
FOR WASTEWATER TREATMENT

Owner/Applicant: THE ORCHARDS LLC

Address: 227 Hideaway Lane
Mooresville, NC 28117
Phone: 704-201-6465
County: Iredell
Location: THE ORCHARDS Subdivision Lot #14

Source of Wastewater Flow: 3 Bedroom Single Family Residence
Estimated Daily Wastewater Production: 480 gpd
System Flow: 19.58538462

Design Specifications

Drainfield Size: 207
Loading Rate: 0.3 gpd/ft.^{2}
Depth of Gravel in Trench: NA (PPBPS)
Gravel Size: NA (PPBPS)
Trench Depth: 36 in.
Trench Width: 36 in.
Septic Tank Size: 1000
Pump Tank Size: 1000

Estimated Supply Line Length: 154
Supply Line Diameter: 2 in. SCH 40 PVC
Supply Line Volume: 26.80
Dosing Volume: 115.22
Supply Manifold: N/A
Supply Manifold Length: N/A
Supply Manifold Volume: N/A

Recommended Float Controls: SJE Sensor Float Control Switches as Required for Control Panel or County Approved Equivalents
Recommended Control Panel: SJE-Rhombus Model 112 (NEMA 4x) Control Panel or County Approved Control Panel.

Pressure Head: 2 ft.
Friction Head: 1.29
Elevation Head: 16.10
Total Dynamic Head: 22.30

Threaded Union: In Tank
Gate Valves: 1 in Tank
1 per lateral (4)
Check Valves: In Tank
Anti-Siphon Hole: NA
Additional Comments: Soil suitability was performed by Rollans Soil & Environmental Services

THE ORCHARDS Subdivision Lot #14
LP PPBPS

DESIGN FLOW:	360
SOIL APPLICATION RATE:	0.3 gpd/ft.2
TOTAL AREA TRENCH BOTTOM:	621
TOTAL LATERAL LENGTH:	207
NUMBER OF FIELDS:	1
LATERAL LENGTH REQUIRED PER FIELD:	200
SUPPLY LINE LENGTH:	154
TOTAL DYNAMIC HEAD:	22.30
MANIFOLD SIZE:	N/A
DOSING VOLUME:	115.22
PUMP TANK DRAW DOWN*:	5.5
SEPTIC TANK SIZE:	1000
PUMP TANK SIZE:	1000

**Pump tank draw down based on a volume basis of 21 gallons per inch. Draw down may vary among pump tank manufacturers.*

THE ORCHARDS LOT 14

Project #: 01-1195

LAYOUT FOR 3 BEDROOM HOME

August 30, 2006

LINE #	FLAG COLOR	BS	HI	FS	ELEVATION	FLAGGED LINE LENGTH	DESIGN LINE LENGTH
TBM		4.7			100.00		
INSTR. 1			104.70				
HOUSE CNR				5.50	99.20		
P. TANK				14.30	90.40		
1	*PINK*			*3.20*	*101.50*	*83*	*83*
2	*ORANGE*			*3.90*	*100.80*	*84*	*84*
3	*BLUE*			*5.00*	*99.70*	*40*	*40*
4	BLUE			5.00	99.70	40	40
5	RED			6.10	98.60	80	80
6	PINK			7.30	97.40	63	63
7	ORANGE			8.30	96.40	45	45
					Total	435	435

	LINE LENGTH	LTAR GPD/FT2	SYSTEM TYPE	SOIL LTAR GPD/FT2	TRENCH SYSTEM	DISTRIBUTION
** System*	*207*	*0.3*	*MOD.*	*0.30*	*PPBPS*	*LOW PRESSURE*
Repair	228	0.3	MOD.	0.30	PPBPS	LOW PRESSURE

Notes:

** TBM located top of ground at EIP at corner of lot (see site plan)

**TBM is assumed to be 100'

**All measures in feet

**Nitrification lines are demonstrated on contour via colored pin flags

**BS, HI, and FS indicate rod readings

LP PPBPS TAPSHEET -THE ORCHARDS LOT 14

SYSTEM

Line #	Color	Elevation	Length	Hole Size	Flow/hole	Trench Area	Number of Panels
1	***ORANGE***	101.5	***83***	0.156	**0.41**	249	19
2	***PINK***	100.8	***84***	0.156	**0.41**	252	19
3	***BLUE***	99.7	***40***	0.156	**0.41**	120	9

total	**feet =**	**207**	**gal/min =**	**19.585385**
		Des. Flow	**360**	
		Pump Run=	**5.88**	
		soil LTAR	**0.3**	
		LTAR +5%	**0.315**	
		LTAR with mod.	**0.27**	
		LTAR with mod.. + 5%	**0.2835**	

.156 equals 5/32 inch hole

CALCULATIONS

Location THE ORCHARDS

Project Number 01-1195

Lot No: Lot 14

No. of Bedrooms	3	
Design Flow	360	$^{gal}/_{day}$
LTAR	0.3	gpd/ft2
PPBPS? (YES OR NO)	YES	
Supply Line Length	154	ft.
Supply Line Volume	26.796	gal.
Required Feet of Line	200	ft.
Amount of Line from Layout	207	ft.
Gallons per Minute	19.58538	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Minimum Standard Tank Size	1000	
Panel Volume	3.6	gal.
# of Panels	48	
Dosing Volume	115.22	gal.

Note: Dosing Volume based on 33% of # of panels times 3.6 gal/panel

Tank Draw Down	5.5	*Generic Draw Down of 21 gal.per in.*
Pump Run Time	5.88	minutes
Elevation Head	16.1	ft.
Pressure Head	2	ft.
Friction Factor	0.84	ft./100 ft. *(From the interpolater.)*
Friction Head	1.29	ft.
Total Dynamic Head (+15%)	22.30	ft.

FRICTION FACTOR INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42