ROLLANS *Soil & Environmental Services, Inc.*

470 North Broad St., Suite D, Mooresville, NC 28115 *Phone: (704) 658-1723* *Fax: (704) 658-1724*

Ashley Rollans, NC Licensed Soil Scientist
Mobile: (704) 746-5046
E-mail: Rollansfortcj@aol.com

Brady Freeman, Registered Sanitarian
Mobile: (704) 746-6497
E-mail: bfree209@yahoo.com

Attached is a proposed design for an Accepted (25% reduction) Septic System with Pressure Manifold distribution for a 3 bedroom single family residence on Lot #28 in Shepherds Bluff Subdivision, Iredell County, North Carolina.

Contents: **Page**

Information for the Installer---------- 1

Design Information
- Design Specifications---------- 2-3
- Layout Specifications---------- 4
- System Tapsheet---------- 5
- Pressure Manifold Diagram---------- 6

Site Plan/System Plan---------- 7

Calculations---------- 8

Profile Descriptions---------- 9

May 24, 2007
Project #: 01-1064
Design By: Rollans Soil and Environmental Services

PRESSURE MANIFOLD SYSTEM
FOR WASTEWATER TREATMENT

Owner:	Shepherds Bluff, LLC
Address:	111-B Raceway Dr Mooresville, NC 28117
Phone:	704-664-7029
County:	Iredell
Location:	Shepherds Bluff Lot 28
Source of Wastewater Flow:	3 Bedroom Single Family Residence
Estimated Gallons Per Day Flow:	360
System Flow:	21.92

Design Specifications

Drainfield Size:	360
Loading Rate (gpd/ft.^{2}):	0.25
Depth of Gravel in Trench:	NA (25% reduction)
Gravel Size:	NA (25% reduction)
Trench Depth:	45 in.
Trench Width:	36 in.
Septic Tank Size:	1000
Pump Tank Size:	1000
Estimated Supply Line Length:	138
Supply Line Diameter:	2 in. SCH 40 PVC
Supply Line Volume:	24.01
Dosing Volume:	164.56
Supply Manifold:	4 in. SCH 80 PVC
Supply Manifold Length:	4 ft. (minimum)
Supply Manifold Volume:	N/A
Recommended Float Controls:	SJE Sensor Float Control Switches as Required for Control Panel or County Approved Equivalents
Recommended Control Panel:	SJE-Rhombus Model 112 (NEMA 4x) Control Panel or County Approved Control Panel.
Pressure Head:	2 ft.
Friction Head:	5.91
Elevation Head:	15.50
Total Dynamic Head:	26.92
Threaded Union:	In Tank
Gate Valves:	1 in Tank 1 at Pressure Manifold
Check Valves:	In Tank
Anti-Siphon Hole:	NA
Additional Comments:	Soil suitability was performed by Rollans Soil & Environmental Services.

Shepherds Bluff Lot 28
PRESSURE MANIFOLD DESIGN

DESIGN FLOW (gpd):	360
SOIL APPLICATION RATE (gpd/ft.^{2}):	0.25
TOTAL AREA TRENCH BOTTOM:	1080
TOTAL LATERAL LENGTH:	360
NUMBER OF FIELDS:	1
LATERAL LENGTH REQUIRED PER FIELD:	360
SUPPLY LINE LENGTH:	138
TOTAL DYNAMIC HEAD:	26.92
MANIFOLD SIZE:	4 in.SCH 80 PVC
DOSING VOLUME:	164.56
PUMP TANK DRAW DOWN*:	7.8
SEPTIC TANK SIZE:	1000
PUMP TANK SIZE:	1000

**Pump tank draw down based on a volume basis of 21 gallons per inch. Draw down may vary among pump tank manufacturers.*

Shepherds Bluff Lot 28

Project #: 01-1064

LAYOUT FOR 3 BEDROOM HOME

May 24, 2007

LINE #	FLAG COLOR	BS	HI	FS	ELEVATION	FLAGGED LINE LENGTH	DESIGN LINE LENGTH
TBM					200.00		
INSTR. 1					200.00		
HOUSE CNR					205.60		
P. TANK					200.30		
1	WHITE				211.60	31	31
2	PINK				211.70	47	47
3	ORANGE				211.90	67	67
4	***WHITE***				***210.80***	***92***	***92***
5	***PINK***				***209.80***	***84***	***75***
6	ORANGE				208.50	31	31
7	***WHITE***				***208.40***	***98***	***98***
8	***PINK***				***207.80***	***99***	***95***
9	ORANGE				207.60	45	45
10	WHITE				208.20	31	31
					Total	**625**	**612**

	LINE LENGTH	LTAR GPD/FT^2	SYSTEM TYPE	SOIL LTAR GPD/FT^2	TRENCH SYSTEM	DISTRIBUTION
**** System***	***360***	***0.25***	***ACCEPT.***	***0.25***	***25% RED.***	**PRESSURE MANIFOLD**
Repair	252	0.25	*MOD.*	0.25	PPBPS	LOW PRESSURE

Notes:

**Elevations Obtained by Don Allen & Associates Surveying

**All measures in feet

**Nitrification lines are demonstrated on contour via colored pin flags

**BS, HI, and FS indicate rod readings

Shepherds Bluff Lot 28

System

Line #	Color	Elev	Length	Hole Size	Flow/Tap	gpd	Trench Area	Line LTAR
4	*WHITE*	*210.80*	92	SCH 40 3/4	**12.5**	84.03	276	0.30
5	*PINK*	*209.80*	75	SCH 80 3/4	**10.1**	67.90	225	0.30
7	*WHITE*	*208.40*	98	SCH 40 3/4	**12.5**	84.03	294	0.29
8	*PINK*	*207.80*	95	SCH 40 3/4	**12.5**	84.03	285	0.29
	total	**feet =**	**360**	**gal/min =**	**47.6**			
			Des. Flow	**320**				
			Pump Run=	**6.72**				
			LTAR	**0.25**				
			LTAR + 5%	**0.2625**				
			LTAR w / INNOV	**0.333333333**				
			LTAR w / INNOV + 5%	**0.35**				

Some lines flagged longer in the field, shorten to lengths shown here

CALCULATIONS

Location Shepherds Bluff

Project Number 01-1064

Lot No: Lot 28

No. of Bedrooms	3	
Design Flow	360	$^{gal}/_{day}$
LTAR	0.25	$^{gpd/ft^2}$
25% RED.? (YES OR NO)	YES	
Supply Line Length	138	ft.
Supply Line Volume	24.012	gal.
Required Feet of Line	360	ft.
Amount of Line from Layout	360	ft.
Gallons per Minute	47.6	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Minimum Standard Tank Size	1000	
Lateral Line Volume	235.08	gal.
Dosing Volume	164.56	gal.

Note: Dosing Volume based on70% of lateral line volume

Tank Draw Down	7.8	*Generic Draw Down of 21 gal.per in.*
Pump Run Time	3.46	minutes
Elevation Head	15.5	ft.
Pressure Head	2	ft.
Friction Factor	4.28	ft./100 ft. *(From the interpolater.)*
Friction Head	5.91	ft.
Total Dynamic Head (+15%)	26.92	ft.

FRICTION FACTOR INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42