IREDELL COUNTY HEALTH DEPARTMENT

STATESVILLE 704-878-5305 MOORESVILLE 704-664-5281

IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM INSPECTION

PERMIT # _____ PIN # 4664249689 DATE 7-30-2012

OWNER or APPLICANT Martha Strawn PHONE: Business _____ Home: 704 892-5130

OWNER or APPLICANT ADDRESS P.O. Box 936 Davidson, NC 28036 (Front on Property in Meek Co.)

LOCATION / DIRECTIONS Shearers Rd (S) TR Greystone past Abersham subdivision to 1st drive on right (address off front 3301

SUBDIVISION _____ BLOCK / SECT _____ LOT # _____ LOT AREA 9ac. DESIGN FLOW 480 L.T.A.R. 3

Existing Septic Tank 1000 Gallons: STB _____ Date _____

Pump Tank _____ Gallons: P T _____ Date _____

Pump Make _____ Model _____ Serial # _____

Nitrification Field No Fields 1 No Lines 4 Linear Feet 200

Trench Width 36" Max. Trench Bottom Depth 30" Gravel Depth N/A

☐ New System ☐ Repair ☒ Expansion System Type I II III IV V VI

System Description Gravity - 25% Reduction

Repair System Description Modified Conventional

Maintenance Agreement Required ☐ YES ☒ NO

☒ GRAVITY ☐ PRESSURE

☒ Residence No. Bedrooms 4 ☐ Business No. Persons _____ ☐ Other No. Employees _____ ☐ Slab ☒ Crawl Space ☐ Basement w/plumbing ☐ Basement w/o plumbing

Water Supply ☒ Private ☐ Public ☐ Community

Magnolia tree on left of drive

Upgrade to Exist System

Comments / Conditions

Lean Shed

Pool House

INITIAL SITE SKETCH

Scale 1:60

Road Drive

Pool 15'

Sleeve & bury Supply line 30"

Existing Dwelling

Tool Shed

Addition

22 x 25'

Existing House

Drive

Iredell County Line

Meek Co Line

Studio

To Greystone Rd

Comments / Conditions Hook onto end of existing drainfield (bury Supply line 30" under drive or sleeve in ductile iron

Install 4 lines @ 50ft ea to upgrade to 4 Bedrooms

Note: 2 lines @ 50ft ea (100ft Total) for 3 Bedroom.

AS BUILT SKETCH

Must Keep Septic System at least 5ft from any Building

Consult with Iredell Co HD prior to installation.

Installed (New) 4 Lines

1-50', 2-75' lines

Serial Dist.

(Connected onto end of existing System)

The proposed / existing 22'x25' Addition addition does not appear to impact the existing septic system.

**NOTE: Must keep Building at least 5ft from Septic

Number of Total Bedrooms Date: 5/28/14 Maria Watson R.S.

Can not exceed 4 CHD-Environmental Health Division

Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system.

☐ IMPROVEMENT PERMIT w / plat valid without expiration ☐ IMPROVEMENT PERMIT w / site plan valid for 60 mos. ☐ AUTHORIZATION TO CONSTRUCT valid for period equal to IMPROVEMENT PERMIT-not to exceed 60 mo.

Owner / Applicant Signature: Martha A Strawn Date 8/31/12

Improvement Permit by: Maria Watson RS Date 7/30/12

Authorization to Construct by: Maria Watson RS Date 7/30/12


Installed by: E J Ervin RS


Operation Permit by: Maria Watson Date: 11/13/12

Existing System Inspected by: _____ Date: _____

YOU SHOULD CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION.

WHITE COPY Environmental Health YELLOW COPY (Final) Owner / Applicant PINK COPY (Initial) Owner / Applicant


Log Cabin
Built in 1802
Ray said it's a "cool" place


Please call
Ray Kelly Mobile
704-936-7874
When you go out
to inspect.