STATE OF NORTH CAROLINA
COUNTY OF IREDELL

AGREEMENT FOR INSPECTIONS OF ON-SITE WASTEWATER SYSTEM

This Agreement is entered into this 21st day of September 2007, by and between Michael C. Jones (hereinafter the "Owner") and Xtreme Wastewater Management of Newton, NC (hereinafter the "Contractor").

WITNESSETH

WHEREAS, the Owner owns or controls the property upon which a ground absorption sewage treatment system (hereinafter "system") is installed, such system being designated a Type IVA System under the Rules for Sanitary Sewage Collection, Treatment and Disposal found at 15A NC Administrative Code 18A.1900 et seq; and

WHEREAS, 15A NC Administrative Code 18A.1961 requires a contract to be executed between the system owner and a management entity prior to the issuance of an Operation Permit for said system; and

WHEREAS, 15A NC Administrative Code 18A 1961 requires that a condition of the Operation Permit for said system be that a property executed contract between the system owner and a management entity shall be in effect for as long as the system is in use; and

WHEREAS, the Contractor is a management entity of a type authorized by 15A NC Administrative Code18A. 1961 to manage a Type IVA System.

NOW, THEREFORE, in consideration of the premises and of the mutual covenants and promises contained in this Agreement, it is hereby agreed by and between the Owner and the Contractor as stipulated below.

1. The Contractor's Obligations. The Contractor shall perform the following services on the Owner's system located at 113 Huntington Ridge Place, Mooresville, N.C. Huntington Ridge Lot #10
   a. The contractor shall inspect the system at least at the frequency required in Table V (b) of 15A NC Administrative Code 18A 1961 for a Type IVA System.
   b. The Contractor shall perform the following routine maintenance procedures in accordance with the conditions of the Operation Permit.
      1. Inspect the structural integrity and maintain all of the physical and mechanical components of the system.
      2. Inspect the performance and condition of the drainfield.
      3. Flush and clean the laterals of the system.
      4. Check and set pressures in the system.
      5. Check and adjust pump delivery rate of the system.
      6. Clean septic tank filter if applicable and accessible.
      7. Perform any other requirements of the Operation Permit.
   c. The Contractor shall report the results of its inspections to the local health department at the frequency specified in Table V (b) NC Administrative Code 18A. 1961(b) for a Type IVA System.
   d. If an inspection indicates the need for system repairs, the Contractor shall notify the local health department within 48 hours of the inspection.
   e. The Contractor shall notify the Owner of needed repairs which are outside of the scope of routine maintenance described in subparagraph (b) above. The Contractor shall perform necessary repairs to the system that require the use of hand tools only at the request of the Owner and shall be entitled to payment therefore at the