CALCULATIONS

Location ANNISTON SUBDIVISION

Project Number 01-1005

Lot No: LOT 27

No. of Bedrooms	4	
Design Flow	480	$^{gal}/_{day}$
LTAR	0.3	$^{gal}/_{ft^2\ day}$
25% RED.? (YES OR NO)	YES	
Supply Line Length	703	ft.
Supply Line Volume	122.322	gal.
Required Feet of Line	400	ft.
Amount of Line from Layout	399	ft.
Gallons per Minute	21.33	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Minimum Standard Tank Size	1000	
Lateral Line Volume	260.547	gal.
Dosing Volume	182.38	gal.

Note: Dosing Volume based on70% of lateral line volume

Tank Draw Down	8.7	*Generic Draw Down of 21 gal.per in.*
Pump Run Time	8.55	minutes
Elevation Head	18	ft.
Pressure Head	2	ft.
Friction Factor	0.84	ft./100 ft. *(From the interpolater.)*
Friction Head	5.91	ft.
Total Dynamic Head (+15%)	29.79	ft.

FRICTION FACTOR INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42