
CABINET BLOCKING NOTES	
VANITY BASE BATH CABINETS	30" CENTER ABOVE FINISHED FLOOR
KITCHEN BASE CABINETS	34 1/2" CENTER ABOVE FINISHED FLOOR
BOTTOM OF WALL UPPER	54" CENTER ABOVE FINISHED FLOOR
TOP OF WALL UPPER 30" CABINET	84" CENTER ABOVE FINISHED FLOOR
TOP OF WALL UPPER 36" CABINET	90" CENTER ABOVE FINISHED FLOOR
TOP OF WALL UPPER 42" CABINET	96" CENTER ABOVE FINISHED FLOOR

104


NOTE:
1. Openings between the garage and residence shall be equipped with either a solid wood door not less than 1 3/8" in thickness or 20-minute fire-rated doors.
2. The garage shall be separated from the residence and its attic by means of minimum 1/2" gypsum board applied to the garage side.
3. Garage and carport floor surfaces shall be of approved noncombustible material. That area of floor used for parking of automobiles or other vehicles shall be sloped to facilitate the movement of liquids to a drain or toward the main vehicle entry doorway.
4. The total area under the floor shall be treated to prevent termite infestation.


AREA CALCULATIONS


First Floor Heated: 2194 sf
Second Floor Heated: 1547 sf
Garage: 662 sf
Porch: 60 sf
Deck: 152 sf
TOTAL AREA 4463 sf



RAISED HEARTH FRAMING DETAIL







Acknowledgement Of Plans Submittal ONLY
Date 1-11-08
Date 1-11-08

Full Brick Veneer
10' Ceiling Height on First Floor
8' Tall Doors 8' Window Hdr. Ht.
Double Hung Windows

N BLOCK DEVELOPMENT CORPORATION
300 MCGILL AVENUE N.W.
CONCORD, NC
(704) 788-4818 FAX (704) 784-3720

LOT #103
ANNISTON

FIRST FLOOR
FLOOR PLAN

DATE: 10/10/2007
PLAN: PRESTON
SCALE: 1/4"=1'-0"
DRAWN BY: WCO
ESTIMATED BY: AK
CHECKED BY: MN
SHEET NO. 4FF