IREDELL COUNTY HEALTH DEPARTMENT

Statesville Office (704) 878-5305 | Mooresville Office (704) 660-3625 | PERMIT # 312790

SEPTIC IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM

PIN # 4666489820

APPLICANT/OWNER: Greybrook Homes | APPLICANT ADDRESS: 11220 Elm Ln Suite 109 Charlotte, NC 28277

SITE ADDRESS: 176 Riverstone Dr Davidson, NC 28036 | PHONE: 704 507-6327 | ALT. PHONE

SITE DIRECTIONS: Shearers Rd South TL Anniston Way TR Burnell TL Walking Horse TL TR Riverstone

SUBDIVISION: Riverstone @ Anniston | SECTION: 1 | LOT # 14 | LOT AREA: .512 Acre | SAP CONTROLLED: ☐ YES ☒ NO | DESIGN FLOW: 480gpd | L.T.A.R.: .25


Septic Tank	1000	(gal)	STB 854	Date	6-30-21	☒ New System	☐ Repair	☐ Expansion	System Type: I II III IV V VI	☒ Residence	No. Bedrooms 4
Pump Tank	1000	(gal)	PT 169	Date	7-9-2021	System Description:	LP PPBPS			☐ Business	No. Persons 8
Pump Make	Gulds	Model	WE 0312MV	Serial #	53 HP	Repair System Description:	LP PPBPS			☐ Other	No. Employees
# Nitrification Fields	1	# Lines	4	Linear Ft.	320	Maintenance Agreement Required:	☒ YES	☐ NO		☐ Slab	☒ Crawl Space
Trench Width	24" min	Trench Bottom Depth(Low side)	33"	Gravel Depth	N/A		☐ GRAVITY	☒ PRESSURE		☐ Basement w/plumbing	☐ Basement w/o plumbing

Water Supply: ☒ Private ☐ Public ☐ Community

Comments / Conditions: Divert surface/ storm water away from Septic area.
Dose volume = 259.2gal Pump run 8.78 minutes
Pressure head = 2ft

Note: Drain lines exceeding 70ft need 1 1/2" pipe thru panels
*Any foundation drains must be a minimum of 10ft from Septic Lines Installed as Drawn

INITIAL SITE SKETCH



AS BUILT SKETCH

Scale 1:40

	Date	Initials
Drain Lines Checked	10-13-21	
Tanks Checked	10-13-21	
Pressure Manifold or Valve Box Checked	10-13-21	
Pressure Head Set	1-5-22	
Electrical Checked	1-5-22	
Floats Set	1-5-22	
Alarm Checked	1-5-22	
Maintenance Contract (Y) N	1-5-22	
Comments:		

Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system. CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION

☐ IMPROVEMENT PERMIT *with plat* valid without expiration. ☒ IMPROVEMENT PERMIT *with site plan* valid for 60 mos. ☒ AUTHORIZATION TO CONSTRUCT valid for period equal to IMPROVEMENT PERMIT--not to exceed 60 mo.

Owner / Applicant Signature: _____ Date: 1/29/21 Installed by: A-1 Backhoe

IMPROVEMENT PERMIT by: _____ Date: 1/22/2021 OPERATION PERMIT by: _____ Date: 1-5-2022

AUTHORIZATION TO CONSTRUCT by: _____ Date: 1/29/2021 Existing System Inspected by: _____ Date: _____

LOW PRESSURE PPBPS SYSTEM
INSTALL SPECIFICATIONS

Location RIVERSTONE AT ANNISTON LOT 14

Owner/Applicant Information

Owner: RUFUS ROAD PARTNERS LLC
Address: 11220 ELM LN. SUITE 107
CHARLOTTE, NC 28277
Client: JOE DORITY
Phone Number: 803-381-5921

Approved
5/30/18
MP

Source of Wastewater Flow: 4 Bedroom Single Family Residence
Estimated Gallons Per Day Flow: 480
System Flow: 29.52

Design Specifications

Drainfield Size: 320
Required Drainfield Size: 320
Loading Rate (gpd/ft.^{2}): 0.25
Depth of Gravel in Trench: NA (PPBPS)
Gravel Size: NA (PPBPS)
Trench Depth: 33 in.
Trench Width: 24 in.

Septic Tank Size: 1000
Pump Tank Size: 1000

Repair Trench Width: 24 in.
Repair Trench Depth: 33 in.

Estimated Supply Line Length: 9
Supply Line Diameter: 2 in. SCH 40 PVC
Supply Line Volume: 1.57
Dosing Volume: 259.20

Recommended Pump: Iredell County Approved Pump
Recommended Float Controls: Iredell County Approved Controls
Recommended Control Panel: Iredell County Approved Control Panel

Pressure Head: 2 ft.
Friction Head: 0.16
Elevation Head: 7.50
Total Dynamic Head: 11.59

Threaded Union: In Tank
Gate Valves: 1 in Tank
1 per lateral
Check Valves: In Tank
Anti-Siphon Hole: **YES**
Additional Comments: Soil suitability performed by Carolina Soil & Septic Consulting, PLLC

**Pump tank draw down based on a volume basis of 21 gallons per inch. Draw down may vary among pump tank manufacturers.*

DOSING CALCULATIONS

Location RIVERSTONE AT ANNISTON

Lot No: 14

Approved
5/30/18
MD

No. of Bedrooms	4	
Design Flow	480	$^{gal}/_{day}$
LTAR	0.250	$^{gal}/_{ft^2\ day}$
PPBPS? (YES OR NO)	YES	
Supply Line Length	9	ft.
Supply Line Volume	1.566	gal.
Required Feet of Line	320	ft.
Amount of Line from Layout	320	ft.
Gallons per Minute	29.52	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Minimum Standard Tank Size	1000	
Panel Volume	3.6	gal.
# of Panels	72	
Dosing Volume	259.20	gal.

Note: Dosing Volume based on 100% of # of panels times 3.6 gal/panel

FRICTION FACTOR INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42

Tank Draw Down	12.3	*Generic Draw Down of 21 gal.per in.*
Pump Run Time	8.78	minutes
Elevation Head	7.5	ft.
Pressure Head	2	ft.
Friction Factor	1.78	ft./100 ft. *(From the interpolater.)*
Friction Head	0.16	ft.
Total Dynamic Head (+20%)	11.59	ft.

DEPARTMENT OF HEALTH AND HUMAN SERVICES
DIVISION OF PUBLIC HEALTH, ENVIRONMENTAL HEALTH SECTION
ON-SITE WATER PROTECTION BRANCH

Approved 5/30/18 MD

PROPERTY ID #: 4664898202
COUNTY: IREDELL

SOIL/SITE EVALUATION
***for* ON-SITE WASTEWATER SYSTEM**
(Complete all fields in full)

OWNER: RUFUS RD. PARTNERS LLC
ADDRESS: 11220 ELM. LN. SUITE 107, CHARLOTTE, NC 28277
PROPOSED FACILITY: SFR
PROPOSED DESIGN FLOW (.1949): 480
LOCATION OF SITE: RIVERSTONE AT ANNISTON LOT 14

APPLICATION DATE 3-20-18
DATE EVALUATED: 3-19-18
PROPERTY SIZE: .512 AC
PROPERTY RECORDED: YES

WATER SUPPLY: Ξ Private ☐ Public ☐ Well ☐ Spring ☐ Other
EVALUATION METHOD: ☐ Auger Boring Ξ Pit ☐ Cut
TYPE OF WASTEWATER: Ξ Sewage ☐ Industrial Process ☐ Mixed

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
PIT 1	LSS 10%	0-4	BRSCL,W,SBK	FR,SS,SP,SEXP	FEW Y/BR @ 22-49"	49"	NA	49"	.25
		4-22	RC,M,SBK	FR,SS,SP,SEXP					
		22-49	RC,S,ABK	FI,S,SP,SEXP					
PIT 2	LSS 10%	0-6	COMPACTED		MANG @ 44-56"	56"	NA	56"	.275
		6-33	RC,S,ABK	FI,S,SP,SEXP					
		33-56	RC,M,ABK	FI,S,SP,SEXP					
PIT 3	LSS 10%	0-3	COMPACTED		NA	57"	NA	57"	.3
		3-18	BR/RC,M,SBK	FR,SS,SP,SEXP					
		18-57	RC,S,ABK	FI,S,SP,SEXP					
PIT 4	LSS	0-5	BRSCL,W,SBK	FR,SS,SP,SEXP	MANG @ 30-48"	48"	NA	48"	.25
		5-15	RC,M,ABK	FR,SS,SP,SEXP					
		15-48	RC,S,ABK	FI,S,SP,SEXP					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	PS	PS
System Type(s)	LP PPBPS	LP PPBPS
Site LTAR	.275	.25

OTHER FACTORS (.1946): NONE
SITE CLASSIFICATION (.1948): PS

EVALUATED BY: BEN ALDRIDGE
OTHER(S) PRESENT: JACOB CONRAD, DAVID BEANE

COMMENTS:

RECEIVED NOV 2 4 2020

IREDELL COUNTY DEPARTMENT of ENVIRONMENTAL HEALTH

APPLICATION FORM

intermediate

AP-234495
AP-812090 - Fees
$320.00

Application For: ( ) New Well Permit ( ) Well Repair Permit ( ) Well Abandonment
(X) Septic Improvement Permit ( ) Authorization to Construct ( ) Existing System Inspection ( ) Septic System Repair

THE ABOVE PERMIT DOCUMENTS WILL BECOME INVALID IF INFORMATION PROVIDED ON THIS APPLICATION IS FALSIFIED OR CHANGED, OR IF THE SITE IS ALTERED. THE IMPROVEMENT PERMIT IS VALID FOR EITHER 60 MONTHS OR WITHOUT EXPIRATION DEPENDING UPON DOCUMENTATION SUBMITTED. APPLICATION WITH SITE PLAN 60 MONTHS, APPLICATION WITH COMPLETE, SCALED PLAT WITHOUT EXPIRATION. SEE 15A NCAC 18A .1937(f) FOR DETAILS.

Page 2: *Site Plan Worksheet* form MUST accompany this application

The following optional attachments may also be submitted: ( ) Survey Plat, scaled no more than 1 inch = 60 feet
Place an (X) *beside whichever is submitted if applicable* ( ) Custom Site Plan, scaled no more than 1 inch = 60 feet

Applicant Information: (PRINT CLEARLY)

Applicant Name: Greybrook Homes **Address:** 11220 Elm Ln. Suite 109 **Zip:** 28277

Applicant Email: nick@greybrookhomes.com **Phone:** 704-507-6327 **Alt. Phone:**

Owner Name: Rufus Rd Partners **Address:** 11220 Elm Ln. Suite 107 **Zip:** 28277

Owner Email: Joe@greybrookhomes.com **Phone:** 803-381-5921 **Alt. Phone:**

Property Information:

Street Address: 176 Riverstone Dr. Davidson, NC 28036

Subdivision Name: Anniston **Section/Phase:** **Lot Number:** 14

Driving Directions: Shearers Rd to Anniston Way to Burnell to Walking Horse Trail to Riverstone Dr.

Site Development Information: *(check or complete ALL that apply*

CHECK FOUNDATION TYPE

( ) New Single Family Residence
( ) New Multi-Family Residence
( ) Accessory Building
( ) Bedroom(s) Addition
( ) Repair to failing septic system ___ Tank ___ Drain lines **Describe Problem:**

Maximum Number of Bedrooms: 4
Maximum Number of Occupants: 8
( ) Swimming Pool
( ) Other Addition/Structure:

(X) Crawl Space Foundation
( ) Concrete Slab Foundation
( ) Basement with Plumbing
( ) Basement without Plumbing

Non-Residential Site Development: **Type of Business:**
Square Footage of Building: **Max. Number of Employees:** **Max. Number of Seats/Beds/Other:**

Water Supply: ( ) Replacement Well – Reason:
( ) Multi-connection Well **Number of Houses:** **Number of Persons:**

( ) New Well ( ) Existing Well ( ) Community Well ( ) City Water ( ) Other Public Water

Desired Septic System Type: *(you may rank in order of preference)* **Year existing system installed:**
( ) No Preference ( ) Alternative ( ) Conventional ( ) Innovative ( ) Modified Conventional ( ) Other:

Please answer the following to the best of your ability:

( ) Yes ( ) No **Does the site contain any jurisdictional wetlands?**
( ) Yes ( ) No **Is any non-domestic sewage (i.e. industrial) to be generated?**
( ) Yes ( ) No **Is the site subject to approval by any other public agency?**

I have read this application and certify that the information provided herein is true, complete, and correct. Authorized county and state officials are granted right of entry to conduct necessary inspections to determine compliance with applicable laws and rules. I understand that I am solely responsible for the proper identification and labeling of all property lines and corners and making the site accessible so that a complete site evaluation can be performed.

Signature: Nick Belk
Property owner or owner's legal representative signature (SIGNATURE REQUIRED)

11/17/2020
DATE

IREDELL COUNTY DEPARTMENT OF ENVIRONMENTAL HEALTH

DOCUMENTATION TO AUTHORIZE AN OWNER'S LEGAL REPRESENTATIVE

(Check and sign only ONE of the options below)

1. *** APPLICANT AND OWNER ARE THE SAME. *** (*Sign here*) Nick Belk

Applications for permits require the "signature of the owner or owner's legal representative" (15A NCAC 18A .1937). If the owner does not sign the application himself or herself, they can submit any one of the following documents to designate their legal representative: *Power of Attorney; Real Estate Contract; Estate executor; Bankruptcy trustee; Court ordered guardianship*
In the absence of the above documentation, the property owner may provide the local health department with documentation that designates a legal representative. A property owner may:
Complete this form to document his or her legal representative, or provide his or her own form that contains the information in this form. If there are multiple property owners, then all property owners must sign the form that designates a legal representative.
By signing a form that designates a legal representative for purposes of 15A NCAC 18A .1937, the property owner authorizes that representative to act on their behalf in matters pertaining to the application and permitting process, including signing or receiving any application, document or permit. The owner retains full responsibility to meet all permit conditions specified by the local health department.

2. I, Nick Belk, am the legal owner(s) of the property located at _____, identified as

PIN (Parcel Identification Number) 4664-89-8202, located in Iredell County, North Carolina.

I do hereby authorize (**print legal representative/company name**) _____,
Nick Belk, to act as an agent on my behalf in applying for/signing/obtaining any of the documents described below.

- Application for Improvement Permit (IP) / Authorization to Construct (AC)
- Improvement Permit (IP) / Authorization to Construct (AC)
- Application for soil-site evaluation (new/repair)
- Application/permit for private drinking water well/well abandonment
- Application for Compliance Inspection

I agree to abide by all decisions and/or conditions between the legal representative acting on my behalf and the Iredell County Department of Public Health, Environmental Health Division.

Nick Belk
Signature of Owner(s)

11/17/2020
Date

Mooresville - Environmental Health
ronda.hart@co.iredell.nc.us
Fax: 704-662-3239
610 E. Center Avenue, Mooresville, NC 28115


Statesville - Environmental Health
adrienne.shea@co.iredell.nc.us
Fax: 704-871-3483
349 N. Center Street, Statesville, NC 28677


SITE DEVELOPMENT PLAN

PREPARED BY:

DELTA LAND SERVICES, INC.
FIRM LICENSE #C-735
608-G Matthews Mint Hill Road
MATTHEWS, NORTH CAROLINA 28105
(704) 847-4700

THIS SITE PLAN IS TO SHOW THE PROPOSED LOCATION OF THE HOUSE ON THE LOT AND IS NOT TO BE RELIED UPON FOR CONSTRUCTION.





STAKEOUT ☐

NOT FOR RECORDATION, CONVEYANCES OR SALES

Subdivision RIVERSTONE AT ANNISTON County IREDELL
Address 176 RIVERSTONE DRIVE Owner CONCEPT
Lot 14 Block ___ Plan berkeley Elevation C Drive (Left) ___ (Right) X (Courtyard) ___ Deck ___
Patio ___ Fireplace ___ Garage (1 Car) ___ (2 Car) ___ (3 Car) X Brick ___ Basement ___ Curtain Wall ___
Crawl ___ Slab X Other REAR COVERED PORCH

REVISED: DWN: TMM CKD: DATE: 08/ 28/ 20

General Floor Plan Notes

General Floor Plan Notes shall apply unless noted otherwise on plan.


1. Wall Heights: Typically 9'-1-1/2" at first floor and second floor, and 8' 1-1/2" at attics U.N.O.. All walls are constructed using a double top plate. Splices at Double Top Plate do not need to occur at Vertical Studs but must be at least 24" apart from Joint in other Top Plate layer. Special wall heights are noted on plans where they occur.
2. Wall Thickness is typically 4" at exterior walls, 3-1/2" at interior. 2x6 frame shall be used at walls that back up to plumbing fixtures. Walls greater than 10' high shall be framed with 2x6 framing or greater and will be noted as a special condition where it occurs on plan.
3. Header height shall be 7'-8" AFF at First Floor, and 6'-10" AFF at Second Floor unless noted otherwise.
4. Jacks: Openings up to 3'-4" wide shall have (1) 2x4 jack stud SPF on each side. Openings greater than 3'-4" wide shall have (2) 2x4 jack studs SPF on each side.
5. Soffit, Coffered Ceilings, Trey Ceilings and other significant ceiling plan elements are shown on the floor plans and are denoted as single dashed lines. Unless specifically call out as included, Kitchens do not include soffits over wall cabinetry.
6. Door & Window frames, where occurring near corners, shall be a minimum of 4-1/2" from corner. Except for walk-in closets with doors near a corner, doors at closets shall be centered on closet.
7. Windows: Shall have at least (1) window in each sleeping room, that meets egress. Shall be provided with tempered glass at hazardous glazing areas. Fake windows shall be installed with obscure glazing.
8. Closets for clothing or coat storage shall be equipped with 1 rod/shelf, open wire. Closets for linen shall have 5 open wire shelves. Closets for pantries shall have 5 wood shelves, painted.
9. Stair treads shall be 10" deep, risers shall be a maximum of 7-3/4", unless noted otherwise.
10. Handrails and Guards at stairs shall be 34" above the finished surface of the ramp surface of the stair. Handrails at landings and overlooks at multilevel spaces shall be 36" above finished floor. Guards (pickets or balusters) shall be spaced with no more than 4" between guards.
11. Attic Access shall be provided at all attic area with a height greater than 30". Minimum clear attic access shall be 20" x 30". Pull down stairs and access doors in knee walls meeting minimum criteria are also acceptable.
12. Garage Door to Living Space shall be 2'-8" x 6'-8" minimum size and shall be 20 minute fire rated and weather sealed.
13. Garage Walls, as a minimum, shall be separated from living space and living space attic by installing 1/2" gypsum board on the garage side of the wall.

Permitted House 70' w 855' deep

61'4.

55'

61.4



See Side load garage 3 Car

SOUTH DESIGNS
(O) 919-556-2226
(F) 919-556-2228
www.southdesigns.com

Concept Homes

REV.#	DESCRIPTION	DATE
1	PROTOTYPE WALK CHANGES, ELECTRICAL, ADDED SIGN, PORCH OPT	10/9/2018
2	---	---
3	---	---
4	---	---
5	---	---
6	---	---

3141 - COLUMBIA - RH
SIGNATURE COLLECTION
First Floor Plan 'C'

DRAWN BY:	South Designs
ISSUE DATE	12/18/2018
CURRENT REVISION DATE:	12/18/2018
SCALE	1/8" = 1'-0"
SHEET	2.1c


Plan ... ate 1/22/2021

... ate ____

General Floor Plan Notes

General Floor Plan Notes shall apply unless noted otherwise on plan.

1. Wall Heights: Typically 9'-1-1/2" at first floor and second floor, and 8'-1-1/2" at attics U.N.O.. All walls are constructed using a double top plate. Splices of Double Top Plate do not need to occur at Vertical Studs but must be at least 24" apart from joint in other Top Plate layer. Special wall heights are noted on plans where they occur.
2. Wall Thickness is typically 4" at exterior walls, 3-1/2" at interior. 2x6 frame shall be used at walls that back up to plumbing fixtures. Walls greater than 10' high shall be framed with 2x6 framing or greater and will be noted as a special condition where it occurs on plan.
3. Header height shall be 7'-8" AFF at First Floor, and 6'-10" AFF at Second Floor unless noted otherwise.
4. Jacks: Openings up to 3'-4" wide shall have (1) 2x4 jack stud SPF on each side. Openings greater than 3'-4" wide shall have (2) 2x4 jack studs SPF on each side.
5. Soffits, Coffered Ceilings, Tray Ceilings and other significant ceiling plan elements are shown on the floor plans and are denoted as single dashed lines. Unless specifically call out as included, Kitchens do not include soffits over wall cabinetry.
6. Door & Window Frames, where occuring near corners, shall be a minimum of 4-1/2" from corner. Except for walk-in closets with doors near a corner, doors at closets shall be centered on closet.
7. Windows: Shall have at least (1) window in each sleeping room, that meets egress. Shall be provided with tempered glass at hazardous glazing areas. False windows shall be installed with obscure glazing.
8. Closets for clothing or coat storage shall be equipped with 1 rod/shelf, open wire. Closets for linen shall have 5 open wire shelves. Closets for pantries shall have 5 wood shelves, painted.
9. Stair treads shall be 10" deep, risers shall be a maximum of 7-3/4", unless noted otherwise.
10. Handrails and Guards at stairs shall be 34" above the finished surface of the ramp surface of the stair. Handrails at landings and overlooks of multilevel spaces shall be 36" above finished floor. Guards (pickets or ballisters) shall be spaced with no more than 4" between guards.
11. Attic Access shall be provided at all attic area with a height greater than 30". Minimum clear attic access shall be 20" x 30". Pull down stairs and access doors in knee walls meeting minimum criteria are also acceptable.
12. Garage Door to Living Space shall be 3'-0" x 6'-8" minimum size and shall be 20 minute fire rated and weather sealed.
13. Garage Walls, as a minimum, shall be separated from living space and living space attic by installing 1/2" gypsum board on the garage side of the wall.



SECOND FLOOR OPT. GAMEROOM PLAN 'C'

SCALE: 1/8"=1'-0" ON 11x17, 1/4"=1'-0" ON 22x34

SOUTH DESIGNS
(O) 919-556-2226
(F) 919-556-2228
www.southdesigns.com

Concept Homes

REV. #	DESCRIPTION	DATE
1	PROTOTYPE WALK CHANGES, ELECTRICAL, ADDED SIGN, PORCH OPT	10/19/2018
2	-	-
3	-	-
4	-	-
5	-	-
6	-	-
7	-	-
8	-	-

3141 - COLUMBIA - RH
SIGNATURE COLLECTION
Second Floor Plan 'C'

DRAWN BY: South Designs
ISSUE DATE: 12/18/2018
CURRENT REVISION DATE: 12/18/2018
SCALE: 1/8" = 1'-0"
SHEET: 2.2c

Plan[illegible] ONL[illegible]
Maria Dobson 1/22/24
ate

IREDELL COUNTY

PO Box 788
349 North Center St.
Statesville, NC 28677

APPLICATION NUMBER
234495
Issue Date: 03/29/2018

ZONING PERMIT

Parcel Number	Street Address	Jurisdiction
4664898202.000	176 RIVERSTONE DRIVE, DAVIDSON, NC 28036	

Owner Information		Applicant Information	
Owner:	RUFUS ROAD PARTNERS LLC	Applicant:	CAROLINA SOIL SEPTIC C
Address:	242 JOHNSON DAIRY ROAD	Address:	162 WEST B ST
	MOORESVILLE, NC 28115		KANNAPOLIS, NC 28081
Phone:		Phone:	704-202-5791

Use Requested	Zone Code
SFD	

Lot Acreage	F Setback	B Setback	L Setback	R Setback	Watershed	Flood Zone
	35.00	35.00	15.00	15.00	NOT	X

Remarks:

The applicant certifies that there are no deed restrictions, contractual agreements or governmental regulations of any kind that interfere with or prohibit the use of the property or the use for which this permit is requested. The applicant further acknowledges that enforcement of deed restrictions, plat conditions and other contractual agreements will not be undertaken by Iredell County and is the sole responsibility of the affected parties.

Applicant: _____ Date: _____

Permit Number	133876	TOTAL FEES:	$ 77.25