CALCULATIONS

Location WALDED RIDGE SUBDIVISION

Project Number 01-1069

Lot No: Lot 53

No. of Bedrooms	4	
Design Flow	480	$^{gal}/_{day}$
LTAR	.3 gpd/ft²	
25% RED.? (YES OR NO)	YES	
Supply Line Length	190	ft.
Supply Line Volume	33.06	gal.
Required Feet of Line	400	ft.
Amount of Line from Layout	400	ft.
Gallons per Minute	28.44	$^{gal}/_{min}$
Required Septic Tank Capacity	1000	gal.
Minimum Standard Tank Size	1000	
Lateral Line Volume	261.2	gal.
Dosing Volume	182.84	gal.
	Note: Dosing Volume based on70% of lateral line volume	
Tank Draw Down	8.7	*Generic Draw Down of 21 gal.per in.*
Pump Run Time	6.43	minutes
Elevation Head	35.8	ft.
Pressure Head	2	ft.
Friction Factor	1.78	ft./100 ft. *(From the interpolater.)*
Friction Head	3.38	ft.
Total Dynamic Head (+15%)	47.36	ft.

FRICTION FACTOR INTERPOLATER
2" SCH 40 PVC

GPM	*f*
20	0.84
	-0.88
25	1.27
	-1.28
30	1.78
	-1.76
35	2.37
	-2.25
40	3.03
43.07	3.48
45	3.77
48.14	4.28
50	4.58
57.11	5.89
60	6.42