DOOR SCHEDULE

SYMBOL ◯

MARK	SIZE	QUAN.	DESCRIPTION
1	3'-0" x 6'-8"	1	EXT., THREE-QUARTER GLASS, W/ (2) 12" SIDELITES & 12" ARCHED TRANSOM
2	(2) 2'-6" x 6'-8"	2	EXT., FULL GLASS, W/ 12" TRANSOM
3	2'-8" x 6'-8"	1	EXT., 1 HOUR FIRE-RATED
4	16'-0" x 7'-0"	1	GARAGE
5	2'-8" x 6'-8"	5	INT.
6	2'-4" x 6'-8"	3	INT.
7	2'-0" x 6'-8"	6	INT.
8	(2) 2'-0" x 6'-8"	4	INT.

WINDOW SCHEDULE

SYMBOL ▭

MARK	SIZE	QUAN.	DESCRIPTION
A	(2) 2'-0" x 5'-10"	1	DH
B	2'-8" x 5'-10"	1	DH, ARCH TOP
C	3'-0" x 4'-6"	1	* DH W/ 12" ARCH TRANSOM
	1'-8" x 4'-6"	2	* DH W/ 12" ARCH TRANSOM
D	1'-8" x 3'-10"	1	DH
E	(2) 2'-5" x 2'-11"	1	CSMT, ARCH TOP FIXED
F	(2) 2'-8" x 6'-2"	4	DH
G	(3) 2'-8" x 6'-2"	2	DH
H	2'-8" x 4'-2"	1	DH
J	4'-0" x 4'-2"	1	FIXED
K	1'-9 1/2" x 3'-2 1/2"	4	** VELUX SKYLIGHT FSF-104
L	2'-8" x 6'-2"	1	DH
M	1'-8" x 6'-2"	2	DH
N	3'-4" x 6'-2"	1	DH
P	3'-0" x 5'-10"	1	DH
Q	1'-4" x 3'-2"	1	FIXED, ARCH TOP

ALL WINDOWS ARE INSULATED AND WEATHERSTRIPPED.

VERIFY LOCAL CODE EGRESS WINDOW REQUIREMENTS PRIOR TO CONSTRUCTION

WINDOW MANUFACTURER TO PROVIDE TEMPERED GLASS WHERE REQUIRED BY CODE.

* SEE ELEVATION FOR TRANSOM.

** VERIFY SKYLIGHT INSTALLATION REQUIREMENTS BEFORE CONSTRUCTION. IF CURB INSTALLATION IS RECOMMENDED DUE TO CLIMATIC CONDITIONS, MODEL NUMBER AND/OR ROUGH OPENING SIZE MAY VARY.

ELECTRICAL LEGEND

SYMBOL	DESCRIPTION
	DUPLEX OUTLET (GROUNDED TYPE)
UP	WEATHER PROOF DUPLEX OUTLET
	ABOVE COUNTER LOCATION
	FLUSH FLOOR DUPLEX OUTLET, OWNER VERIFY LOCATION
	220 VOLT OUTLET OR CONNECTION
	CEILING MOUNTED LIGHT FIXTURE
	WALL BRACKET MOUNTED LIGHT FIXTURE
	SUSPENDED CEILING MOUNTED LIGHT FIXTURE
	RECESSED DIRECTIONAL CEILING LIGHT FIXTURE
	RECESSED CEILING LIGHT FIXTURE
W	RECESSED LIGHT FOR WET AREA
	UNDER COUNTER FLUORESCENT LIGHT
	EXTERIOR CAST ALUMINUM FLOOD LIGHTS
	CEILING MOUNTED PADDLE FAN w/ LIGHT
	CEILING MOUNTED FAN - EXHAUST
	CEILING MOUNTED FAN AND HEATER
	CEILING MOUNTED FAN, LIGHT, AND HEATER

PLAN NOTES:

1. VERIFY ALL LOCAL CODES, ENERGY TYPES, AND SITE CONDITIONS PRIOR TO CONSTRUCTION.
2. REVIEW SELECTED MECHANICAL SYSTEMS WITH OWNER PRIOR TO CONSTRUCTION. RECOMMENDED LOCATIONS ARE AS FOLLOWS: THE WATER HEATER MAY TYPICALLY BE PLACED IN THE CRAWL SPACE OR IN THE GARAGE. H.V.A.C. UNIT(S) MAY TYPICALLY BE PLACED, IN THE CRAWL SPACE OR IN THE ATTIC FOR ONE STORY HOUSES, IN THE CRAWL SPACE FOR THE FIRST FLOOR AND IN ATTIC FOR THE SECOND ~~FLOOR IN TWO STORY HOUSES.~~ H.V.A.C. EQUIPMENT IN ATTIC SPACE SHALL BE ACCESSIBLE BY AN OPENING AS LARGE AS THE LARGEST PIECE OF EQUIPMENT AND IN NO CASE LESS THAN 22"X36".
3. SEE STRUCTURAL DRAWINGS FOR ADDITIONAL INFORMATION.
4. INSULATE AROUND ALL BATHS AND UTILITY ROOM.
5. TYPICAL WALL, 2X4'S @ 16" O.C., UNLESS OTHERWISE DIMENSIONED.
6. PROVIDE SMOKE DETECTORS AS REQUIRED BY CODE.
7. PROVIDE DOORBELLS, TRANSFORMER, AND CHIME.

Acknowledgement Of Plans Submittal ONLY!

Date 5-22-13

Date 5-22-13

