BLDR - 2023 - 35230

ICHD - ENVIRONMENTAL HEALTH DIVISION

Statesville Office (704) 878-5305 Mooresville Office (704) 660-3625

PERMIT # OSWP-2023-18657

SEPTIC: IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM

PIN # 4711-23-9421

APPLICANT / OWNER: Michael Athanas & Associates | APPLICANT ADDRESS: 2630 Statesville Blvd, Salisbury, NC 28147

SITE ADDRESS: 106 WINDBLUFF CT, STATESVILLE, NC 28677 | PHONE: 7043101832 | ALT. PHONE:

SITE DIRECTIONS: Laurel Cove Rd to Harbor Watch to Harbor Ridge to Wind Bluff | SAP CONTROLLED: YES ☐ NO ☒

SUBDIVISION: Harbor Watch | SECTION: 54 | LOT #: 163 | LOT AREA: 1.13 | DESIGN FLOW: 600 | L.T.A.R.: .30

Septic Tank: (gal) 1500	STB:	Date:	☐ New System ☐ Repair ☐ Expansion	System Type: III	☑ Residence	No. Bedrooms: 5	Water Supply:
Pump Tank: (gal) 1500	PT:	Date:	System Description: PM-25% Reduction		☐ Business	No. Persons: 10	
Pump Make:	Model:	Serial #:	Repair System Description: PPBPS-50% Reduction		☐ Other	No. Employees:	
# Nitrification Fields: 1	# Lines: 4	Linear Ft.: 500	Maintenance Agreement Required: ☐ YES ☒ NO		☐ Slab	☐ Crawl Space	
Trench Width: 36in	Trench Bottom Depth (Low side): 24in.		Gravel Depth: –	☐ GRAVITY ☑ PRESSURE	☑ Basement w/ Plumbing	☐ Basement w/o Plumbing	

Comments / Conditions: * Lines may be moved if necessary

INITIAL SITE SKETCH

See attached Site Plan and Design by Michael Athanas + Associates

AS BUILT SKETCH

Lines
PM
Pump Line } SH 6/21/24

PH
Electrical MW
Alarm 1/31/25
Floats

Permit can be suspended or revoked if any false information is supplied toward securing the permit / any unauthorized changes are made to the site / any unauthorized changes are made in the installation of the system. CONTACT A LOCATOR SERVICE PRIOR TO ANY EXCAVATION

☐ IMPROVEMENT PERMIT with plat valid without expiration. ☑ IMPROVEMENT PERMIT with site plan valid for 60 mos. ☑ AUTHORIZATION TO CONSTRUCT valid for period equal to IMPROVEMENT PERMIT--not to exceed 60 mo.

Owner / Applicant Signature: | Date:

IMPROVEMENT PERMIT by: Benjamin A. Boger | Date: 3/28/2023


AUTHORIZATION TO CONSTRUCT by: Benjamin C. White | Date: 8-28-2023

Installed By: Abernathy

OPERATION PERMIT by: MW | Date: 1/31/25

Existing System Inspected By: | Date:

FOR SEPTIC FINAL INSPECTION CALL: 704-664-3703 BETWEEN 8am-9am the day the inspection is needed.



Harbor Ridge Dr

MA&A
SOIL & ENVIRONMENTAL CONSULTANTS

MICHAEL ATHANAS & ASSOCIATES
LICENSED SOIL SCIENTIST
556 Walden Trail
Weddington, NC 28173
(704) 576-3887
2/27/2023

Reference: Data Sheet for 106 Windbluff Ct, Harbor Watch Lot 163
House Footprint: 75' x 75'
Building Setbacks: 35' front/rear, 15' side, 25' side street
Water Source: Private well
Number of Bedrooms/Daily Flow: 5/600 GPD
Proposed LTAR: 0.3 GPD/FT^2
Proposed System Type: 25% Reduction
Proposed Repair System Type: PPBPS
Distribution: Pressure manifold
Flow per Tap: 2 @ 7.11 GPM, 2 @ 5.48 GPM
Tap Size and Material: 2 @ ½" SCH 40, 2 @ ½" SCH 80
System Flow: 25.2 GPM
Dosing Volume: 218.8 gallons
Pump Run Time: 8.7 minutes
Elevation Head: 37.6'
Friction Head: 3'
Pressure Head: 2'
Total Dynamic Head: 42.6'
Supply Line Length: 230' of 2" PVC
Septic/Pump Tank Size: 1500/1500 gallons
Proposed Trench Bottom: 24-36"

Line	Design Length	Actual Length	Elevation	
Yellow 1		50'	3.0'	
Blue 2		80'	3.6'	
Orange 3	**140'**	**165'**	**4.7'**	**½" SCH 40**
White 4	**140'**	**150'**	**5.8'**	**½" SCH 40**
Pink 5	**110'**	**135'**	**6.9'**	**½" SCH 80**
Yellow 6	**110'**	**120'**	**8.4'**	**½" SCH 80**
Blue 7		100'	10.1'	
Orange 8		40'	11.5'	
White 9		40'	13.3'	
Blue 10		40'	14.7'	

Initial System: 500'
Pump Tank: 37.3'
Benchmark: 4.1'
Repair System: 350'
House Corner: 35.1'


Comments:
The septic area should be fenced off and the fence maintained during construction. Failure to do so will result in the permit being voided.

Do not grade within 15' of the septic area.

General Floor Plan Notes

General Floor Plan Notes shall apply unless noted otherwise on plan.

1. Wall Heights: Typically 10'-1-1/2" at first floor, 9'-1-1/2" at second floor, and 8' 1-1/2" at attics U.N.O. All walls are constructed using a double top plate. Splices at Double Top Plate do not need to occur at Vertical Studs but must be at least 24" apart from Joint in other Top Plate layer. Special wall heights are noted on plans where they occur.
2. Wall Thickness is typically 4" at exterior walls. 3-1/2" at interior. 2x6 frame shall be used at walls that back up to plumbing fixtures. Walls greater than 10' high shall be framed with 2x6 framing or greater and will be noted as a special condition where it occurs on plan.
3. Header height shall be 8'-0" AFF at First floor, and 7'-4" AFF at Second Floor unless noted otherwise.
4. Jacks: Openings up to 3'-4" wide shall have (1) 2x4 jack stud SPF on each side. Openings greater than 3'-4" wide shall have (2) 2x4 jack studs SPF on each side.
5. Soffits, Coffered Ceilings, Trey Ceilings and other significant ceiling plan elements are shown on the floor plans and are denoted as single dashed lines. Unless specifically call out as included, Kitchens do not include soffits over wall cabinetry.
6. Door & Window Frames, where occurring near corners, shall be a minimum of 4-1/2" from corner. Except for walk-in closets with doors near a corner, doors at closets shall be centered on closet.
7. Windows: Shall have at least (1) window in each sleeping room, that meets egress. Shall be provided with tempered glass at hazardous glazing areas. False windows shall be installed with obscure glazing.
8. Closets for clothing or coat storage shall be equipped with 1 rod/shelf, open wire. Closets for linen shall have 5 open wire shelves. Closets for pantries shall have 5 wood shelves, painted.
9. Stair treads shall be 10" deep, risers shall be a maximum of 7-3/4", unless noted otherwise.
10. Handrails and Guards at stairs shall be 34" above the finished surface of the ramp surface of the stair. Handrails at landings and overlooks of multilevel spaces shall be 34" above finished floor. Guards (pickets or ballisters) shall be spaced with no more than 4" between guards.
11. Attic Access shall be provided at all attic area with a height greater than 30". Minimum clear attic access shall be 20" x 30". Pull down stairs and access doors in knee walls meeting minimum criteria are also acceptable.
12. Garage Door to Living Space shall be 2'-8" x 6'-8" minimum size and shall be 20 minute fire rated and weather sealed.
13. Garage Walls, as a minimum, shall be separated from living space by installing 1/2" gypsum board on the garage side of the wall. With habitable space above, the inside of all garage walls require 1/2" GWB supporting 5/8" type X GWB on ceiling.



FIRST FLOOR PLAN 'A'
SCALE: 1/8"=1'-0" ON 11x17, 1/4"=1'-0" ON 22x34

SOUTH DESIGNS
(O) 919-556-2226
(F) 919-556-2228
www.southdesigns.com

GREYBROOK HOMES

REV. #	DESCRIPTION	DATE


3191 - DAVIDSON - LH
SIGNATURE COLLECTION
First Floor Plan 'A'

DRAWN BY: South Designs
ISSUE DATE: 10/07/2020
CURRENT REVISION DATE: —
SCALE: 1/8" = 1'-0"
SHEET: 2.1a

General Floor Plan Notes

General Floor Plan Notes shall apply unless noted otherwise on plan.

1. **Wall Heights:** Typically 10'-1-1/2" at first floor, 9'-1-1/2" at second floor, and 8' 1-1/2" at attics U.N.O. All walls are constructed using a double top plate. Splices at Double Top Plate do not need to occur at Vertical Studs but must be at least 24" apart from Joint in other Top Plate layer. Special wall heights are noted on plans where they occur.
2. **Wall Thickness** is typically 4" at exterior walls. 3-1/2" at interior. 2x6 frame shall be used at walls that back up to plumbing fixtures. Walls greater than 10' high shall be framed with 2x6 framing or greater and will be noted as a special condition where it occurs on plan.
3. **Header height** shall be 8'-0" AFF at First Floor, and 7'-6" AFF at Second Floor unless noted otherwise.
4. **Jacks:** Openings up to 3'-4" wide shall have (1) 2x4 jack stud SPF on each side. Openings greater than 3'-4" wide shall have (2) 2x4 jack studs SPF on each side.
5. **Soffits, Coffered Ceilings, Trey Ceilings** and other significant ceiling plan elements are shown on the floor plans and are denoted as single dashed lines. Unless specifically call out as included. Kitchens **do not** include soffits over wall cabinetry.
6. **Door & Window Frames**, where occurring near corners, shall be a minimum of 4-1/2" from corner. Except for walk-in closets with doors near a corner, doors at closets shall be centered on closet.
7. **Windows:** Shall have at least (1) window in each sleeping room, that meets egress. Shall be provided with tempered glass at hazardous glazing areas. False windows shall be installed with obscure glazing.
8. **Closets** for clothing or coat storage shall be equipped with 1 rod/shelf, open wire. Closets for linen shall have 5 open wire shelves. Closets for pantries shall have 5 wood shelves, painted.
9. **Stair treads** shall be 10" deep, risers shall be a maximum of 7-3/4", unless noted otherwise.
10. **Handrails and Guards** at stairs shall be 34" above the finished surface of the ramp surface of the stair. Handrails at landings and overlooks of multilevel spaces shall be 36" above finished floor. Guards (pickets or balisters) shall be spaced with no more than 4" between guards.
11. **Attic Access** shall be provided at all attic area with a height greater than 30". Minimum clear attic access shall be 20" x 30". Pull down stairs and access doors in knee walls meeting minimum criteria are also acceptable.
12. **Garage Door to Living Space** shall be 2'-8" x 6'-8" minimum size and shall be 20 minute fire rated and weather sealed.
13. **Garage Walls**, as a minimum, shall be separated from living space by installing 1/2" gypsum board on the garage side of the wall. With habitable space above, the inside of all garage walls require 1/2" GWB supporting 5/8" type X GWB on ceiling.



SECOND FLOOR PLAN 'A'

SCALE: 1/8"=1'-0" ON 11x17, 1/4"=1'-0" ON 22x34

SOUTH DESIGNS
(O) 919-556-2226
(F) 919-556-2228
www.southdesigns.com

GREYBROOK HOMES

REV. #	DESCRIPTION	DATE

3191 - DAVIDSON - LH

SIGNATURE COLLECTION

Second Floor Plan 'A'

DRAWN BY: South Designs

ISSUE DATE: 10/07/2020

CURRENT REVISION DATE: —

SCALE: 1/8" = 1'-0"

SHEET: 2.2a

DAS DON ALLEN & ASSOCIATES, P.A.
"Since 1971"
Commercial * Residential * Mortgage Surveys * Multi-Family
Construction Staking * Subdivision Design * Topographical
127 Promenade Drive – Suite E * Mooresville * NC * 28117
(704) 664-7029 (704) 664-8041 Fax


I, certify that this map was drawn under my supervision from an actual survey made under my supervision recorded in deed book 2391, page 745, and/or plat book 30, page 55, that the ratio of precision is 1':10,000, that this map was prepared in accordance with the General Statutes of North Carolina Chapter 89C.

my hand and seal on the 2, day of AUGUST, A.D. 20 23.

REVISED 8/3/23
UPDATED DRIVE & WALK

WILLIAM M. ALLEN

NORTH CAROLINA PROFESSIONAL SEAL L-3499 LAND SURVEYOR WILLIAM M. ALLEN



LOT 162
TSEGA & RUSSOM OGBAI
1211/707

CURVE TABLE				
CURVE	RADIUS	LENGTH	BEARING	CHORD
C1	275.00'	5.59'	N 64°55'01" E	5.59'
C2	20.00'	31.72'	S 69°03'56" E	28.50'
C3	539.74'	234.59'	N 36°04'55" W	232.75'

LOT 166
DIANE L & TERRANCE CLARKE
1442/1239

N66°23'44"E
221.65'

15' SIDE

59.6'

35' FRONT

PROPOSED HOUSE

88.4'

GULLY

35' REAR

LOT 164
JOSEPH F ZEMAN
1157/924

S30°14'40"E
246.03'

WINDBLUFF CT
(50' R/W)

C3

39.4'

SEPTIC

SEPTIC

SEPTIC

25' CORNER

10' DRAINAGE & UTILITY ESMT.

C2

S65°29'58"W
173.93'

C1

CONC. CALC
DRIVE = 2,014 SF.
WALK = 235 SF.

HARBOR RIDGE DRIVE
(50' R/W)

FIELD PICKS

LEGEND
P.P. = POWER POLE
E.I.P. = EXISTING IRON FOUND
I.P.S. = #4 REBAR SET
R/W = RIGHT-OF-WAY
W = WELL
CP = COMPUTED POINT

0' 20' 40' 100'
SCALE IN FEET

PLOT PLAN SURVEY

OF
106 WINDBLUFF CT
LOT 163 HARBOR WATCH SECTION IV
FALLSTOWN TWSP., IREDELL CO. N.C.

SCALE 1" = 40'
ACQUIRED BY: KLH ACQUISITIONS LLC

NOTES
1) THIS PROPERTY MAY BE SUBJECT TO ANY EASEMENTS AND/OR RIGHTS OF WAY OF RECORD.
2) ACREAGE COMPUTED BY THE COORDINATE METHOD.
3) UNDERGROUND POWER
4) NO GRID MONUMENT FOUND WITHIN 2000 FEET.

FIELD BOOK:
FILE: HARBOR WATCH 163 S4
DC FILE:
TAX MAP NO: 4711239421

PROPERTY ID #: 4711239421__
COUNTY: _Iredell_____

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

OWNER: KLH Acquisitions LLC_____ APPLICATION DATE_____
ADDRESS: 11220 Elm Ln, STE 107, Charlotte, NC 28277_____ DATE EVALUATED: _____
PROPOSED FACILITY: __5 BDRM_____PROPOSED DESIGN FLOW (.1949): _600 GPD_____ PROPERTY SIZE: _1.93 AC_____
LOCATION OF SITE:106 Windbluff Ct, Harbor Watch 163_____ PROPERTY RECORDED: _____
WATER SUPPLY: X Private Public X Well Spring Other _____
EVALUATION METHOD: X Auger Boring X Pit Cut TYPE OF WASTEWATER: X Sewage Industrial Process Mixed

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
PIT 1	LS 8%	0-5	Br CL WSBK	FR SS SP SXP	N/A	60"	N/A	N/A	PS 0.3
		5-32	R C SBK	FR SS SP SXP					
		32-60	R CL WSBK	FR SS SP SXP					
PIT 2	LS 8%	0-3	Br CL WSBK	FR SS SP SXP	N/A	54"		N/A	PS 0.3
		3-24	R C SBK	FR SS SP SXP					
		24-54	R CL WSBK	FR SS SP SXP			Few SAP Few Rock		
PIT 3	LS 10%	0-5	Br CL WSBK	FR SS SP SXP	N/A	64"	N/A	N/A	PS 0.3
		5-34	R C SBK	FR SS SP SXP					
		34-64	R CL WSBK	FR SS SP SXP					
PIT 4	LS 10%	0-5	Br CL WSBK	FR SS SP SXP	N/A	57"		N/A	PS 0.3
		5-34	R C SBK	FR SS SP SXP			Few SAP/WR		
		34-57	R CL WSBK	FR SS SP SXP					

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM
Available Space (.1945)	1500 FT^2	700 FT^2
System Type(s)	25% Reduction	PPBPS
Site LTAR	0.3	0.3

OTHER FACTORS (.1946): _____
SITE CLASSIFICATION (.1948): _____PS_____
EVALUATED BY: _____MA&A_____
OTHER(S) PRESENT: _____

COMMENTS:_____
_____

SOIL/SITE EVALUATION

(Continuation Sheet)

PROPERTY ID #: 4711239421____
DATE OF EVALUATION: _____
COUNTY: __IREDELL____

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941)		OTHER PROFILE FACTORS				PROFILE CLASS & LTAR
			.1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	.1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	
AB 1	LS 10%	0-28	R C SBK	FR SS SP SXP	N/A	48"	N/A	N/A	PS 0.3
		28-48	R CL WSBK	FR SS SP SXP					

PERMIT SNAPSHOT REPORT OSWP-2023-18657 FOR IREDELL COUNTY

Permit Type: Environmental Health OSWP
Work Class: EH Septic Improvement Permit
Status: PRIORITY PERMIT
Valuation: $0.00
Description: PRIORITY PERMIT EXPEDITED REVIEW

Project:
District: Iredell County
Square Feet: 0.00
Assigned To: Botkins, Ben

App Date: 03/10/2023
Exp Date: NOT AVAILABLE
Completed: NOT COMPLETED
Approval Expire Date:

Parcel: 4711239421.000 Main
Address: 106 Windbluff Ct Main
Statesville, NC 28677
Zone: RA(Residential Agricultural District)

Property Owner
KLH ACQUISITIONS LLC

Applicant/Authorized Agent
Michael Athanas & Associates
Gary McNeely
2630 Statesville Blvd
Salisbury, NC 28147
Mobile: (704) 310-1832

Permit Custom Fields

How is your site plan being submitted	Custom Site Plan	Does the site contain any jurisdictional wetlands	No	Non-domestic Sewage Generated	No
Other Public Agency	No	All proposed structure dimensions	See plan	If other Addition/Structure, please explain	
Maximum Number of Bedrooms	5	Number of Occupants	10	Foundation Type	Basement with Plumbing
Desired Septic System Type	Innovative	If other septic system type, please explain		Has this project been approved by TRC	No
Lot Acreage	1.13	Front Setback	35	Back Setback	35
Left Setback	25	Right Setback	15	Is the structure or development in the floodplain	No
Is the property in a local historic district?	No	Is the property located downtown?	No	Additional Unique Setbacks Apply	No

Attachment File Name	Added On	Added By	Attachment Group	Notes
Signature_Gary_McNeely_3/10/2023.jpg	03/10/2023 9:09	McNeely, Gary		Uploaded via CSS
FT Check List_v1.pdf	03/10/2023 9:26	COMEAUX, DEBRA	Available Online	Additional Supporting Information
Harbor Watch 163 AF_v1.pdf	03/10/2023 9:26	COMEAUX, DEBRA	Available Online	Authorize to Act as Agent
HARBOR WATCH 163 SOIL_v1.doc	03/10/2023 9:26	COMEAUX, DEBRA	Available Online	Additional Supporting Information
Harbor Watch 163_v1.docx	03/10/2023 9:26	COMEAUX, DEBRA	Available Online	Additional Supporting Information
Harbor Watch 163_v1.pdf	03/10/2023 9:26	COMEAUX, DEBRA	Available Online	Site Plan

Invoice No.	Fee	Fee Amount	Amount Paid
INV-00010426	New Gravity System	$850.00	$850.00
	Iredell Zoning Tech Fee	$2.25	$2.25
	Iredell Zoning Permit Fee	$75.00	$75.00
	Total for Invoice INV-00010426	$927.25	$927.25
	Grand Total for Permit	**$927.25**	**$927.25**

Workflow Step / Action Name	Action Type	Start Date	End Date
Application Completeness Check v.1		03/10/2023 9:45	03/10/2023 9:45
Confirm application complete v.1	Generic Action		03/10/2023 9:45
Zoning Review v.1		03/17/2023 14:23	03/17/2023 14:24
Iredell County Zoning Approval v.1	Task	03/17/2023 14:23	03/17/2023 14:24
Issue Invoice v.1	Generic Action		03/17/2023 14:24

PERMIT SNAPSHOT REPORT (OSWP-2023-18657)

Fees Paid v.1	Generic Action		03/17/2023 14:24
Fees v.1		03/17/2023 14:24	03/17/2023 14:24
Issue Invoice v.1	Generic Action		03/17/2023 14:24
Fees Paid v.1	Generic Action		03/17/2023 14:24
Lot Readiness Verification v.1			
OSWP Septic Preliminary Site Visit v.1	Inspection		
OSWP Site Examination v.1	Inspection		
Issue Improvement Permit v.1			
Issue Invoice v.1	Generic Action		
Fees Paid v.1	Generic Action		
Issue Permit v.1	Generic Action		
Permit Completion Process v.1			
Authorization to Construct Permit v.1	Create Sub Permit		
Issue Authorization to Construct v.1	Generic Action		

PERMIT SNAPSHOT REPORT OSWP-2023-33193 FOR IREDELL COUNTY

Permit Type: Environmental Health OSWP
Work Class: EH Septic Permit
Status: In Progress
Valuation: $0.00
Project:
District: Iredell County
Square Feet: 0.00
Assigned To: White, Bryant
App Date: 08/08/2023
Exp Date: NOT AVAILABLE
Completed: NOT COMPLETED
Approval Expire Date:

Description: LINKED TO OSWP-2023-18657 BEN ISSUED IP Authorization to Construct for a SFD

Parcel: 4711239421.000 Main
Address: 106 Windbluff Ct Statesville, NC 28677 Main
Zone: RA(Residential Agricultural District)

Property Owner
Joe Dority
Home: (803) 804-6956

Applicant/Authorized Agent
Leigh Homes
11220 Elm Lane Suite 109
Charlotte, NC 28277

Permit Custom Fields

How is your site plan being submitted	Custom Site Plan	Septic Application/Permit Type	Authorization to Construct	Does the site contain any jurisdictional wetlands	No
Non-domestic Sewage Generated	No	Other Public Agency	No	All proposed structure dimensions	65' x 71'
What are the proposed structures	New Single Family Residence	Type of New Single-Family Residence	Stick Built	Maximum Number of Bedrooms	5
If other Addition/Structure, please explain		Number of Occupants	10	Foundation Type	Basement with Plumbing
Water Supply	New Well	Desired Septic System Type	Conventional (most common)	Has this project been approved by TRC	No
Lot Acreage	1.13	Front Setback	35	Back Setback	35
Left Setback	25	Right Setback	15	Is the structure or development in the floodplain	No
Is the property in a local historic district?	No	Is the property located downtown?	No	Additional Unique Setbacks Apply	No

Attachment File Name	Added On	Added By	Attachment Group	Notes
Signature_Leigh_Homes_8/8/2023.jpg	08/08/2023 12:16	Homes, Leigh		Uploaded via CSS
AA form_v2.pdf	08/09/2023 15:56	Nebel, Barbara	Available Online	Authorize to Act as Agent

Linked Record Relationship	Module	Record Number	Linked Record Type	Linked Record Work Class
Child	Permit	OSWP-2023-18657	Environmental Health OSWP	EH Septic Permit

Workflow Step / Action Name	Action Type	Start Date	End Date
Application Completeness Check v.1		08/09/2023 15:56	08/09/2023 15:59
Confirm application complete v.1	Generic Action		08/09/2023 15:59
~~Fees v.1~~			08/09/2023 15:57
~~Issue Invoice v.1~~	Generic Action		08/09/2023 15:57
~~Fees Paid v.1~~	Generic Action		08/09/2023 15:57
Permit Completion Process v.1		08/09/2023 15:58	
Authorization to Construct Permit v.1	Create Sub Permit	08/09/2023 15:58	
Issue Authorization to Construct v.1	Generic Action		
~~Zoning Review v.1~~			08/09/2023 15:57
~~Floodplain Admin Overview v.1~~	Task		08/09/2023 15:57
~~Issue Invoice v.1~~	Generic Action		08/09/2023 15:57
~~Fees Paid v.1~~	Generic Action		08/09/2023 15:57

PERMIT SNAPSHOT REPORT (OSWP-2023-33193)

Lot Readiness Verification v.1	
OSWP Septic Preliminary Site Visit v.1	Inspection
OSWP Site Evaluation v.1	Inspection
Issue Improvement Permit v.1	
Issue Invoice v.1	Generic Action
Fees Paid v.1	Generic Action
Issue Permit v.1	Generic Action