DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

PROPERTY RECORDED: _____
COUNTY: Iredell

SOIL/SITE EVALUATION
FOR
ON-SITE WASTEWATER SYSTEM

APPLICANT: Angela Wekalsch OWNER __ AGENT __ PHONE: _____
ADDRESS: _____ APPLICATION DATE: _____ DATE EVALUATED: 7-5-94
PROPOSED FACILITY: 3 Bedroom House
PROPERTY SIZE: _____
LOCATION OF SITE: Glen Ridge S/D Lot # 40
WATER SUPPLY: On-Site Well ✓ Comm. Well ___ Public ___ Other _____ EVAL. METHOD: Auger Boring ✓ Pit ___ Cut ___

PROFILE #	1940 LANDSCP POS./ SLOPE %	HORIZON DEPTH (IN.)	1941 (a)(1) TEXTURE	(a)(2) STRUCTURE	(a)(3) CONSISTENCY	
1	3-5% L	0-3"	l	gr	vfr	1942 WETNESS CONDITION - S
		3"-36"	c	Abk	fi	1943-1956 SAPROLITE - 36" P.S.
		36"-40"	C/sap mix	Abk/m	fr	1944 RESTRICTIVE HORIZON - NA
		40"-48"	Saprolite	m	fr	1945 PROFILE CLASSIFICATION - P.S
						PROFILE LTAR - .3
2	3-5% L	0-4"	l	gr	vfr	1942 WETNESS CONDITION - S
		4"-40"	c	Abk	fi	1943-1956 SAPROLITE - 40" P.S.
		40"-43"	C/sap mix	Abk/m	fr	1944 RESTRICTIVE HORIZON - NA
		43"-48"	Saprolite	m	fr	1945 PROFILE CLASSIFICATION - P.S
						PROFILE LTAR - .3
3	2-3% L	0-3"	l	gr	vfr	1942 WETNESS CONDITION - S
		3"-42"	c	Sbk	fr	1943-1956 SAPROLITE - 42" P.S.
		42"-49"	C/sap mix	Sbk/m	fi	1944 RESTRICTIVE HORIZON - NA
		49"-48"	saprolite	m	fr	1945 PROFILE CLASSIFICATION - P.S
						PROFILE LTAR - .35
4	3-5% L	0-5"	l	gr	vfr	1942 WETNESS CONDITION - S
		5"-36"	c	Abk	fi	1943-1956 SAPROLITE - 36" P.S
		36"-38"	C/sap mix	Abk/m	fr	1944 RESTRICTIVE HORIZON - NA
		38"-48"	Saprolite	m	vfr	1945 PROFILE CLASSIFICATION - P.S
						PROFILE LTAR - .3
5	3-5% L	0-4"	l	gr	vfr	1942 WETNESS CONDITION - S
		4"-40"	c	Abk	fi	1943-1956 SAPROLITE - 40" P.S.
		40"-43"	C/sap mix	Abk/m	fi	1944 RESTRICTIVE HORIZON - NA
		43"-48"	Saprolite	m	fr	1945 PROFILE CLASSIFICATION - P.S
BACK ←						PROFILE LTAR - .3

AVAILABLE SPACE (.1945): S SITE CLASSIFICATION (.1943): P.S. SITE LONG-TERM ACCEPTANCE RATE: .3 gpd/ft²
OTHER FACTORS(.1946): _____ SYSTEM TYPE: Conventional, gravity fed
EVALUATED BY: Michael Dawson OTHER(S) PRESENT: _____
COMMENTS: Install system shallow

DRAFT