General Framing Notes

The following notes are suggested minimum requirements only. Due to a variance of codes per region, please refer and comply with all your local codes. Consult with local engineers for all structural requirements.

1. Provide purlins at mid height of all walls.
2. All joists and rafters shall be aligned over studs below.
3. All headers shall be 2-2x10's with 1/2" plywood filtch plate, unless otherwise noted.
4. Framer to install double floor joists under partition wall parallel to joist direction.
5. Provide 1x4 cross bridging at mid point of span or 8'-0" o.c. maximum in all floors.
6. All exterior corners (inside and outside corners) shall be braced with 1/2" CDX plywood. Nailing schedule shall be 8d commons at 6" o.c. at all edges and 8d commons at 12"o.c. at all intermediate studs. (Option - approved diagonal corner braces both directions at all corners.)
7. All columns or solid framing shall extend down thru all levels and terminate at the basement floor and be supported by a thickened slab, grade beam, or footing designed to carry load.
8. Provide double 2x8 stongback at mid span for ceiling joises with spans greater than 10'-0".
9. Provide collar ties at upper 1/3 of vertical distance between ridge board and ceiling joises at 4'-0" o.c. max.
10. Hip, valley rafters, and ridge boards shall be one "2x" size larger than rafters.
11. Roof decking shall be 1/2" CDX plywood minimum.
12. Where pre-engineered floor and roof trusses are used, truss manufacturer must provide shop drawings which bear seal of registered engineer in state in which work is to be performed.
13. All ceiling joists and rafter bracing to bear on load bearing walls designed to carry load thru all levels and terminate at basement floor and be supported by thickened slab grade beam or footing designed to carry load.
14. All basement walls, beams, and columns to be designed by local structural engineer and meet all local codes.
15. All solid framing, columns, beams, etc., to be designed by local structural engineer and meet all local codes.

GENERAL NOTES

1. All work shall be performed in accordance with all applicable local, state, and local codes, regulations, and FHA/VA MPS.
2. Contractor shall verify all conditions and dimensions at site before beginning construction. Any discrepancies shall be reported to Frank Betz Associates, Inc. for justification and/or correction before proceeding with work. Contractors shall assume responsibility for errors that are not reported.
3. All dimensions should be read or calculated and never scaled.
4. All footings to be below frost line (see local code) and must rest on undisturbed soil, capable of holding the building. Consult local engineer for proper footing and reinforcing sizes.
5. Contractor shall insure compatability of the building with all site requirements.
6. Where fill exceeds 4' or as last any foundation wall reinforce as per code.
7. All foundation and structural members should be verified and stamped by an engineer in the state where construction is occuring due to a wide variance in local codes, soil bearing conditions, frost line depth, geological and weather conditions, etc. The contractor is responsible for adjusting and revising all structural details and conditions to meet all local codes and to insure a quality and safe structure.
8. All steel, concrete and steel structural members shall be of a good grade and quality and meet all national, state and local building codes where applicable.
9. All columns or solid framing should be designed to carry loads and should extend down thru the levels below and terminate at the basement floor or at other bearing points designed to carry the load.


Acknowledgement Of Plans Submittal ONLY!
Date 3-3-06
Mark B. Loy Date 3-3-06


Assumed 4 BEDROOM PLAN
FLIP PLAN
STOOBOOT THRD
GARAGE

COPYRIGHT © 1990 BY FRANK BETZ ASSOCIATES, INC., NOT TO BE REPRODUCED

SQUARE FOOTAGE :	
FIRST FLOOR	1089 S.F.
SECOND FLOOR	1190 S.F.
TOTAL	2279 S.F.

FIRST FLOOR PLAN
1/4" = 1'-0"





DATE	REV	DATE	REV
12-5-05			
6-26-92	1 STAIRS		
8-6-90	MSTR SUITE		

Designs and ideas protected by copyright laws. Reproducing without the written permission of Frank Betz Assoc. Inc. is prohibited.

HOMEPLANS — DESIGNED FOR TODAY'S MARKET

FIRST FLOOR PLAN
THE TALISMAN

FBA
FRANK BETZ ASSOCIATES, INC.
1800 LAKE PARK DRIVE/SUITE 101
SMYRNA, GEORGIA 30080
404/431-0888

BY eht CK fll
DATE 3/4/20
SHEET 3 OF 5

General Framing Notes

The following notes are suggested minimum requirements only. Due to a variance of codes per region, please refer and comply with all your local codes. Consult with local engineers for all structural requirements.

1. Provide purlins at mid height of all walls.
2. All joists and rafters shall be aligned over studs below.
3. All headers shall be 2-2x10's with 1/2" plywood flitch plate, unless otherwise noted.
4. Framer to install double floor joists under partition wall parallel to joist direction.
5. Provide 1x4 cross bridging at mid point of span or 8'-0" o.c. maximum in all floors.
6. All exterior corners (inside and outside corners) shall be braced with 1/2" CDX plywood. Nailing schedule shall be 6d commons at 6" o.c. at all edges and 8d commons at 12"o.c. at all intermediate studs. (Option - approved diagonal corner braces both directions at all corners.)
7. All columns or solid framing shall extend down thru all levels and terminate at the basement floor and be supported by a thickened slab, grade beam, or footing designed to carry load.
8. Provide double 2x8 stongback at mid span for ceiling joists with spans greater than 10'-0".
9. Provide collar ties at upper 1/3 of vertical distance between ridge board and ceiling joists at 4'-0" o.c. max.
10. Hip, valley rafters, and ridge boards shall be one "2x" size larger than rafters.
11. Roof decking shall be 1/2" CDX plywood minimum.
12. Where pre-engineered floor and roof trusses are used, truss manufacturer must provide shop drawings which bear seal of registered engineer in state in which work is to be performed.
13. All ceiling joists and rafter bracing to bear on load bearing walls designed to carry load thru all levels and terminate at basement floor and be supported by thickened slab grade beam-and footing designed to carry load.
14. All basement walls, beams, and columns to be designed by local structural engineer and meet all local codes.
15. All solid framing, columns, beams, etc., to be designed by local structural engineer and meet all local codes.


GENERAL NOTES

1. All work shall be performed in accordance with all applicable national, state, and local codes, regulations, and FHA/VA MPS.
2. Contractor shall verify all conditions and dimensions at site before beginning construction. Any discrepancies shall be reported to Frank Betz Associates, Inc. for justification and/or correction before proceeding with work. Contractors shall assume responsibility for errors that are not reported.
3. All dimensions should be read or calculated and never scaled.
4. All footings to be below frost line (see local code) and must rest on undisturbed soil, capable of handling the building. Consult local engineer for proper footing and reinforcing sizes.
5. Contractor shall insure compatability of the building with all site requirements.
6. If backfill exceeds 4' against any foundation wall reinforce as per code.
7. All foundation and structural members should be verified and stamped by an engineer in the state where construction is occurring due to a wide variance in local codes, soil bearing conditions, frost line depth, geological and weather conditions, etc. The contractor is responsible for adjusting and verifying all structural details and conditions to meet all local codes and to insure a quality and safe structure.
8. All wood, concrete and steel structural members shall be of a good grade and quality and meet all national, state and local building codes where applicable.
9. All columns or solid framing should be designed to carry loads and should extend down thru the levels below and terminate at the basement floor or at other bearing points designed to carry the load.


COPYRIGHT © 1990 BY FRANK BETZ ASSOCIATES, INC., NOT TO BE REPRODUCED

SECOND FLOOR PLAN

1/4" = 1'-0"



Frank Betz Associates, Inc. assumes no liability for any changes or modifications made to these plans by others.



BAY DETAIL

1/2" = 1'-0"

DATE	REV	DATE	REV
6-26-90	STAINS		
8-6-90	GARAGE STAIRS		

The drawings and the reproductions thereof are copyrighted and property of Frank Betz Associates, Inc. Any reproduction without the written authorization of Frank Betz Associates, Inc. is prohibited.

HOMEPLANS — DESIGNED FOR TODAY'S MARKET

SECOND FLOOR PLAN
THE TALISMAN

FBA
FRANK BETZ ASSOCIATES, INC.
1800 LAKE PARK DRIVE/SUITE 101
SMYRNA, GEORGIA 30080
404/431-0888

BY eht CK jbc

DATE 7/4/90

SHEET 4 OF 5