W/ FINISH HED ATTIC ACCESS

NO LENGTH EXTENSIONS PERMITTED TO THESE MODULES

58'-0"

13'-6 1/2" | 3'-5" | 13'-10 1/2" | 15'-6" | 9'-6 1/2"

3/0x5/2 (3) 2X6'S SPF No.2

6/0 SLIDER (3) 2X8'S SPF No.2

(3) 2X6'S SPF No.2 2/4x3/0

W15 30L B 27 | W12 30L | SB36 | W18 30R D/W H/U | W18 30L B 12 | W3014 OMIT & PREP FOR ON SITE MICROWAVE | W18 30R B 18 | W3612 F342(3")

(4) SHELVES (4) SHELVES

BEDROOM 3

DINING ROOM

KITCHEN VINYL

F331(3") C V

B 9 | SCB 36/39 | FLUOR. LIGHT | B 36 | DB 184 | FLUOR. LIGHT

PANTRY VINYL

(4) SHELVES (4) LINEN SHELVES

#6

2/4X3/0

SLOPED WALLS 37" ABOVE TREAD w/CAP BOARD

W/H

9'-9 1/2"

4/0 | 2/8 | (1) SHELF @ 66" | (2)SHELVES LINEN | 1/6 | 2'-8 1/2" | 4'-4" FLAT CEILING | (1) SHELF @ 66" COAT | 2/6 | 4'-4 3/4" | 2x8 PLUMB WALL

38'-6"

(4) 1-1/2x9-1/4" LVL (2) EACH SIDE 17'-2 3/4" FLAT CEILING

C V | 3'-9 1/2" DRYWALL FINISH 6" HEADER

2'-0" | 26'-0" | 34'-2"

3/0X5/2 UPPER GABLE

PANEL BOX

LAUNDRY VINYL

2/8 9-LITE | 2/8 | 2/8 | 2/4

DRYWALL FINISH 6" HEADER

LIVING ROOM

JB

(1) SHELF @ 66"

8'-1 1/2"

15'-8 1/2"

BATH 1 VINYL

#3

VSB30 VSB30

2/4

6'-11"

D W (1) SHELF @ 66"

BATH 2 VINYL

VSB30 #1

2/8

2/4

2/8

BEDROOM 1

JB

17'-4 3/4"

2x6 PLUMB WALL

4'-6 1/2" (1) SHELF @ 66"

2/4

FIR-OUT TO FLUSH AFTER MODULES ARE SET

12'-0" (1) 1-1/2"x16" LVL RBS SIDE

FLAT CEILING

(3) 2X6'S SPF No.2 3/0x5/2 SHUTTERS "WSD" DORMER

(3) 2X6'S SPF No.2 3/0x5/2 SHUTTERS

(3) 2X6'S SPF No.2 3/0 SUNBURST "WSD" DORMER

VINYL

2/4

(1) 1-1/2"x16" LVL RBS SIDE 12'-0"

FLAT CEILING

20'-4"

12'-2"

3'-4"

SITTING AREA

11'-11"

8'-2"

BEDROOM 2

11'-11"

6/0x5/2 SHUTTERS

6/0x5/2 SHUTTERS

12'-11" | 25'-6" | 12'-11"

3/0X5/2 UPPER GABLE

APPROVED BY NTA INC. 07/21/06

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Kristen Cumberland

Acknowledgement Of Plans Submittal ONLY!

Date 7.28.06

Date 7.21.06

LIGHT & VENT CHART

	AREA OF ROOM(SQ FT.)	LIGHT REQUIRED	LIGHT SUPPLIED	VENT REQUIRED	VENT SUPPLIED
LIVING ROOM	213	17.04	22.36	8.52	11.8
DINING ROOM	163	13.04	28.07	6.52	15.6
BEDROOM 1	271	21.68	22.36	10.84	11.8
BEDROOM 2	143	11.44	22.36	5.72	11.8
BEDROOM 3	131	10.48	11.18	5.24	5.9

carolina building solutions

INNOVATIVE HOME-BUILDING SYSTEMS

www.cbsmods.com

MARRIAGE & SIDEWALLS	SERIAL NO. 3031	PLAN SPECS:	
VEGC-1718-B	PROP NO. 4652	ROOF PITCH	10/12
BUILDER: CROSSLAND HOMES(MAIDEN)	WIND ZONE 100 (MPH)	ROOF CENTERS	24 o.c.
RETAIL: COWAN	DEL.ST. NC / CODE: IRC	SIDE WALL HEIGHT	96
33'-10"x58'-0"		EXTERIOR WALLS	24 o.c.
SCALE: 3/16"=1'-0" / CAPE	DR.BY: / DATE:07.11.06	INTERIOR WALLS	24 o.c.

PLAN NOTES:

1.) SEE JOB ORDER FOR ALL SPECIFICATIONS

2.) SEE PAGE QC5D-5 OF QA MANUAL FOR MARRIAGE WALL HEADER CHART

2.) SEE PAGE QC5D-6 OF QA MANUAL FOR EXTERIOR WALL HEADER CHART

*** DO NOT BUILD FOUNDATION BY HOUSE DIMENSIONS ***
*** REFER TO FOUNDATION PLAN FOR DIMENSIONS ***

PAGE NO. 6