IREDELL COUNTY HEALTH DEPARTMENT

STATESVILLE 704-878-5305 MOORESVILLE 704-664-5281

* THIS PERMIT REPLACES REVOKED PERMIT ISSUED 6-14-04

IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM INSPECTION

PERMIT# 127538 PIN# 4730-58-5303

OWNER OR CONTRACTOR CECIL STAMEY LLC DATE 4-26-06

ADDRESS 108 WESTFIELD CT MOORESVILLE, NC 28115 PHONE: Business 704-400-9643 Home 704-528-1969

LOCATION STATE PARK ROAD TO MEADOW GLEN TR 1ST STREET, TR SCOTCH IRISH LANE LOT ON RIGHT NEAR END

SUBDIVISION MEADOW GLEN BLOCK / SECTION 4 LOT 133 LOT AREA 0.359 ACRE SITE CLASS. PS DESIGN FLOW 360 L.T.A.R. 0.30 GPD/FT²

Septic Tank: 1000 Gallons: STB 1012 Date 10-1-05

Pump Tank: 1000 Gallons: PT 17 Date 2-13-06

Pump Make: GOULDS Model WERSITH Serial No. 565400610

Nitrification Field: No Fields 1 Square Feet 1200 Linear Feet 200

No Lines THREE Trench Width 24" Max Trench Bottom Depth 36" Gravel Depth SAND 24"

☑ New System ☐ Repair System Type: I, II, III, IV, V, VI

System Description: 50% REDUCTION, LOW-PRES

Repair System Description: 50% REDUCTION, LOW-PRES

Maintenance Agreement Required: ☑ Yes ☐ No

☑ House/Mod. Home No. Bedrooms 3

☐ Mobile Home No. Bathrooms ___

☐ Business No. Employees ___

☐ Other ___


☐ Slab ☐ Crawl Space ☑ Basement w/plumbing ☐ Basement wo/plumbing

Water Supply: ☐ Individual ☑ Public ☐ Community


Comments/Conditions: ① SEE ATTACHED EASEMENT FOR SEPTIC TANK & DRAINFIELD HORIZONTAL SETBACK EXCEPTIONS ② RELOCATE WATER LINE TO RIGHT SIDE OF DRIVEWAY ③ INSTALL 50% REDUCTION SYSTEM USING 46 PPBPS PANELS (SEE ATTACHED SHEETS)

Comments/Conditions: A CONTRACT SHALL BE EXECUTED BETWEEN THE SYSTEM OWNER & A MANAGEMENT ENTITY PRIOR TO ISSUANCE of OPERATION PERMIT

INITIAL SITE SKETCH



AS BUILT SKETCH



Permit can be suspended or revoked if any false information is supplied toward securing the permit/any unauthorized changes are made to the site/any unauthorized changes are made in the installation of the system. Improvement Permit with plat valid without expiration. Improvement Permit with site plan valid for sixty months. Authorization to Construct is valid for a period equal to that of Improvement Permit – not to exceed sixty months.

Signed: Jessi D'Hillin, Agent date 5-11-06 Installed by: Robbie Brown

Improvement Permit by: STEVE HEDRICK date 4-26-06 Operation Permit by: [signature] date 7-27-06

Authorization to Construct by: STEVE HEDRICK date 4-26-06 Existing System Inspection by: ___ date ___


HEALTH DEPT. COPY: WHITE OWNER COPY (FINAL): YELLOW OWNER COPY (INITIAL): PINK

PUMP TANK DESIGN

MEADOW GLEN LOT #133

ATTACHMENT TO PROPERTY DESCRIPTION # 127538

TAX MAP # A730-58-5303



1) APPROXIMATE PUMP CYCLE
   TIE DOWN "A" - 4½" 6" 8" 10" 12" 14" 16"
   DIFFERENTIAL "B" - 8½" 12" 14" 17" 20" 24" 28"


2) SIZE WIRE TO PUMP FOR TOTAL RUN FROM HOUSE PANEL TO PUMP

3) PROVIDE SEPARATE CIRCUIT BREAKERS FOR PUMP POWER & IN-HOUSE PANEL

4) SEALED MERCURY CONTROL FLOATS ATTACHED TO 2½" SCHEDULE 40 PVC PIPE SLIPPED OVER 2" SCHEDULE 40 PVC PIPE ANCHORED IN CONCRETE

5) USE PUMP SIZED TO DELIVER 19 GPM AT 33 TDH

DOSE = 165 GALLONS



MEADOW GLEN LOT #133

Pressure Dosed PPBPS

# of panels 46.
Size holes 5/32". 1 hole per panel.
Approximate amount of sand needed ~36 TONS
100lbs. of partical sand per 8 panels.
Sidewalls raked and limed.
GPM 19.
TDH 33.

Comments

SCOUR TRENCH SIDEWALLS & APPLY A LIGHT DUSTING of LIME PRIOR TO INSTALLING SAND

DEPARTMENT OF ENVIRONMENT, HEALTH, AND NATURAL RESOURCES
DIVISION OF ENVIRONMENTAL HEALTH
ON-SITE WASTEWATER SECTION

Sheet ___ of ___
PROPERTY ID #: _____
COUNTY: _____

SOIL/SITE EVALUATION
for ON-SITE WASTEWATER SYSTEM

OWNER: _____ APPLICANT: _____
ADDRESS: _____ APPLICATION DATE: _____ DATE EVALUATED: 5-18-04
PROPOSED FACILITY: _____ PROPOSED DESIGN FLOW (.1949): _____ PROPERTY SIZE: _____
LOCATION OF SITE: lot 133 Meadows 6/a PROPERTY RECORDED: _____
WATER SUPPLY: ☐ Private ☐ Public ☐ Well ☐ Spring ☐ Other _____
EVALUATION METHOD: ☐ Auger Boring ☐ Pit ☐ Cut
TYPE OF WASTEWATER: ☐ Sewage ☐ Industrial Process ☐ Mixed

#5 0-5 fill
5-25 wk-mtsbk/cr/fr/sp/exp
25-55+ massive yr/l/sp/fr/sss/p
few mil clay East sidewall .37 5"

PROFILE #	.1940 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY (.1941) .1941 STRUCTURE/ TEXTURE	.1941 CONSISTENCE/ MINERALOGY	OTHER PROFILE FACTORS .1942 SOIL WETNESS/ COLOR	.1943 SOIL DEPTH	.1956 SAPRO CLASS	.1944 RESTR HORIZ	PROFILE CLASS & LTAR
1		0-4	gr brn SL	fr sss p					.25
		4-27	wk-mtsbk/cr/fr/sp/exp	fr sp sexp					
		27-60	(B-C) wk fsbk yr SL	fr sss p common mil sap					
2		0-4	gr brn SL	fr sss p	21"+				(II)
		4-21	wk fsbk yr scl/cr	fr sss p					
		21-56	glayed brn sc	fr sp					
3		0-3	gr brn SL	fr sss p	24"+				(I)
		3-8	wk fsbk brn scl	fr ss p					
		8-28	mtsbk yr/c	fr sp sexp					
		28-57	wk fsbk-massive gray brn sic	fr sp mixed					
4	13% V	0-3	gr brn SL	fr sss p					.3
		3-20	mtsbk rc	fr sp sexp					
		20-30	(B-C) wk fsbk yr/cl	fr sss p common mil sap					
		30-68	massive yr/l sap	fr sss p					

DESCRIPTION	Initial	Repair
Available Space (.1945)	PS	PS
System Type(s)	LPPBPS	LPPBPS
Site LTAR	.3	.25-.3

OTHER(S) EVALUATED: _____
SITE CLASSIFICATION (.1948): PS
EVALUATED BY: _____
OTHER(S) PRESENT: _____

IREDELL COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
Application For Improvement Permit

ALL items on this application form must be completed before Health Department can begin work. One application must be completed by the property owner or agent for each (proposed) site.

PERSONAL INFORMATION:

CECIL STAMEY | 704 400 9643 | 108 WESTFIELD PLAZA | MOOR | NC | 28115
Applicant | Phone # | Mailing Address | City | State | Zip Code

CECIL STAMEY LLC | 108 WESTFIELD PLAZA | MOORESVILLE | NC | 28115
Current Property Owner | Mailing Address | City | State | Zip Code

PROPERTY INFORMATION:

MEDOW GLENN SUBDIV | #133 | SCOTCH IRISH LANE | 03
(Proposed) Subdivision Name | (Proposed) Lot # | (Proposed) Block/Section # | State Road #

Public TROUTMAN 2000 | | 4730488453
(Proposed) Water Supply: Public, Private Well | **Preliminary Plat Approval Date** (DEVELOPERS ONLY) | Tax Map #

Specific Directions to Property STATE PARK Rd - 1st Right
MEDOW GLENN SUBDIV 1 Right +
SCOTCH IRIS LANE

TYPE OF FACILITY: (use check (X) or number as appropriate)

House ✓ Mobile Home _____ Commercial _____ No. Bedrooms 3 No. Baths 2

No. Persons or Employees (commercial only) _____ Basement ✓ Basement with Plumbing _____

Crawl Space _____ Concrete Slab _____ Garbage Disposal _____ Jaccuzi or spa _____

COVENANT AND SIGNATURE:

I hereby make application to the Iredell County Health Department for a soils/site evaluation of the property described above. This evaluation is to be conducted for the sole purpose of obtaining a septic system Improvement Permit. I hereby authorize Iredell County Health Department representatives to go onto the above property for purposes of conducting this evaluation. I understand that, by state law, any Improvement Permit issued on the above property may be voided if substantial changes are made to the designated sewage system site. The issuance of an Improvement Permit by the Iredell County Health Department does not relieve me from compliance with all other relevant state/local laws or regulations. As owner or authorized agent, I covenant that the contents of this application are true and represent the maximum facilities intended to be placed on this property to my knowledge to date.

I understand that any Improvement Permit issued on the above property is valid for five (5) years from the issuance date and is subject to revocation if the above described site plans or intended use changes.

26-04 DATE _____ SIGNATURE OF OWNER/AUTHORIZED AGENT

IREDELL COUNTY HEALTH DEPARTMENT

STATESVILLE 704-878-5305 313.00 fa:9 MOORESVILLE 704-664-5281

IMPROVEMENT PERMIT / AUTHORIZATION TO CONSTRUCT / OPERATION PERMIT / EXISTING SYSTEM INSPECTION

PERMIT# 07-P-02-04 PIN# ~~4730488453~~ 4730-58-5303 DATE June 14, 04

OWNER OR CONTRACTOR Cecil Stamey LLC PHONE: Business _____ Home _____

ADDRESS 108 Westfield Ctd, Mooresville, N.C. 28115

LOCATION State Park Rd TR into Meadow Glen TR 1st Street TR Scotch Irish ON Right near end

SUBDIVISION Meadow Glen BLOCK / SECTION _____ LOT 133 LOT AREA .359 ac SITE CLASS. PS DESIGN FLOW 360 gpd L.T.A.R. .3 initial system

Septic Tank: 1000 Gallons; STB _____ Date _____

Pump Tank: 1000 Gallons; PT _____ Date _____

Pump Make: _____ Model _____ Serial No. _____

Nitrification Field: No Fields 1 Square Feet 400 Linear Feet 200

No Lines 3 Trench Width 24" min 60c Max Trench Bottom Depth 36" Gravel Depth NA

☑ New System ☐ Repair System Type: I, II, III, (IV), V, VI

System Description: LP PPBPS

Repair System Description: LP PPBPS

Maintenance Agreement Required: ☑ Yes ☐ No

☑ House/Mod. Home No. Bedrooms 3

☐ Mobile Home No. Bathrooms 2

☐ Business No. Employees ____

☐ Other _____

☐ Slab ☐ Crawl Space ☐ Basement w/plumbing ☑ Basement wo/plumbing


Water Supply: ☐ Individual ☑ Public ☐ Community

Comments:/Conditions: In Line filter Required in pump tank, 46 panels total; one 3/16" hole per panel; 3' design pressure head, 3¼ gal/min @ 30 TDH

Comments:/Conditions:

1"=50'

INITIAL SITE SKETCH



AS BUILT SKETCH

REVOKED

Permit can be suspended or revoked if any false information is supplied toward securing the permit/any unauthorized changes are made to the site/any unauthorized changes are made in the installation of the system. Improvement Permit with plat valid without expiration. Improvement Permit with site plan valid for sixty months. Authorization to Construct is valid for a period equal to that of Improvement Permit – not to exceed sixty months.

Signed: _____ date 6/8/04

Improvement Permit by: _____ date 6-14-04


Authorization to Construct by: _____ date 6-14-04

Installed by: _____

Operation Permit by: _____ date _____

Existing System Inspection by: _____ date _____

HEALTH DEPT. COPY: WHITE OWNER COPY (FINAL): YELLOW OWNER COPY (INITIAL): PINK


157.74
#4 REBAR
LOT 131-A
9,307 sq. ft.
0.21 acres
200.14
TOTAL)
15.00
23.17
C2
285.27'
S 24°47'06" E
423.88' (TOTAL)
SCOTCH IRISH LANE
(PAVED)
15' SEPTIC ESMT. FOR LOT 131 & 132
L6
L5
N 24°46'30" W
157.17'
#4 REBAR
N38°17'48"W
200.17
L14
C8
L15
15' SEPTIC ESMT.
L13
#4 REBAR
L3
#4 REBAR
138.61'
L8
C5
L9
S 24°47'54" E
66.54'
L10
L4
(TIE-ONLY)
C1
C6
RAILROAD SPIKE
C4
#4 REBAR
40' SETBACK
135
LOT 134
15' SETBACK
15' SETBACK
TYPICAL SETBACK LINES
25' SETBACK
N51°42'10"E
157.96
LOT 133
N 51°42'22" E
144.01'
20' UTILITY EASEMENT
LOT 132
0.34 AC.
C3
CB
12" PVC
C7
LOT 131
0.35 AC.
S 55°24'39" W
123.40'
L2 TOT.
#4 REBAR
#4 REBAR
#4 REBAR
5"W
N38°17'45"W
64.30
N41°33'58"W
35.88
#4 REBAR
N41°33'58"W
101.95
152.55'
74.41'
L1
N 41°31'22" W
226.96' (TOTAL)
LOT 124
LOT 125
LOT 126
LOT 127
LOT 128

Doc ID: 009943040005 Type: CRP
Recorded: 03/31/2006 at 10:27:10 AM
Fee Amt: $26.00 Page 1 of 5
Excise Tax: $0.00
Iredell County, NC
Brenda D. Bell Register of Deeds
BK 1735 PG 238-242

Hold for: Russ West
Prepared by: Russ West

5

NORTH CAROLINA

IREDELL COUNTY

UTILITY AND SEPTIC LINE EASEMENT

This UTILITY AND SEPTIC EASEMENT is made and entered into this the 27th day of March, 2006 by and between Cecil Stamey Inc and Grayson O. Stamey Jr. and Edith L. Stamey;

WITNESSETH:

1. WHEREAS, Cecil Stamey Inc is the owner of Lot 132 of Meadow Glen Subdivision, Phase 4, as shown on plat thereof recorded in Plat Book 37 at page 83 in the Iredell County Public Registry; and

2. WHEREAS, WHEREAS, Grayson O. Stamey, Jr. and Edith L. Stamey are the owners of Lot 133 of Meadow Glen Subdivision, Phase 4, as shown on plat thereof recorded in Plat Book 37 at page 83 in the Iredell County Public Registry; and

3. WHEREAS, Cecil Stamey Inc and Grayson O. Stamey Jr. and Edith L. Stamey deem it necessary and have agreed to convey a 15 foot septic easement across the front boundary (adjacent to Scotch Irish Lane) of Lots 132 and 133 of Meadow Glen Subdivision Phase 4, and

4. WHEREAS, Cecil Stamey Inc and Grayson O. Stamey Jr. and Edith L. Stamey deem it necessary and have agreed to convey a 20 foot utility easement along the common boundary line of Lot 132 and Lot 133 of Meadow Glen Subdivision Phase 4.

NOW, THEREFORE, BE IT RESOLVED:

1. That Cecil Stamey Inc and Grayson O. Stamey Jr. and Edith L. Stamey do hereby grant and convey a permanent and appurtenant 15 foot septic easement across the front boundary (adjacent to Scotch Irish Lane) of Lots 132 and 133 of Meadow Glen Subdivision Phase 4, as shown in Exhibit A attached, and

2. That Cecil Stamey Inc. and Grayson O. Stamey Jr. and Edith L. Stamey do hereby grant and convey a permanent and appurtenant 20 foot utility easement along the common boundary of Lots 132 and 133 of Meadow Glen Subdivision Phase 4, as shown in Exhibit A attached, and

3. That these easements shall be permanent and appurtenant and shall follow the land, and

4. That this instrument further grants and conveys rights of ingress and egress over and upon Lots 132 and 133 of Meadow Glen Subdivision Phase 4 for purposes of septic system installation, operation, maintenance, monitoring, and repairs along and for the benefit of the easements established herein.

Grayson O Stamey V

Cecil Stamey Inc.

Grayson O. Stamey

Grayson O. Stamey Jr.

Edith L Stamey

Edith L. Stamey

NORTH CAROLINA

COUNTY OF IREDELL

I, Cathy B. Sonneville Notary Public of the aforesaid County and State, do hereby certify that Grayson O. Stamey, Jr. personally appeared before me this day and acknowledged the due execution of the foregoing instrument.

This the 30th day of March, 2006.

Cathy B. Sonneville
Notary Public

My commission expires: 12/11/2010.

(SEAL)

CATHY B. SONNEVILLE NOTARY PUBLIC My Comm. Exp. 12-11-2010 IREDELL COUNTY, NC

NORTH CAROLINA

COUNTY OF IREDELL

I, Edith L. Stamey Notary Public of the aforesaid County and State, do hereby certify that Edith L. Stamey personally appeared before me this day and acknowledged the due execution of the foregoing instrument.

This the 30th day of March, 2006.

Edith L. Stamey
Notary Public

My commission expires: 12/11/2010.

(SEAL)

CATHY B. SONNEVILLE NOTARY PUBLIC My Comm. Exp. 12-11-2010 IREDELL COUNTY, NC

STATE OF NORTH CAROLINA

COUNTY OF IREDELL

I Cathy B. Sonneville, a Notary Public of the said County and State, do hereby certify that Grayson O. Stamey, Jr. personally appeared before me this day and being by me duly sworn, acknowledged that he is President of Cecil Stamey, Inc., a North Carolina corporation, and that by authority duly given and as the act of the corporation, he signed the foregoing instrument in his capacity as President of said Corporation, for and on behalf of the Corporation.

Witness my hand and official stamp or seal this the 30th day of March, 2006.

Cathy B. Sonneville
Notary Public

My Commission Expires: 12/11/2010

CATHY B. SONNEVILLE
NOTARY PUBLIC
My Comm. Exp.
12-11-2010
IREDELL COUNTY, NC


#153

IREDELL COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH DIVISION
Application For Improvement Permit
Site Plan Form

INSTRUCTIONS TO APPLICANT: (Items in Parentheses are to be performed by DEVELOPERS ONLY)


All property corners must be staked and flagged with dimensions matching those shown on an approved final (preliminary) plat (**and** proposed house dimensions must be staked and flagged) before the Iredell County Health Department can begin review work on this proposed site. An application for an Improvement Permit is considered complete **only** when this site plan form is completed, signed, and attached to the application form.

As Close To Scale As Is Possible: 1. Draw in the proposed lot showing **all** proposed lot dimensions and orientation to proposed streets or roads. 2. Draw in the proposed structure showing dimensions and distances to property lines (include decks, walkways, etc.). E. Draw in the proposed driveway location. 4. Draw in all wells, both existing and proposed, including those on adjacent property (if known). 5. Draw in any other structure ie. sheds, outbuildings, pools, etc. which will occupy space on the proposed lot.



I hereby convenant that the above representation is correct to the best of my knowledge and ability.

2-6-04 Date _____ SIGNATURE OF OWNER/AUTHORIZED AGENT


COMMON OPEN SPACE 0.5188 ACRES
350.70'
428.88'
285.32'
41.25'
157.24'
IRISH LANE
50' R/W
only 75 area within 60'± of street RW
* Very slim chance for pool/pond in front
looks like a good area
w/ Lot 132
w/side load garage
100.00'
40'
15'
49'9"
37'2"
156
0.3673 ACRES
160.00'
25'
100.00'
49'7"
41'6"
135
0.3673 ACRES
47'10"
28'8"
134
0.3669 ACRES
53.17'
29.46'
20.03'
37'6"
34'0"
133
0.3592 ACRES
157.97'
144.05'
66.50'
30.77'
18'
19'
51'2"
32'7"
132
82.35'
0.3444 ACRES
52.56'
103.93'
105.00'
49.23'
35.88'
18.07'
81.45'
102.00'
25'
123
0.3616 ACRES
150.00'
124
0.3616 ACRES
125
0.3470
126
Prop. 2113644 11

FRANK BETZ ASSOCIATES INC


HOMEPLANS *Designed for Today's Market.*

CHESDIN



1st Floor	637 sq. ft.
2nd Floor	730 sq. ft.
Total	1367 sq. ft.
Basement	587 sq. ft.

Overall Dimensions: 37'-6" x 34'-0"





Floorplans and Elevations are subject to change. Floorplan dimensions are approximate. Consult working drawings for actual dimensions and information. Elevations are artists' conceptions.

Right side Load garage o

Acknowledgement Of Plans Submittal ONLY!

Date 6-14-04

Date

PAID
FEB 10 2004
TOWN OF TROUTMAN

TOWN OF TROUTMAN
ZONING CLEARANCE APPLICATION
PERK TEST ONLY

Change of Principal Use _____
New or Enlarged Principal Use _____
New or Enlarged Accessory Structure _____

PERMIT 07 ***-p-*** 02-04 ***DATE OF APPLICATION*** February 9, 2004

APPLICANT'S NAME Cecil Stamey, LLC
APPLICANT'S MAILING ADDRESS 108 Westfield Center
Mooresville, North Carolina 28115

DAY TIME PHONE # (704) 932-6195

PROPERTY LOCATION: 111 Scotch Irish Lane, Meadow Glen Subdivision Lot #133

TAX MAP OR PARCEL IDENTIFICATION NUMBER (PIN): 4730488453

EXISTING ZONING: R-20 ***IN A SPECIAL FLOOD HAZARD AREA?*** ***Yes*** ____ ***No*** X

LOT DIMENSIONS: ***Length*** 157' ***Area*** .3592 Ac.
(Fill in all four blanks) ***Width*** 103' ***Street Frontage*** 102'

TYPE OF BUILDING PROPOSED AND/OR PROPOSED USE: Single Family Dwelling

PROPERTY OWNER'S NAME: C & S Associates, LLC

PROPERTY OWNER'S MAILING ADDRESS 108 Westfield Plaza, Mooresville, N. C. 28115

RELATIONSHIP OF APPLICANTS TO PROPERTY OWNER Same

IF ACCESSORY STRUCTURE, CHECK PROPOSED YARD LOCATION

Front: _____ ***Right Side:*** _____
Rear: _____ ***Left Side:*** _____

STRUCTURE REQUIREMENT *(Note: A separate application must be completed for each structure)*

(Set Backs)	***Required***	***Proposed***
Lot Area		
Side Yard—Left		
Side Yard—Right		
Front Setback(from road R/W)		
Building Height		
Lot Width at Building Line		
Rear Yard Setback		

****Additional ten feet (10') required on all side yards which abut a public or private street***

Comments: **PERK TEST ONLY!!!!**

133

Zoning Clearance Application
Page 2

ATTACHMENTS

In order to be considered complete, the following must accompany each application:

1. A fee (in cash or a check made payable to the Town of Troutman) in the amount of $25.00 shall be submitted to the Zoning Administrator.
2. A scaled dimensional drawing which shows (a) the exact shape, dimensions and location of the lot to be built upon, and (b) the exact shape, dimensions, use and location of existing structures on the lot. Upon this survey or drawing shall be sketched the following: (a) the exact shape, dimensions and area of the structure(s) to be placed upon the lot; (b) all setback lines on the lot once the proposed structure is completed; and (c) any other information that may be needed to insure that the proposed structure is in compliance with all applicable provisions of the Ordinance

CERTIFICATION

1. I hereby certify that all of the information provided for this application is, to the best of my knowledge, accurate and complete.

D Story
Signature of Applicant

Date: 2-9-04

2. I, D Story, Owner of property 4730488453 (list PIN number) in Troutman, North Carolina, do hereby authorize D Story (Applicant's Name) to submit this zoning permit application to the Zoning Administrator on my behalf.

D Story
Signature of Property Owner

Date: 2-9-04

3. To the best of my knowledge, this application is accepted and deemed complete.

Donald E. Duncan, Jr.
Signature of Zoning Administrator

Date: 2/9/04

(THE FOLLOWING SHALL BE FILLED OUT BY THE ZONING ADMINISTRATOR)

Based on the information hereby furnished to me and my knowledge of the Troutman Zoning Ordinance, I hereby: X **APPROVE** ____ **DISAPPROVE** this Zoning Permit.

COMMENTS: _____

Donald E. Duncan, Jr.
Zoning Administrator

Date: 2/9/04

THIS PERMIT EXPIRES SIX (6) MONTHS FROM THE ISSUE DATE.